

THE CORPORATION OF THE TOWNSHIP OF NORTH STORMONT REQUEST FOR QUOTATION

FOR

FORMER BERWICK SCHOOL - CONVERSION TO MUNICIPAL OFFICE 57 COCKBURN STREET, BERWICK, ON K0C 1G0

CONTRACT NO. RFQ-Administration-HVAC-Mechanical-04-2024

EEG FILE NO. 11,200

The Tenderer is advised that the following **CHECK LIST** is provided to assist in the completion of an accurate and acceptable Tender Form. While every effort has been made to include all information necessary, this **CHECK LIST** may not be complete, therefore the Tenderer is reminded to check all the requirements outlined in Section A, General Special Provisions, prior to delivery of the completed Tender Form.

TENDERER'S CHECK LIST

- Tenderer's name and address (page 2) completed
- Addenda numbers inserted in page 4 (as applicable)
- All tender items bid
- Unit price(s) inserted
- Mathematical extension(s) complete with total(s)
- Mathematical summation complete with TOTAL TENDER AMOUNT
- TOTAL TENDER AMOUNT BID indicated on page 5
- List of Sub-contractors provided
- Erasures, over-writing or strike-outs initialled by person signing on behalf of the Tenderer
- Tender Form dated, signed and witnessed on last page
- Bid Bond Included.
- Agreement to Bond.
- Deliver Tender to Township of North Stormont, 15 Union Street, Berwick, ON K0C 1G0, **mailing address** Township of North Stormont, P.O. Box 40, Finch, ON K0C 1K0 on Friday, April 12th, 2024 before 2:00 o'clock, p.m., (Local Time).
- During the preparation of tenders, all site visits are to be submitted in writing. Send all visit requests to Mr. Andre Brisson, North Stormont Township, by e-mail to abrisson@northstormont.ca no later than Thursday March 28th, 2024.
- During the preparation of tenders, all queries are to be submitted in writing. Send all written questions to Mr. B. Campbell, P.Eng. by e-mail to <u>bcampbell@easteng.com</u> Last day for queries is Thursday, March 28th, 2024.

THE CORPORATION OF THE TOWNSHIP OF NORTH STORMONT

FORMER BERWICK SCHOOL - CONVERSION TO MUNICIPAL OFFICE

CONTRACT NO. RFQ-Administration-HVAC-Mechanical-04-2024

TABLE OF CONTENTS

No. of Pages

10

Tender Form

SECTIONS

A:	General Special Provisions	7
B:	Item Special Provision - N/A	1
C:	Standard Specifications	1
D:	General Conditions of Contract (CCDC 2, 2020)	1
E:	Standard Drawings – N/A	1
F:	Soils Report - N/A	1
G:	Contract Drawings	1
H:	Shop Drawings -N/A	1
Co	ntractor's Schedule of Work	1

Division 1 - GENERAL REQUIREMENTS

Section 011100	-	Summary of Work
Section 011400	-	Work Restrictions
Section 012900	-	Payment Procedures
Section 013300	-	Submittal Procedure
Section 014500	-	Quality Control
Section 015100	-	Temporary Utilities
Section 015200	-	Construction Facilities
Section 015600	-	Temporary Barriers and Enclosures
Section 016100	-	Basic Product Requirements
Section 017050	-	Health and Safety
Section 017100	-	Examination and Preparation
Section 017400	-	Cleaning
Section 017700	-	Closeout Procedures
Section 018200	-	Demonstration and Training
Section 020000	-	Site Work

TENDER FORM

THE CORPORATION OF THE TOWNSHIP OF NORTH STORMONT

CONTRACT FOR

FORMER BERWICK SCHOOL - CONVERSION TO MUNICIPAL OFFICE

CONTRACT NO. RFQ-Administration-HVAC-Mechanical-04-2024

The Corporation of the Township of North Stormont 57 Cockburn Street Berwick, ON K0C 1G0

TENDER FOR:FORMER BERWICK SCHOOL
CONVERSION TO MUNICIPAL OFFICE

CONTRACT NO.: RFQ-Administration-HVAC-Mechanical-04-2024

NAME OF TENDERER (Firm or Individual)

ADDRESS OF TENDERER

(Telephone Number)

NAME OF PERSON SIGNING FOR TENDERER

OFFICE OF PERSON SIGNING FOR TENDERER

NOTE: If the Tender is submitted by or on behalf of any Corporation, it must be signed in the name of such Corporation by some duly authorized officer or agent thereof. The said officer or agent shall subscribe his own name and office and affix the seal of the Corporation thereto. Sealed Tenders, duly completed on the loosely bound Tender Form, complete with attached statements and information requested in the Tender Form, will be received as follows:

Tender for: The Corporation of the Township of North Stormont 57 Cockburn Street Berwick, ON K0C 1G0 Contract No. **RFQ-Administration-HVAC-Mechanical-04-2024**

TENDERS TO BE RECEIVED BY:

Township of North Stormont 15 Union Street, Berwick, ON K0C 1G0 Mailing Address P.O. Box 40 Finch, ON K0C 1K0

BEFORE: <u>2:00 o'clock, p.m. (local time) on Friday, April 12th, 2024</u>

Deposit Required with Tender: as specified in General Special Provisions

Time for Completion of Work and Delivery of Materials Under This Contract:

.1	Start Date of project:	Monday, May 6 th , 2024
.3	Total project to be completed by:	Friday, November 1 st , 2024

The Township reserves the right to reject any Tender if it is deemed advisable to do so, and the lowest or any tender will not necessarily be accepted.

The Corporation of the Township of North Stormont 57 Cockburn Street Berwick, ON K0C 1G0

Attention:

The Tenderer has carefully examined and understands and accepts the Provisions, Specifications, Conditions and Drawings referred to in the Schedule of Provisions, Specifications, Conditions and Drawings and Addenda Nos. _____ to ____* attached hereto as part of this Tender, and has carefully examined the site, including the nature of the utilities and location of the work to be done under this Contract and, for the prices set forth in this Tender, hereby offers to furnish all labour, materials, machinery, tools, apparatus and other means of construction necessary to complete the work in strict accordance with the Provisions, Specifications, Conditions and Drawings referred to in the said Schedule.

Notification of acceptance and delivery of the Form of Agreement shall be made by the Township by prepaid and registered post, addressed to the Tenderer at the address contained in the Tender and, upon such notification of acceptance, the Tenderer shall complete the form of Agreement between the parties and execute the Contract and furnish necessary proof of insurance, within 14 days of mailing of said notification to the Tenderer.

Attached to this Tender is a Bid Bond in the amount required by the General Special Provisions and made payable to: The Township of North Stormont. If the Tenderer fails to file with the Township the Form of Agreement duly executed, together with proof of insurance and proof of Workplace Safety and Insurance Board coverage, all as specified.

* The Tenderer will insert the numbers of the Addenda received by him/her during the tendering period and taken into account by him/her in his/her Tender.

In accordance with the first paragraph of this Tender the Contractor hereby offers to complete the work specified in the Contract for the following prices:

DESCRIPTION	CONTRACTOR'S TOTAL BID IN FIGURES
CONSTRUCTION	
Former Berwick School Conversion to New Municipal Office	\$
TOTAL BID (HST NOT INCLUDED)	\$

EXTRA WORK

The Contractor further agrees that all extra work not provided for in the bid shall be based on actual cost of labour or on negotiated prices.

The Contractor further agrees to provide credit for deletions of work based on the actual cost used to determine the total tender bid without any provisions for profit and overhead.

HOURLY RATES

The following labour rates shall be used for additions and deletions to the contract.

Apprentice/Hr.	
Plumber/Hr.	
Electrician/Hr.	
Labourer/Hr.	
Carpenter/Hr.	

Note: Labour rates are to be calculated based on hourly rates paid plus fringe benefits.

CERTIFICATION RESPECTING COMPLETION OF WORK

The Township requires completion of the work as follows:

.1 Total project to be complete by Friday, November 1, 2024.

Please indicate whether you can guarantee completion of the work in accordance with the aforesaid dates.

Yes _____ No _____

If the answer is "No" please insert the date of completion that you can guarantee and for which the Liquidated Damages Provisions of this Contract would apply.

a) Final completion date of the work _____, 2024.

The Township reserves the right to award a contract based on both tender bid and dates of completion whichever is in the Township's best interests.

The following form or an acceptable alternative must be completed and attached to the tender submitted.

AGREEMENT TO BOND

Bond No.

We, the undersigned, hereby agree to become bound as Surety for

(Name of Tenderer)

in a bond totaling One Hundred Percent (100%) of the Contract Amount and conforming to the Instruments of the Contract attached hereto, for the full and due performance of the work shown as described herein if the Tender for Contract No. RFQ-Administration-HVAC-Mechanical-04-2024 is accepted by the Township.

It is a Condition of this Agreement, that, if the above-mentioned Tender is accepted, application for the required Performance Bond shall be made to the undersigned within ten (10) days of acceptance of the Tender related thereto, otherwise this Agreement shall be null and void.

Dated this ______ day of ______, 2024.

Name of Bonding Company

(Company Seal)

Signature of Authorized Person Signing for Bonding Company

Position

SCHEDULE OF PROVISIONS, SPECIFICATIONS, CONDITIONS AND DRAWINGS

The work specified in the Contract will be performed in strict accordance with the following:

- SECTION A <u>General Special Provisions</u>
- SECTION B Item Special Provisions N/A
- SECTION C <u>Standard Specifications</u>
- SECTION D <u>General Conditions of Contract</u> (CCDC 2, 2020)
- SECTION E <u>Standard Drawings</u>
- SECTION F Soils Report N/A
- SECTION G <u>Contract Drawings</u>
- SECTION H Shop Drawings

The Tenderer, by this Tender, offers to complete this Contract in accordance with the terms and conditions contained herein.

Dated at	this	day of	<u>,</u> 2024.
Witness			
	_	Signature of Authorized Person Signing for Tenderer	

Position

This is the 10th and last page of 10 pages of the Tender Form to be submitted.

SECTION A

GENERAL SPECIAL PROVISIONS

1. <u>TENDER REQUIREMENTS</u>

a) The correct Tender Form, as supplied by the Township, for the Contract being bid on, must be used and must be delivered to:

> Township of North Stormont 15 Union Street, Berwick, ON K0C 1G0 Mailing Address P.O. Box 40 Finch, ON K0C 1K0

Attention: Craig Calder

before: 2:00 o'clock, p.m., (Local Time), Friday, April 12th, 2024.

Bids received after closing time will not be considered.

- b) The entire work is to be awarded to (1) one Contractor and therefore <u>ALL ITEMS</u> must be included in the bid price on the tender form.
- c) When so required by the Township, the Contractor shall produce evidence as to his qualifications and previous experience in the types of work contemplated by this Contract.
- d) All unit prices must be clearly indicated. Erasures, over-writing or strike-outs must be initialled by the person signing on behalf of the Contractor.
- e) The total bid must not be restricted by a statement added to the Tender Form, or a covering letter, or alterations to the Tender Form provided by the Township. Adjustments by e-mail or letter to a Tender already submitted will not be considered. A bidder wishing to make any adjustments to a Tender must withdraw the Tender and/or supersede it with a later submission.
- f) The Tender Form must be signed and witnessed in the spaces provided on the form, with the signature of the bidder or of a responsible official of the organization bidding.
- g) Each amount in the Tender shall be a reasonable price for each item. Unbalanced Tenders will not be considered. The Consultant shall be the sole judge of such matters, and should any Tender be considered, to be unbalanced, it may be rejected.

- h) The Tender must be accompanied by a 10% Bid Bond, or a certified cheque made payable to "Township of North Stormont."
- (i) Each amount in the Tender shall be a reasonable price for each item. Unbalanced Tenders will not be considered. The Township Engineer shall be the sole judge of such matters and should any Tender be considered to be unbalanced it may be rejected.
- (j) The Tender Deposits of the three (3) lowest acceptable bidders shall be retained until the successful bidder has executed the Contract documents. All remaining Tender Deposits shall be returned to the respective bidders on the next business day following the Tender opening.

The Tender Deposit of the successful bidder will be returned when he has fully complied with the conditions outlined in the Contract documents.

2. <u>PERFORMANCE BOND</u>

A Performance Bond is not required for this project. The deposit cheque shall be retained as surety until substantial completion of the project.

3. <u>EXECUTION OF CONTRACT</u>

Tenders shall be open for acceptance for a period of 60 calendar days after closing date. After this time, the Tender may only be accepted with the consent of the successful bidder.

Failure by the selected bidder to meet the Contract criteria will entitle the Township to rescind the acceptance of the Contract and to retain the Tender Deposit as compensation for damages sustained due to the successful bidder's default. The Township may then award the Contract to one of the other bidders or take other action as the Township may choose.

4. <u>LIABILITY INSURANCE</u>

Sub-section GC 11.1.1.1 of General Conditions of Contract, is hereby amended by the following provisions:

The Certificate of Insurance required under this Section shall be submitted to the Consultant as soon as practical after notification of acceptance of the Tender. The liability insurance coverage shall specifically include coverage to the limit of not less than five million dollars (\$5,000,000.00), exclusive of interest and cost, in respect of any one accident.

Sub-section GC11.1.1.2, General Conditions of Contract, is hereby amended by the following:

The automobile liability insurance coverage shall include coverage of not less than five million dollars (\$5,000,000.00), inclusive per occurrence.

Contractor's Pollution Liability

Sub-section GC11.1.1.2, General Conditions of Contract, is hereby amended by the following:

The Contractor shall carry a Contractor's Pollution Liability Policy for a limit of not less than \$5,000,000. Coverage shall include bodily injury, property damage, clean-up and remediation costs. If such insurance is issued on a claims made basis, such insurance shall contain a 24 months extended reporting period or be maintained for a period of two years subsequent to conclusion of services provided under this agreement.

Crane Operators/Hook Liability

Sub-section GC11.1.1.2, General Conditions of Contract, is hereby amended by the following:

If booms or cranes are involved in moving any materials or installing equipment (HVAC), the contractor will require Hook or Crane Operators Liability. The Limit of this coverage should equal the cost of the most expensive piece to be moved or installed.

The Certificate of Insurance shall name the following as additional insured:

- a) Township of North Stormont
- b) Eastern Engineering Group Inc.

5. <u>OCCUPATIONAL HEALTH AND SAFETY</u>

The Contractor's attention is drawn to Sub-section GC3.6, General Conditions of Contract.

In order to avoid any misunderstanding as to the nature of the work to be performed herein, the Contractor, by executing this Contract, acknowledges that he is the Constructor within the meaning of the Occupational Health and Safety Act and Regulation.

6. <u>SCOPE OF WORK</u>

Work on this contract consists of the supply of all materials, equipment, and labour to construct the Former Berwick School Conversion to Municipal Office and complete all site works as prescribed in the Eastern Engineering Group Inc. Drawings File No. 11,200.

The contractor will not be responsible for civil/sites works beyond the limit of 1m outside the building. All services and utilities extending beyond 1m shall be stubbed and will be tied into the building system by the site works contractor.

General

The contractor shall complete all work in accordance with the permit drawings and provisions made by the building department having jurisdiction and consulting engineers for the project. All work shall be performed to good practice and craftsmanship.

7. <u>CONTRACTOR'S SCHEDULE OF WORK</u>

Forthwith upon acceptance of this Contract, the Contractor shall provide a "Contractor's Schedule of Work" to the Consultant. The Contractor must prepare and submit his Schedule to the Consultant within ten (10) calendar days of Contract acceptance and prior to start of construction.

8. <u>PROGRESSION OF WORK AND COMPLETION TIME</u>

Time shall be of the essence of this Contract.

The Contractor shall diligently prosecute his work on this Contract to completion. The Contractor shall schedule the work for progression of same in a continuous and orderly manner to prevent the least amount of delay in completing the total works. The Contractor shall start work on this Contract within <u>15</u> days from receipt of written notice from the Township to commence and shall work continuously to the completion of the Contract.

The total work shall be completed by the Contractor by Friday, November 1, 2024.

If the time limit specified above is not sufficient to permit completion of the work by the Contractor working a normal number of hours each day or week on a single daylight shift basis, it is expected that additional and/or augmented daylight and night shifts will be required throughout the life of the Contract to the extent deemed necessary by the Contractor to insure that the work will be completed within the time limit specified. Any additional costs occasioned by compliance with these provisions will be considered to be

included in the prices bid for the various items of work and no additional compensation will be allowed, therefore.

Working time shall be charged until the date of acceptance of the work by the Township, at which time all work required in the Contract, including all final clean-up and trimming, shall be completed.

1. <u>PAYMENT</u>:

Payment to be made based on monthly progress billing, less a 10% holdback for substantial completion. All progress billing must be balanced and approved by the contract administrator prior to releasing payment. A copy of the contractor's valid WSIB and certificate of insurance shall be accompanied with each billing statement.

10. SALES TAX

a) <u>Harmonized Sales Tax (HST)</u>

The Harmonized Sales Tax (HST) is not to be considered an applicable tax for the purposes of this Contract. The Tenderer shall not include any amount in his bid prices for the said HST. The Township is subject to payment of the Harmonized Sales Tax, therefore the HST will be shown on each payment certificate and will be paid to the Contractor in addition to the amount certified for payment and will therefore not affect the Contract prices.

c) <u>Changes To Government Taxes</u>

Where a change in Canadian federal or provincial taxes occurs after the tender closing date for this Contract, and this change could not have been anticipated at the time of bidding, the Township will increase or decrease contract payments to account for the exact amount of tax change involved.

Claims for compensation for additional tax cost shall be submitted by the Contractor to the Consultant. Such claims for additional tax costs shall be submitted not later than 30 days after the date of acceptance of the work.

Where the Contractor benefits from a change in Canadian federal or provincial taxes, the Contractor shall submit to the Consultant a statement of such benefits. This statement shall be submitted no later than 30 days after the date of acceptance of the work.

The Consultant reserves the right to make deductions from regular progress payments to compensate for the estimated benefit from decreased tax costs. Such deductions will be set-off from Contract payments pending receipt of the statement itemizing the benefits which have resulted from a decrease in tax costs, at which time the final payment adjustment will be determined.

11. <u>EMPLOYMENT</u>

The Contractor and any Sub-contractor of the Contractor will, irrespective of the construction to be carried out under this Contract:

- a) Employ only residents of Canada, and
- b) In employing persons, refrain from discrimination against any person by reason of race, colour, religious views, or political affiliations.
- c) Give preference to local labour if it is necessary to augment his regular forces.

12. <u>USE OF SUB-CONTRACTORS</u>

The Township has the right to reject any of the Sub-contractors so named. In this event the Contractor shall arrange to have the proposed work done by such other Sub-contractor as may be approved by the Township.

Should the Contractor cease operations, under no circumstances shall Sub-contractors be allowed to continue the work on the site unless an authorized representative of the Contractor is present on the site at all times. The Contractor shall notify the Consultant, in writing, of the names and positions of the person or persons so representing the Contractor.

13. <u>DUST CONTROL</u>

The Contractor will be solely responsible for controlling dust nuisance resulting from his operations, within the work area.

Should the Contractor refuse or neglect to carry out proper dust control, the Consultant may authorize the work to be carried out by other persons, and the cost of such work shall be deducted from any payments to the Contractor.

14. <u>EMERGENCY MEASURES</u>

General Conditions of Contract is amended by the addition of the following.

Whenever the construction site is unattended by the general superintendent, the name, address and telephone number of a responsible official of the Contractor shall be given to the Consultant. This official shall be available at all times and have the necessary authority to mobilize workers and machinery and to take any action as directed by the Consultant in case emergency measures are required.

15. <u>SPILLS REPORTING</u>

Spills or discharges of pollutants or contaminants under the control of the Contractor, and spills or discharges of pollutants or contaminants that are a result of the Contractor's operations, that cause or are likely to cause adverse effects shall forthwith be reported to the Consultant. Such spills or discharges and their adverse effects shall be as defined in

the Environmental Protection Act.

All spills or discharges of liquid, other than accumulated rainwater, from luminaries, internally illuminated signs, lamps and liquid type transformers under the control of the Contractor, and all spills or discharges from this equipment that are a result of the Contractor's operations, shall, unless otherwise indicated in the Contract, be assumed to contain PCB's and shall forthwith be reported to the Consultant.

This reporting will not relieve the Contractor of his legislated responsibilities regarding such spills or discharges.

16. <u>SAFETY ON SITE</u>

The Contractor is solely responsible for safety on site.

Public access to the area of work shall be restricted by use of a construction fence with lock and key. All equipment and materials stored on site shall be retained within the protected area. A detour route will be mapped by the contractor and the routes shall be provided with clear signage which are clear and legible.

The selected detour route to be provided shall be required to have final approval from both the Operations Director for the Township of North Stormont and/or the Consulting Firm.

SECTION B

ITEM SPECIAL PROVISION

NOT APPLICABLE

SECTION C

STANDARD SPECIFICATIONS

1. <u>GENERAL</u>

The following Standard Specifications apply to and form part of this Contract:

ACI	- American Concrete Institute
AISC	- American Institute of Steel Construction
ANSI	- American National Standards Institute
ASTM	- American Society for Testing and Materials
CEC	- Canadian Electrical Code (published by CSA)
CEMA	- Canadian Electrical Manufacturer's Association
CGSB	- Canadian General Standards Board
CISC	- Canadian Institute of Steel Construction
CLA	- Canadian Lumberman's Association
CPCA	- Canadian Painting Contractor's Association
CPCI	- Canadian Prestressed Concrete Institute
CRCA	- Canadian Roofing Contractors Association
CSA	- Canadian Standards Association
FM	- Factory Mutual Engineering Corporation
IEEE	- Institute of Electrical and Electronic Engineers
IPCEA	- Insulated Power Cable Engineers Association
NAAMM	- National Association of Architectural Metal Manufacturers
NBC	- National Building Code
NEMA	- National Electrical Manufactures Association
OBC	- Ontario Building Code
TTMAC	- Terrazzo, Tile and Marble Association of Canada
ULC	- Underwriters' Laboratories of Canada

*Most current editions apply.

2. <u>SUPPLY OF MATERIALS</u>

All materials necessary for the proper completion of the work shall be supplied by the Contractor and the payment provided in the Contract shall be deemed to include full compensation for the supply of such materials, unless specifically stated otherwise.

EXCEPTION: Carpentry work materials will be provided by Township of North Stormont.

SECTION D

GENERAL CONDITIONS OF CONTRACT

GENERAL CONDITIONS OF THE STIPULATED PRICE CONTRACT

CCDC 2, 2020

(COPY IS AVAILABLE FOR VIEWING AT THE OFFICE OF EASTERN ENGINEERING GROUP INC.)

SECTION E

STANDARD DRAWINGS

NOT APPLICABLE

SECTION F

SOILS REPORT

NOT APPLICABLE

SECTION G

CONTRACT DRAWINGS

Drawing No. <u>Title</u>

<u>Structural</u>

S0	Construction Notes
S1	Demolition Plan – Proposed Plan
S2	Roof Framing Plan and Stage Construction Details
S3	Construction Details

Architectural

A000	Cover Page/Architectural Drawing List/Material Specs/OBC Matrix
A001	Site Plan
A100	Overall Floor Plan and Details
A101	Roof Plan – Demo and New Work
A200	Demo Plans
A300	New Floor Finish Plan & RCP
A301	Ceiling Details
A500	Interior Elevations
A600	Millwork Details
A601	Millwork Details
A700	Door Schedule
A701	Window and Room Finish Schedule
A702	Material Finish Board

Mechanical and Electrical

M001	Mechanical Notes and Legends
M002	Mechanical Schedules & Details
M100	Mechanical Plumbing Demolition
M101	Mechanical HVAC Demolition
M201	Mechanical Plumbing
M202	Mechanical HVAC
E001	Electrical Notes & Legends
E002	Electrical Schedules
E003	Electrical Details
E100	Electrical Main Floor Plan Demolition
E101	Electrical Power & Systems Roof Plan
E102	Electrical Lighting

Hazardous Building Materials Assessment

CONTRACTOR'S SCHEDULE OF WORK

DIVISION 1 – GENERAL REQUIREMENTS

SECTION H

SHOP DRAWINGS

NOT APPLICABLE

Part 1 General

.1

1.1 RELATED SECTIONS

All

1.2 WORK COVERED BY CONTRACT DOCUMENTS

.1 Work of this Contract comprises general construction of the Former Berwick School conversion to Municipal Office located in Berwick, ON.

1.3 CONTRACT METHOD

- .1 Construct Work under a single stipulated price contract, additional cost allowances may be issued upon contractor selection at the Owners discretion.
- .2 Employ suppliers and subcontractors authorized by the Owner for required work.
- .3 Relations and responsibilities between the Contractor and subcontractors authorized by the Owner are as defined in Conditions of Contract. Assigned Subcontractors must, in addition:
 - .1 Furnish to the Contractor, bonds covering faithful performance of subcontracted work and payment of obligations there under when the Contractor and subcontractors are required to furnish such bonds to the Owner.
 - .2 Purchase and maintain liability insurance to protect Contractor and subcontractors from claims for not less than limits of liability which the Contractor and subcontractors are required to provide to the Owner.

1.4 WORK BY OTHERS

- .1 Co-operate with other Contractors in carrying out their respective works and carry out instructions from the Consultant.
- .2 Co-ordinate work with that of other Contractors. If any part of work under this Contract depends for its proper execution or result upon work of another Contractor, report promptly to the Consultant, in writing, any defects which may interfere with proper execution of Work.
- .3 Work of Project which will be executed prior to completion of Work in this Contract, and which is specifically excluded from this Contract:
 - .1 Demolition of existing building.

1.5 CONTRACTOR USE OF PREMISES

- .1 Unrestricted use of site until substantial completion.
- .2 Limit use of premises for Work, storage, and access, to allow:
 - .1 Owner occupancy.
 - .2 Work by other contractors.
 - .3 Parking.

- .4 Daily operations.
- .3 Co-ordinate use of premises under direction of the Consultant and Owner.
- .4 Obtain and pay for use of additional storage or work areas needed for operations under this Contract.
- .5 Remove or alter existing work to prevent injury or damage to portions of existing work which remain.

1.6 OWNER OCCUPANCY

- .1 Owner will not occupy premises during entire construction period.
- .2 Co-operate with Owner in scheduling removals and storage of vehicles to minimize conflict with the Owner temporary storage solutions.

1.7 EXISTING SERVICES

- .1 Notify, the Consultant, Owner and utility companies of intended interruption of services and obtain required permission.
- .2 Where Work involves breaking into or connecting to existing services, give the Consultant a minimum 48 hour notice for necessary interruption of mechanical or electrical service throughout course of work. Minimize duration of interruptions. Carry out work at times as directed by governing authorities with minimum disturbance to owner tenant operations.
- .3 Provide alternative routes for operational and employee vehicular traffic.
- .4 Establish location and extent of service lines in area of work before starting Work. Notify the Consultant of the findings.
- .5 Submit schedule to and obtain approval from the Consultant and the Owner for any shutdown or closure of active service or facility including power and communications services. Adhere to approved schedule and provide notice to affected parties.
- .6 Provide temporary services when directed by the Consultant to maintain critical building and tenant systems.
- .7 Provide adequate bridging over trenches which cross sidewalks or roads to permit normal traffic.
- .8 Where unknown services are encountered, immediately advise the Consultant and confirm findings in writing.
- .9 Protect, relocate or maintain existing active services. When inactive services are encountered, cap off in manner approved by authorities having jurisdiction.
- .10 Record locations of maintained, re-routed and abandoned service lines.
- .11 Construct barriers in accordance with Section 015600 Temporary Barriers and Enclosures.

1.8 DOCUMENTS REQUIRED

- .1 Maintain at job site, one copy each document as follows:
 - .1 Contract Drawings.
 - .2 Specifications.
 - .3 Addenda.
 - .4 Reviewed Shop Drawings.
 - .5 List of Outstanding Shop Drawings.
 - .6 Change Orders.
 - .7 Other Modifications to Contract.
 - .8 Field Test Reports.
 - .9 Copy of Approved Work Schedule.
 - .10 Health and Safety Plan and Other Safety Related Documents. Other documents as specified.

END OF SECTION

Part 1 General

.1

1.1 RELATED SECTIONS

All.

1.2 ACCESS AND EGRESS

.1 Design, construct and maintain temporary "access to" and "egress from" work areas, including stairs, runways, ramps or ladders, and scaffolding; independent of finished surfaces and in accordance with relevant municipal, provincial and other regulations.

1.3 USE OF SITE AND FACILITIES

- .1 Execute work with least possible interference or disturbance to normal use of premises. Make arrangements with the Consultant and Owner to facilitate work as stated.
- .2 Maintain existing services to building and provide for personnel and vehicle access.
- .3 Where security is reduced by work provide temporary means to maintain security.
- .4 The Owner will not assign sanitary facilities for use by Contractor's personnel. The contractor shall provide sufficient temporary facilities on site.
- .5 Closures: protect work temporarily until permanent enclosures are completed.

1.4 ALTERATIONS, ADDITIONS OR REPAIRS TO EXISTING BUILDING

.1 Execute work with least possible interference or disturbance to building operations and normal use of premises. Arrange with the Consultant and Owner to facilitate execution of work.

1.5 EXISTING SERVICES

- .1 Notify, the Consultant, Owner and utility companies of intended interruption of services and obtain required permission.
- .2 Where Work involves breaking into or connecting to existing services, give the Consultant a minimum 48 hour of notice for necessary interruption of mechanical or electrical service throughout course of work. Keep duration of interruptions minimum. Carry out interruptions after normal working hours of occupants, preferably on weekends.
- .3 Provide for routes for vehicular traffic.
- .4 Construct barriers in accordance with Section 015600 Temporary Barriers and Enclosures.

1.6 SPECIAL REQUIREMENTS

- .1 Finishes in normally occupied areas shall be completed Monday to Friday outside hours of normal operation and on Saturdays, Sundays, and statutory holidays. Co-ordinate with Owner for hours of normal operation.
- .2 Carry out noise generating Work in accordance with the requirements of the Owner. Noise generating work shall be performed as to not disturb livestock on site.
- .3 Submit a short form schedule the Consultant and Owner with expected completion times of the various phases of work. This shall include site work, foundations, steel building erection, partition erection, finishes, mechanical and electrical and commissioning the building.
- .4 Ensure that Contractor personnel employed on site become familiar with and obey regulations including safety, fire, traffic, security regulations or facility requirements as specified by the owner.
- .5 Keep within limits of work and avenues of ingress and egress.
- .6 Ingress and egress of Contractor vehicles at site is limited to normal construction hours.
- .7 Deliver materials outside of peak traffic hours unless otherwise approved by the Consultant and/or Owner.

1.7 SECURITY CLEARANCES

- .1 Personnel employed on this project will be subject to security check. Obtain clearance, as instructed, for each individual who will require to enter premises.
- .2 Personnel will be checked daily at start of work shift and provided with pass which must be worn at all times. Pass must be returned at end of work shift and personnel checked out.

1.8 SECURITY ESCORT

- .1 Personnel employed on this project must be escorted when executing work in non-public areas during normal working hours. Personnel must be escorted in all areas after normal working hours.
- .2 Submit an escort request to the facility manager at least 5 days before service is needed. For requests submitted within time noted above, costs of security escort will be paid for by the Owner. Cost incurred by late request will be Contractor's responsibility.
- .3 Any escort request may be cancelled free of charge if notification of cancellation is given at least 8 hours before scheduled time of escort. Cost incurred by late request will be Contractor's responsibility.
- .4 Calculation of costs will be based on average hourly rate of security officer for minimum of 8 hours per day for late service request and of 4 hours for late cancellations.

Section 011400 WORK RESTRICTIONS Page 3

1.9 BUILDING SMOKING ENVIRONMENT

.1 Comply with smoking restrictions. Smoking is allowed only in areas designated on site and approved by the Owner.

END OF SECTION
1.1 SECTION INCLUDES

- .1 Applications for payments.
- .2 Substantial performance procedures.
- .3 Release of holdback procedures.
- .4 Schedule of values.

1.2 REFERENCES

- .1 Owner/Contractor Agreement.
- .2 Canadian Construction Documents Committee (CCDC).
 - .1 CCDC 2 2020, Stipulated Price Contract.

1.3 APPLICATIONS FOR PROGRESS PAYMENT

- .1 Refer to CCDC 2.
- .2 Make applications for payment on account monthly as Work progresses.
- .3 Date applications for payment last day of agreed monthly payment period and ensure amount claimed is for value, proportionate to amount of Contract, of Work performed and Products delivered to Place of Work at that date.
- .4 Submit to Consultant, at least 10 days before first application for payment. Schedule of values for parts of Work, aggregating total amount of Contract Price, so as to facilitate evaluation of applications for payment.

1.4 SCHEDULE OF VALUES

.1 Refer to CCDC 2.

1.5 **PROGRESS PAYMENT**

.1 Consultant will issue to Owner, no later than 10 days after receipt of an application for payment, certificate for payment in amount applied for or in such other amount as Consultant determines to be properly due. If Consultant amends application, Consultant will give notification in writing giving reasons for amendment.

1.6 SUBSTANTIAL PERFORMANCE OF WORK

.1 Refer to CCDC 2.

1.7 PAYMENT OF HOLDBACK UPON SUBSTANTIAL PERFORMANCE OF WORK

.1 Refer to CCDC 2.

1.8 PROGRESSIVE RELEASE OF HOLDBACK

.1 Refer to CCDC 2.

1.9 FINAL PAYMENT

- .1 Refer to CCDC 2, GC 5.7.
- Part 2 Products
- 2.1 NOT USED
 - .1 Not Used.

Part 3 Execution

3.1 NOT USED

.1 Not Used.

1.1 SECTION INCLUDES

- .1 Shop drawings and product data.
- .2 Samples.
- .3 Certificates and transcripts.

1.2 RELATED SECTIONS

- .1 Section 014500 Quality Control.
- .2 Section 017700 Closeout Procedures.

1.3 REFERENCES

- .1 Canadian Construction Documents Committee (CCDC)
 - .1 CCDC 2 2020, Stipulated Price Contract.

1.4 ADMINISTRATIVE

- .1 Submit to Consultant submittals listed for review. Submit with reasonable promptness and in orderly sequence so as to not cause delay in Work. Failure to submit in ample time is not considered sufficient reason for an extension of Contract Time and no claim for extension by reason of such default will be allowed.
- .2 Work affected by submittal shall not proceed until review is complete.
- .3 Present shop drawings, product data, samples and mock-ups in Imperial units.
- .4 Where items or information is not produced in Imperial units converted values are acceptable.

- .5 <u>Review submittals prior to submission to Consultant</u>. This review represents that necessary requirements have been determined and verified, or will be, and that each submittal has been checked and co-ordinated with requirements of Work and Contract Documents. Submittals not stamped, signed, dated and identified as to specific project will be returned without being examined and shall be considered rejected.
- .6 Notify Consultant, in writing at time of submission, identifying deviations from requirements of Contract Documents stating reasons for deviations.
- .7 Verify field measurements and affected adjacent Work are coordinated.
- .8 Contractor's responsibility for errors and omissions in submission is not relieved by Consultant's review of submittals.
- .9 Contractor's responsibility for deviations in submission from requirements of Contract Documents is not relieved by Consultant review.
- .10 Keep one reviewed copy of each submission on site.

1.5 SHOP DRAWINGS AND PRODUCT DATA

- .1 The term "shop drawings" means drawings, diagrams, illustrations, schedules, performance charts, brochures and other data which are to be provided by Contractor to illustrate details of a portion of Work.
- .2 Indicate materials, methods of construction and attachment or anchorage, erection diagrams, connections, explanatory notes and other information necessary for completion of Work. Where articles or equipment attach or connect to other articles or equipment, indicate that such items have been coordinated, regardless of Section under which adjacent items will be supplied and installed. Indicate cross references to design drawings and specifications.
- .3 Allow 10 days for Consultant's review of each submission.
- .4 Adjustments made on shop drawings by Consultant are not intended to change Contract Price. If adjustments affect value of Work, state such in writing to Consultant prior to proceeding with Work.
- .5 Make changes in shop drawings as Consultant may require, consistent with Contract Documents. When resubmitting, notify Consultant in writing of any revisions other than those requested.

- .6 Accompany submissions with transmittal letter, containing:
 - .1 Date.
 - .2 Project title and number.
 - .3 Contractor's name and address.
 - .4 Identification and quantity of each shop drawing, product data and sample.
 - .5 Other pertinent data.
- .7 Submissions shall include:
 - .1 Date and revision dates.
 - .2 Project title and number.
 - .3 Name and address of:
 - .1 Subcontractor.
 - .2 Supplier.
 - .3 Manufacturer.
 - .4 Contractor's stamp, signed by Contractor's authorized representative certifying approval of submissions, verification of field measurements and compliance with Contract Documents.
 - .5 Details of appropriate portions of Work as applicable:
 - .1 Fabrication.
 - .2 Layout, showing dimensions, including identified field dimensions, and clearances.
 - .3 Setting or erection details.
 - .4 Capacities.
 - .5 Performance characteristics.
 - .6 Standards.
 - .7 Operating weight.
 - .8 Wiring diagrams.
 - .9 Single line and schematic diagrams.
 - .10 Relationship to adjacent work.
- .8 After Consultant's review, distribute copies.
- .9 Submit 3 prints of shop drawings for each requirement requested in specification Sections and as consultant may reasonably request, in addition to a digital copy in PDF or JPG format.
- .10 Submit 3 copies of product data sheets or brochures for requirements requested in specification Sections and as requested by Consultant where shop drawings will

not be prepared due to standardized manufacture of product, in addition to a digital copy in PDF or JPG format.

- .11 Delete information not applicable to project.
- .12 Supplement standard information to provide details applicable to project.
- .13 If upon review by Consultant, no errors or omissions are discovered or if only minor corrections are made, copies will be returned and fabrication and installation of Work may proceed. If shop drawings are rejected, noted copy will be returned and resubmission of corrected shop drawings, through same procedure indicated above, must be performed before fabrication and installation of Work may proceed.

1.6 SAMPLES

- .1 Submit for review samples in triplicate as requested in respective specification Sections. Label samples with origin and intended use.
- .2 Deliver samples prepaid to Consultant's business address.
- .3 Notify Consultant in writing, at time of submission of deviations in samples from requirements of Contract Documents.
- .4 Where colour, pattern or texture is criterion, submit full range of samples.
- .5 Adjustments made on samples by Consultant are not intended to change Contract Price. If adjustments affect value of Work, state such in writing to Consultant prior to proceeding with Work.
- .6 Make changes in samples which Consultant may require, consistent with Contract Documents.
- .7 Reviewed and accepted samples will become standard of workmanship and material against which installed Work will be verified.

1.7 MOCK-UPS

.1 Erect mock-ups in accordance with 014500 - Quality Control.

- Part 2 Products
- 2.1 NOT USED
 - .1 Not Used.
- Part 3 Execution
- 3.1 NOT USED
 - .1 Not Used.

Section 014500 QUALITY CONTROL Page 1

Part 1 General

1.1 SECTION INCLUDES

- .1 Inspection and testing, administrative and enforcement requirements.
- .2 Tests and mix designs.
- .3 Mock-ups.
- .4 Mill tests.
- .5 Equipment and system adjust and balance.

1.2 RELATED SECTIONS

- .1 Section 013300 Submittal Procedures.
- .2 Section 017700 Closeout Procedures.

1.3 REFERENCES

- .1 Canadian Construction Documents Committee (CCDC)
 - .1 CCDC 2-20, Stipulated Price Contract.

1.4 INSPECTION

- .1 Allow Consultant access to Work. If part of Work is in preparation at locations other than Place of Work, allow access to such Work whenever it is in progress.
- .2 Give timely notice requesting inspection if Work is designated for special tests, inspections or approvals by Consultant instructions, or law of Place of Work.
- .3 If Contractor covers or permits to be covered Work that has been designated for special tests, inspections or approvals before such is made, uncover such Work, have inspections or tests satisfactorily completed and make good such Work.
- .4 Consultant may order any part of Work to be examined if Work is suspected to be not in accordance with Contract Documents. If, upon examination such work is found not in accordance with Contract Documents, correct such Work and pay cost of examination and correction.

1.5 INDEPENDENT INSPECTION AGENCIES

- .1 Independent Inspection/Testing Agencies to be engaged by Contractor for purpose of inspecting and/or testing for concrete work, compaction testing and material testing.
- .2 Provide equipment required for executing inspection and testing by appointed agencies.
- .3 Employment of inspection/testing agencies does not relax responsibility to perform Work in accordance with Contract Documents.

Section 014500 QUALITY CONTROL Page 2

.4 If defects are revealed during inspection and/or testing, agency will request additional inspection and/or testing to ascertain full degree of defect. Correct defect and irregularities as advised by Independent Inspection/Testing Agency.

1.6 ACCESS TO WORK

- .1 Allow inspection/testing agencies access to Work, off site manufacturing and fabrication plants.
- .2 Co-operate to provide reasonable facilities for such access.

1.7 **PROCEDURES**

- .1 Notify appropriate agency and Consultant in advance of requirement for tests, in order that attendance arrangements can be made.
- .2 Submit samples and/or materials required for testing, as specifically requested in specifications. Submit with reasonable promptness and in an orderly sequence so as not to cause delay in Work.
- .3 Provide labour and facilities to obtain and handle samples and materials on site. Provide sufficient space to store and cure test samples.

1.8 REJECTED WORK

- .1 Remove defective Work, whether result of poor workmanship, use of defective products or damage and whether incorporated in Work or not, which has been rejected by Consultant as failing to conform to Contract Documents. Replace or re-execute in accordance with Contract Documents.
- .2 Make good other Contractor's work damaged by such removals or replacements promptly.
- .3 If in opinion of Consultant it is not expedient to correct defective Work or Work not performed in accordance with Contract Documents, Owner may deduct from Contract price difference in value between Work performed and that called for by Contract Documents, amount of which shall be determined by Consultant.

1.9 TESTS AND MIX DESIGNS

.1 Furnish test results and mix designs as may be requested.

1.10 MOCK-UPS

- .1 Prepare mock-ups for Work specifically requested in specifications. Include for Work of all Sections required to provide mock-ups.
- .2 Construct in all locations acceptable to Consultant as specified in specific Section.

- .3 Prepare mock-ups for Consultant's review with reasonable promptness and in an orderly sequence, so as not to cause any delay in Work.
- .4 Failure to prepare mock-ups in ample time is not considered sufficient reason for an extension of Contract Time and no claim for extension by reason of such default will be allowed.
- .5 If requested, Consultant will assist in preparing a schedule fixing dates for preparation.
- .6 Remove mock-up at conclusion of Work or when acceptable to Consultant.

1.11 MILL TESTS

.1 Submit mill test certificates as requested.

1.12 EQUIPMENT AND SYSTEMS

.1 Submit adjustment and balancing reports for mechanical, electrical and building equipment systems.

Part 2 Products

2.1 NOT USED

.1 Not Used.

Part 3 Execution

3.1 NOT USED

.1 Not Used.

1.1 SECTION INCLUDES

.1 Temporary utilities.

1.2 RELATED SECTIONS

.1 Section 015200 - Construction Facilities.

1.3 INSTALLATION AND REMOVAL

- .1 Provide temporary utilities controls in order to execute work expeditiously.
- .2 Remove from site all such work after use.

1.4 **DEWATERING**

.1 Provide temporary drainage and pumping facilities to keep excavations and site free from standing water.

1.5 WATER SUPPLY

.1 A continuous supply of potable water for construction use shall be accessible on-site from the existing and proposed well systems. Contractor shall coordinate water access schedule with owner prior to commencing with construction schedule.

1.6 TEMPORARY HEATING AND VENTILATION – Managed by Township

- .1 Provide temporary heating required during construction period, including attendance, maintenance and fuel.
- .2 Construction heaters used inside building must be vented to outside or be non-flameless type. Solid fuel salamanders are not permitted.
- .3 Provide temporary heat and ventilation in enclosed areas as required to:
- .1 Facilitate progress of Work.
- .2 Protect Work and products against dampness and cold.
- .3 Prevent moisture condensation on surfaces.
- .4 Provide ambient temperatures and humidity levels for storage, installation and curing of materials.
- .5 Provide adequate ventilation to meet health regulations for safe working environment.
- .4 Maintain temperatures of minimum 10 degrees C in areas where construction is in progress.
- .5 Ventilating:
 - .1 Prevent accumulations of dust, fumes, mists, vapours or gases in areas occupied during construction.

- .2 Provide local exhaust ventilation to prevent harmful accumulation of hazardous substances into atmosphere of occupied areas.
- .3 Dispose of exhaust materials in manner that will not result in harmful exposure to persons.
- .4 Ventilate storage spaces containing hazardous or volatile materials.
- .5 Ventilate temporary sanitary facilities.
- .6 Continue operation of ventilation and exhaust system for time after cessation of work process to assure removal of harmful contaminants.
- .6 Maintain strict supervision of operation of temporary heating and ventilating equipment to:
 - .1 Conform with applicable codes and standards.
 - .2 Enforce safe practices.
 - .3 Prevent abuse of services.
 - .4 Prevent damage to finishes.
 - .5 Vent direct-fired combustion units to outside.
- .7 Be responsible for damage to Work due to failure in providing adequate heat and protection during construction.

1.7 TEMPORARY POWER AND LIGHT

- .1 Contractor will pay for temporary power during construction for temporary lighting and operating of power tools.
- .2 Arrange for connection with appropriate utility company. Pay all costs for installation, maintenance and removal.
- .3 Provide and maintain temporary lighting throughout project.
- .4 Electrical power and lighting systems installed under this Contract may be used for construction requirements only with prior approval of Consultant provided that guarantees are not affected. Make good damage to electrical system caused by use under this Contract. Replace lamps which have been used for more than 3 months.

1.8 TEMPORARY COMMUNICATION FACILITIES

.1 Provide and pay for temporary telephone necessary for own use.

1.9 FIRE PROTECTION

- .1 Provide and maintain temporary fire protection equipment during performance of Work required by insurance companies having jurisdiction and governing codes, regulations and bylaws.
- .2 Burning rubbish and construction waste materials is not permitted on site.

Section 015100 TEMPORARY UTILITIES Page 3

- Part 2 Products Not Used
- Part 3 Execution Not Used

1.1 SECTION INCLUDES

- .1 Construction aids.
- .2 Office and sheds.
- .3 Parking.
- .4 Project identification.

1.2 RELATED SECTIONS

.1 Section 015100 - Temporary Utilities.

1.3 REFERENCES

- .1 Canadian Construction Documents Committee (CCDC)
 - .1 CCDC 2-20, Stipulated Price Contract.

1.4 INSTALLATION AND REMOVAL

- .1 Provide construction facilities in order to execute work expeditiously.
- .2 Remove from site all such work after use.

1.5 SCAFFOLDING

.1 Provide and maintain scaffolding and ladders as required to complete the work.

1.6 HOISTING

- .1 Provide, operate and maintain hoists cranes required for moving of workers, materials and equipment. Make financial arrangements with Subcontractors for use thereof.
- .2 Cranes shall be operated by qualified operator.

1.7 SITE STORAGE/LOADING

- .1 Confine work and operations of employees by Contract Documents. Do not unreasonably encumber premises with products.
- .2 Do not load or permit to load any part of Work with a weight or force that will endanger the Work.

1.8 CONSTRUCTION PARKING

- .1 Parking will be permitted on site provided it does not disrupt performance of work or access to the existing lab, barns and offices for normal operations.
- .2 Provide and maintain adequate access to project site.
- .3 Contractor to provide snow removal during period of Work.
- .4 Existing roads for access to project site may be used. Maintain such roads for duration of Contract and make good damage resulting from Contractors' use of roads.

1.9 SECURITY

.1 Ensure site is secure after every working day and provide and pay for security if contractor deems necessary.

1.10 OFFICES

- .1 Provide office heated to 22 °C, lighted 750 lx and ventilated, of sufficient size to accommodate site meetings and furnished with drawing laydown table.
- .2 Provide a clearly marked and fully stocked first-aid case in a readily available location.
- .3 Subcontractors may provide their own offices as necessary. Direct location of these offices.

1.11 EQUIPMENT, TOOL AND MATERIALS STORAGE

- .1 Provide and maintain, in a clean and orderly condition, lockable weatherproof sheds for storage of tools, equipment and materials.
- .2 Locate materials not required to be stored in weatherproof sheds on site in a manner to cause least interference with work activities.

1.12 SANITARY FACILITIES

- .1 Provide sanitary facilities for work force in accordance with governing regulations and ordinances.
- .2 Post notices and take such precautions as required by local health authorities. Keep area and premises in sanitary condition.

Section 015200 CONSTRUCTION FACILITIES Page 3

Part 2 Products – Not Used

Part 3 Execution – Not Used

1.1 RELATED SECTIONS

.1 Section 024117-Structure Demolition-Short Form.

1.2 REFERENCES

- .1 Canadian General Standards Board (CGSB)
 - .1 CGSB 1.59-97, Alkyd Exterior Gloss Enamel.
 - .2 CAN/CGSB 1.189-00, Exterior Alkyd Primer for Wood.
- .2 Canadian Standards Association (CSA International)
 - .1 CSA-O121-M1978(R2003), Douglas Fir Plywood.
- .3 Public Works Government Services Canada (PWGSC) Standard Acquisition Clauses and Conditions (SACC)-ID: R0202D, Title: General Conditions 'C', In Effect as Of: May 14, 2004.

1.3 INSTALLATION AND REMOVAL

- .1 Provide temporary controls in order to execute Work expeditiously.
- .2 Remove from site all such work after use.

1.4 HOARDING

- .1 Erect temporary site enclosures using scaffold type shoring or an approved equal. The design of all shoring and temporary bracing shall furnished and provided by the contractor in accordance with the Occupational Health and Safety Act 2000.
- .2 Apply planks and panels for work platforms in accordance with the Occupational Health and Safety Act 2000.
- .3 Provide one lockable truck entrance gate and at least one pedestrian door as directed and conforming to applicable traffic restrictions on site. Equip gates with locks and keys.
- .4 Erect and maintain pedestrian walkways including roof and side covers, complete with signs and electrical lighting as required by law.
- .5 Paint public side of site enclosure in selected colours with one coat primer to CAN/CGSB 1.189 and one coat exterior paint to CGSB 1.59. Maintain public side of enclosure in clean condition.
- .6 Erect temporary site enclosure using new 1.2 m high snow fence wired to rolled steel "T" bar fence posts spaced at 2.4 m on centre. Provide one lockable truck gate. Maintain fence in good repair.
- .7 Provide barriers around trees and plants designated to remain. Protect from damage by equipment and construction procedures.

1.5 GUARD RAILS AND BARRICADES

- .1 Provide secure, rigid guard rails and barricades around deep excavations, open shafts, open stair wells, open edges of floors and roofs, and scaffolding.
- .2 Provide as required by governing authorities. WEATHER ENCLOSURES
- .3 Provide weather tight closures to unfinished door and window openings, tops of shafts and other openings in floors and roofs.
- .4 Close off floor areas where walls are not finished; seal off other openings; enclose building interior work for temporary heat.
- .5 Design enclosures to withstand wind pressure as noted on drawing S0.

1.6 DUST TIGHT SCREENS

- .1 Provide dust tight screens or air tight partitions to localize dust generating activities, and for protection of workers, finished areas of Work and public.
- .2 Maintain and relocate protection until such work is complete.

1.7 ACCESS TO SITE

.1 Provide and maintain access roads, sidewalk crossings, ramps and construction runways as may be required for access to Work.

1.8 FIRE ROUTES

.1 Maintain access to property including overhead clearances for use by emergency response vehicles.

1.9 PROTECTION FOR OFF-SITE AND PUBLIC PROPERTY

- .1 Protect surrounding private and public property from damage during performance of Work.
- .2 Be responsible for damage incurred.

1.10 **PROTECTION OF BUILDING FINISHES**

- .1 Provide protection for finished and partially finished building finishes and equipment during performance of Work.
- .2 Provide necessary screens, covers, and hoardings.
- .3 Confirm with the Consultant locations and installation schedule 5 days prior to installation.
- .4 Be responsible for damage incurred due to lack of or improper protection.

1.11 WASTE MANAGEMENT AND DISPOSAL

.1 Separate waste materials for reuse and recycling in accordance with laws and bylaws.

- Part 2 Products
- 2.1 NOT USED
 - .1 Not Used.
- Part 3 Execution
- 3.1 NOT USED
 - .1 Not Used.

1.1 SECTION INCLUDES

- .1 Product quality, availability, storage, handling, protection, and transportation.
- .2 Manufacturer's instructions.
- .3 Quality of Work, coordination and fastenings.

1.2 REFERENCE STANDARDS

- .1 Canadian Construction Documents Committee (CCDC)
 - .1 CCDC 2 2020, Stipulated Price Contract.
- .2 Within text of each specifications section, reference may be made to reference standards.
- .3 Conform to these reference standards, in whole or in part as specifically requested in specifications.
- .4 If there is question as to whether any product or system is in conformance with applicable standards, Consultant reserves right to have such products or systems tested to prove or disprove conformance.
- .5 Cost for such testing will be born by Owner in event of conformance with Contract Documents or by Contractor in event of non-conformance.
- .6 Conform to latest date of issue of referenced standards in effect on date of submission of Tenders, except where specific date or issue is specifically noted.

1.3 QUALITY

- .1 Products, materials, equipment and articles (referred to as products throughout specifications) incorporated in Work shall be new, not damaged or defective, and of best quality (compatible with specifications) for purpose intended. If requested, furnish evidence as to type, source and quality of products provided.
- .2 Defective products, whenever identified prior to completion of Work, will be rejected, regardless of previous inspections. Inspection does not relieve responsibility, but is precaution against oversight or error. Remove and replace defective products at own expense and be responsible for delays and expenses caused by rejection.
- .3 Should any dispute arise as to quality or fitness of products, decision rests strictly with Consultant based upon requirements of Contract Documents.

- .4 Unless otherwise indicated in specifications, maintain uniformity of manufacture for any particular or like item throughout building.
- .5 Permanent labels, trademarks and nameplates on products are not acceptable in prominent locations, except where required for operating instructions, or when located in mechanical or electrical rooms.

1.4 AVAILABILITY

- .1 Immediately upon signing Contract, review product delivery requirements and anticipate foreseeable supply delays for any items. If delays in supply of products are foreseeable, notify Consultant of such, in order that substitutions or other remedial action may be authorized in ample time to prevent delay in performance of Work.
- .2 In event of failure to notify Consultant at commencement of Work and should it subsequently appear that Work may be delayed for such reason, Consultant reserves right to substitute more readily available products of similar character, at no increase in Contract Price or Contract Time.

1.5 STORAGE, HANDLING AND PROTECTION

- .1 Handle and store products in manner to prevent damage, adulteration, deterioration and soiling and in accordance with manufacturer's instructions when applicable.
- .2 Store packaged or bundled products in original and undamaged condition with manufacturer's seal and labels intact. Do not remove from packaging or bundling until required in Work.
- .3 Store products subject to damage from weather in weatherproof enclosures.
- .4 Store cementitious products clear of earth or concrete floors, and away from walls.
- .5 Keep sand, when used for grout or mortar materials, clean and dry. Store sand on wooden platforms and cover with waterproof tarpaulins during inclement weather.
- .6 Store sheet materials, lumber on flat, solid supports and keep clear of ground. Slope to shed moisture.
- .7 Store and mix paints in heated and ventilated room. Remove oily rags and other combustible debris from site daily. Take every precaution necessary to prevent spontaneous combustion.
- .8 Remove and replace damaged products at own expense and to satisfaction of Consultant.

.9 Touch-up damaged factory finished surfaces to Consultant's satisfaction. Use touch-up materials to match original. Do not paint over name plates.

1.6 TRANSPORTATION

.1 Pay costs of transportation of products required in performance of Work.

1.7 MANUFACTURER'S INSTRUCTIONS

- .1 Unless otherwise indicated in specifications, install or erect products in accordance with manufacturer's instructions. Do not rely on labels or enclosures provided with products. Obtain written instructions directly from manufacturers.
- .2 Notify Consultant in writing, of conflicts between specifications and manufacturer's instructions, so that Consultant may establish course of action.
- .3 Improper installation or erection of products, due to failure in complying with these requirements, authorizes Consultant to require removal and re-installation at no increase in Contract Price or Contract Time.

1.8 QUALITY OF WORK

- .1 Ensure Quality of Work is of highest standard, executed by workers experienced and skilled in respective duties for which they are employed. Immediately notify Consultant if required Work is such as to make it impractical to produce required results.
- .2 Do not employ anyone unskilled in their required duties. Consultant reserves right to require dismissal from site, workers deemed incompetent or careless.
- .3 Decisions as to standard or fitness of Quality of Work in cases of dispute rest solely with Consultant, whose decision is final.

1.9 CO-ORDINATION

- .1 Ensure cooperation of workers in laying out Work. Maintain efficient and continuous supervision.
- .2 Be responsible for coordination and placement of openings, sleeves and accessories.

1.10 CONCEALMENT

.1 In finished areas, conceal pipes, ducts and wiring in floors, walls and ceilings, except where indicated otherwise.

.2 Before installation, inform Consultant if there is interference. Install as directed by Consultant.

1.11 REMEDIAL WORK

- .1 Refer to CCDC 2-2020.
- .2 Perform remedial work required to repair or replace parts or portions of Work identified as defective or unacceptable. Coordinate adjacent affected Work as required.
- .3 Perform remedial work by specialists familiar with materials affected. Perform in a manner to neither damage nor put at risk any portion of Work.

1.12 LOCATION OF FIXTURES

- .1 Consider location of fixtures, outlets, and mechanical and electrical items indicated as approximate.
- .2 Inform Consultant of conflicting installation. Install as directed.

1.13 FASTENINGS

- .1 Provide metal fastenings and accessories in same texture, colour and finish as adjacent materials, unless indicated otherwise.
- .2 Prevent electrolytic action between dissimilar metals and materials.
- .3 Use non-corrosive hot dip galvanized steel fasteners and anchors for securing exterior work, unless stainless steel or other material is specifically requested in affected specification Section.
- .4 Space anchors within individual load limit or shear capacity and ensure they provide positive permanent anchorage. Wood, or any other organic material plugs are not acceptable.
- .5 Keep exposed fastenings to a minimum, space evenly and install neatly.
- .6 Fastenings which cause spalling or cracking of material to which anchorage is made are not acceptable.

1.14 FASTENINGS - EQUIPMENT

.1 Use fastenings of standard commercial sizes and patterns with material and finish suitable for service.

- .2 Use heavy hexagon heads, semi-finished unless otherwise specified. Use No. 304 stainless steel for exterior areas.
- .3 Bolts may not project more than one diameter beyond nuts.
- .4 Use plain type washers on equipment, sheet metal and soft gasket lock type washers where vibrations occur. Use resilient washers with stainless steel.

1.15 **PROTECTION OF WORK IN PROGRESS**

.1 Prevent overloading of any part of building. Do not cut, drill or sleeve any load bearing structural member, unless specifically indicated without written approval of Consultant.

1.16 EXISTING UTILITIES

- .1 When breaking into or connecting to existing services or utilities, execute Work at times directed by local governing authorities, with minimum of disturbance to Work.
- .2 Protect, relocate or maintain existing active services. When services are encountered, cap off in manner approved by authority having jurisdiction. Stake and record location of capped service.

Part 2 Products

2.1 NOT USED

.1 Not Used.

Part 3 Execution

3.1 NOT USED

.1 Not Used.

1.1 **RELATED SECTIONS**

.1 Section 013300 - Submittal procedures.

1.2 REFERENCES

- .1 Canada Labour Code, Part 2, Canada Occupational Safety and Health Regulations.
 - .1 Occupational Health and Safety Act, R.S.A. 2000.
- .2 Province of Ontario
 - .1 Occupational Health and Safety Act and Regulations for Construction Projects, R.S.O. 1990 as amended 213/91.

1.3 SUBMITTALS

- .1 Make submittals in accordance with Section 013300 Submittal Procedures.
- .2 Submit site-specific Health and Safety Plan: Within 7 days after date of Notice to Proceed and prior to commencement of Work. Health and Safety Plan must include:
 - .1 Results of site specific safety hazard assessment.
 - .2 Results of safety and health risk or hazard analysis for site tasks and operation found in work plan.
- .3 Submit 1 copy of Contractor's authorized representative's work site health and safety inspection reports to Consultant and/or authority having jurisdiction.
- .4 Submit copies of reports or directions issued by Federal, Provincial and Territorial health and safety inspectors.
- .5 Submit copies of incident and accident reports.
- .6 Submit Material Safety Data Sheets (MSDS) to Consultant.
- .7 Consultant will review Contractor's site-specific Health and Safety Plan and provide comments to Contractor within 10 days after receipt of plan. Revise plan as appropriate and resubmit plan to Consultant within 10 days after receipt of comments from Consultant.
- .8 Consultant's review of Contractor's final Health and Safety plan should not be construed as approval and does not reduce the Contractor's overall responsibility for construction Health and Safety.

- .9 Medical Surveillance: Where prescribed by legislation, regulation or safety program, submit certification of medical surveillance for site personnel prior to commencement of Work, and submit additional certifications for any new site personnel to Consultant.
- .10 On-site Contingency and Emergency Response Plan: Address standard operating procedures to be implemented during emergency situations.

1.4 FILING OF NOTICE

.1 File Notice of Project with Provincial authorities prior to commencement of Work.

1.5 SAFETY ASSESSMENT

.1 Perform site specific safety hazard assessment related to project.

1.6 MEETINGS

.1 Schedule and administer Health and Safety meeting with Consultant prior to commencement of Work.

1.7 REGULATORY REQUIREMENTS

.1 Do Work in accordance with Regulatory Requirements as prescribed in the Ontario Health and Safety Act for construction projects.

1.8 GENERAL REQUIREMENTS

- .1 Develop written site-specific Health and Safety Plan based on hazard assessment prior to commencing any site Work and continue to implement, maintain, and enforce plan until final demobilization from site. Health and Safety Plan must address project specifications.
- .2 Consultant may respond in writing, where deficiencies or concerns are noted and may request re-submission with correction of deficiencies or concerns.

1.9 RESPONSIBILITY

- .1 Be responsible for health and safety of persons on site, safety of property on site and for protection of persons adjacent to site and environment to extent that they may be affected by conduct of Work.
- .2 Comply with and enforce compliance by employees with safety requirements of Contract Documents, applicable federal, provincial, territorial and local statutes, regulations, and ordinances, and with site-specific Health and Safety Plan.

1.10 UNFORSEEN HAZARDS

.1 Should any unforeseen or peculiar safety-related factor, hazard, or condition become evident during performance of Work, and follow procedures in place for Employee's Right to Refuse Work in accordance with Acts and Regulations of Ontario having jurisdiction. Advise Consultant verbally and in writing.

1.11 HEALTH AND SAFETY CO-ORDINATOR

- .1 Employ and assign to Work, competent and authorized representative as Health and Safety Co-ordinator. Health and Safety Co-ordinator must:
 - .1 Have minimum 2 years' site-related working experience specific to activities associated with a building.
 - .2 Have working knowledge of occupational safety and health regulations.
 - .3 Be responsible for completing Contractor's Health and Safety Training Sessions and ensuring that personnel not successfully completing required training are not permitted to enter site to perform Work.
 - .4 Be responsible for implementing, enforcing daily and monitoring sitespecific Contractor's Health and Safety Plan.

1.12 **POSTING OF DOCUMENTS**

.1 Ensure applicable items, articles, notices and orders are posted in conspicuous location on site in accordance with Acts and Regulations of Province Territory having jurisdiction, and in consultation with Consultant.

1.13 CORRECTION OF NON-COMPLIANCE

- .1 Immediately address health and safety non-compliance issues identified by authority having jurisdiction or by Consultant.
- .2 Provide Consultant with written report of action taken to correct non-compliance of health and safety issues identified.
- .3 Consultant may stop Work if non-compliance of health and safety regulations is not corrected.

1.14 BLASTING

.1 Blasting or other use of explosives is not permitted.

1.15 **POWDER ACTUATED DEVICES**

.1 Use powder actuated devices only after receipt of written permission from Consultant.

Section 017050 HEALTH AND SAFETY Page 4

1.16 WORK STOPPAGE

- .1 Give precedence to safety and health of public and site personnel and protection of environment over cost and schedule considerations for Work.
- Part 2 Products
- 2.1 NOT USED
 - .1 Not used.
- Part 3 Execution
- 3.1 NOT USED
 - .1 Not used.

1.1 RELATED SECTIONS

.1 Section 011100-Summary of Work.

1.2 REFERENCES

- .1 Canadian Construction Documents Committee (CCDC)
 - .1 CCDC 2-2020, Stipulated Price Contract.
- .2 Owner's identification of existing survey control points and property limits.

1.3 QUALIFICATIONS OF SURVEYOR

.1 Qualified registered land surveyor, licensed to practice in Place of Work, acceptable to the Consultant.

1.4 SURVEY REFERENCE POINTS

- .1 Existing base horizontal and vertical control points are designated on drawings.
- .2 Locate, confirm and protect control points prior to starting site work. Preserve permanent reference points during construction.
- .3 Make no changes or relocations without prior written notice to the Consultant.
- .4 Report to the Consultant when reference point is lost or destroyed, or requires relocation because of necessary changes in grades or locations.
- .5 Require surveyor to replace control points in accordance with original survey control.

1.5 SURVEY REQUIREMENTS

- .1 Establish two permanent bench marks on site, referenced to established bench marks by survey control points. Record locations, with horizontal and vertical data in Project Record Documents.
- .2 Establish lines and levels, locate and lay out, by instrumentation.
- .3 Stake for grading, fill and topsoil placement as well as landscaping features.
- .4 Stake slopes and berms.
- .5 Establish pipe invert elevations.
- .6 Stake formwork for foundations.
- .7 Stake exterior slab locations and elevations.
- .8 Establish foundation column locations and floor elevations.

.9 Establish lines and levels for mechanical and electrical work.

1.6 EXISTING SERVICES

- .1 Before commencing work, establish location and extent of service lines in area of Work and notify the Consultant of findings.
- .2 Remove abandoned service lines within 2m of structures. Cap or otherwise seal lines at cut-off points as directed by the Consultant.

1.7 LOCATION OF EQUIPMENT AND FIXTURES

- .1 Location of equipment, fixtures and outlets indicated or specified are to be considered as approximate.
- .2 Locate equipment, fixtures and distribution systems to provide minimum interference and maximum usable space and in accordance with manufacturer's recommendations for safety, access and maintenance.
- .3 Inform the Consultant of impending installation and obtain approval for actual location.
- .4 Submit field drawings to indicate relative position of various services and equipment when required by the Consultant.

1.8 RECORDS

- .1 Maintain a complete, accurate log of control and survey work as it progresses.
- .2 On completion of foundations and major site improvements, prepare a certified survey showing dimensions, locations, angles and elevations of Work.
- .3 Record locations of maintained, re-routed and abandoned service lines.

1.9 SUBMITTALS

- .1 Submit name and address of Surveyor to the Consultant. On request of the Consultant, submit documentation to verify accuracy of field engineering work.
- .2 Submit certificate signed by surveyor certifying and noting those elevations and locations of completed Work that conform or do not conform to the Contract Documents.

1.10 SUBSURFACE CONDITIONS

- .1 Promptly notify Consultant in writing if subsurface conditions at Place of Work differ materially from those indicated in Contract Documents, or a reasonable assumption of probable conditions based thereon.
- .2 After prompt investigation, should Consultant determine that conditions do differ materially, instructions will be issued for changes in Work as provided in Changes and Change Orders.

- Part 2 Products
- 2.1 NOT USED
 - .1 Not Used.
- Part 3 Execution
- 3.1 NOT USED
 - .1 Not Used.

1.1 SECTION INCLUDES

- .1 Progressive cleaning.
- .2 Final cleaning.

1.2 REFERENCE STANDARDS

- .1 Canadian Construction Documents Committee (CCDC)
 - .1 CCDC 2 2020, Stipulated Price Contract.

1.3 PROJECT CLEANLINESS

- .1 Maintain Work in tidy condition, free from accumulation of waste products and debris, other than that caused by Owner or other Contractors.
- .2 Remove waste materials from site at regularly scheduled times or dispose of as directed by Consultant. Do not burn waste materials on site, unless approved by Consultant.
- .3 Clear snow and ice from access to building.
- .4 Make arrangements with and obtain permits from authorities having jurisdiction for disposal of waste and debris.
- .5 Provide on-site containers for collection of waste materials and debris.
- .6 Remove waste material and debris from site and deposit in waste container at end of each working day.
- .7 Dispose of waste materials and debris.
- .8 Clean interior areas prior to start of finish work, and maintain areas free of dust and other contaminants during finishing operations.
- .9 Store volatile waste in covered metal containers, and remove from premises at end of each working day.
- .10 Provide adequate ventilation during use of volatile or noxious substances. Use of building ventilation systems is not permitted for this purpose.
- .11 Use only cleaning materials recommended by manufacturer of surface to be cleaned, and as recommended by cleaning material manufacturer.

.12 Schedule cleaning operations so that resulting dust, debris and other contaminants will not fall on wet, newly painted surfaces nor contaminate building systems.

1.4 FINAL CLEANING

- .1 When Work is Substantially Performed, remove surplus products, tools, construction machinery and equipment not required for performance of remaining Work.
- .2 Remove waste products and debris other than that caused by others, and leave Work clean and suitable for occupancy.
- .3 Prior to final review, remove surplus products, tools, construction machinery and equipment.
- .4 Remove waste products and debris other than that caused by Owner or other Contractors.
- .5 Remove waste materials from site at regularly scheduled times or dispose of as directed by Consultant. Do not burn waste materials on site, unless approved by Consultant.
- .6 Make arrangements with and obtain permits from authorities having jurisdiction for disposal of waste and debris.
- .7 Clean and polish glass, mirrors, hardware, wall tile, stainless steel, chrome, porcelain enamel, baked enamel, plastic laminate, and mechanical and electrical fixtures. Replace broken, scratched or disfigured glass.
- .8 Remove stains, spots, marks and dirt from decorative work, electrical and mechanical fixtures, furniture fitments, walls, and floors.
- .9 Clean lighting reflectors, lenses, and other lighting surfaces.
- .10 Vacuum clean and dust building interiors, behind grilles, louvres and screens.
- .11 Inspect finishes, fitments and equipment and ensure specified workmanship and operation.
- .12 Broom clean and wash exterior walks, steps and surfaces; rake clean other surfaces of grounds.
- .13 Remove dirt and other disfiguration from exterior surfaces.
- .14 Clean and sweep roofs, gutters, areaways, and sunken wells.
- .15 Sweep and wash clean paved areas.

- .16 Clean equipment and fixtures to a sanitary condition; clean or replace filters of mechanical equipment.
- .17 Clean roofs, downspouts, and drainage systems.
- .18 Remove debris and surplus materials from crawl areas and other accessible concealed spaces.
- .19 Remove snow and ice from access to building.

Part 2 Products

2.1 NOT USED

- .1 Not Used.
- Part 3 Execution
- 3.1 NOT USED
 - .1 Not Used.

1.1 SECTION INCLUDES

.1 Administrative procedures preceding preliminary and final inspections of Work.

1.2 RELATED SECTIONS

.1 Section 018200 – Demonstration and Training

1.3 REFERENCES

- .1 Canadian Construction Documents Committee (CCDC)
 - .1 CCDC 2-20, Stipulated Price Contract.

1.4 INSPECTION AND DECLARATION

- .1 Contractor's Inspection: Contractor and all Subcontractors shall conduct an inspection of Work, identify deficiencies and defects, and repair as required to conform to Contract Documents.
 - .1 Notify Consultant in writing of satisfactory completion of Contractor's Inspection and that corrections have been made.
 - .2 Request Consultant's Inspection.
- .2 Consultant's Inspection: Consultant and Contractor will perform inspection of Work to identify obvious defects or deficiencies. Contractor shall correct Work accordingly.
- .3 Completion: submit written certificate that following have been performed:
 - .1 Work has been completed and inspected for compliance with Contract Documents.
 - .2 Defects have been corrected and deficiencies have been completed.
 - .3 Equipment and systems have been tested, adjusted and balanced and are fully operational.
 - .4 Certificates required by Utility companies have been submitted.
 - .5 Operation of systems have been demonstrated to Owner's personnel.
 - .6 Work is complete and ready for Final Inspection.
- .4 Final Inspection: when items noted above are completed, request final inspection of Work by Owner, Consultant, and Contractor. If Work is deemed incomplete by Owner and Consultant, complete outstanding items and request reinspection.

- .5 Declaration of Substantial Performance: when Consultant consider deficiencies and defects have been corrected and it appears requirements of Contract have been substantially performed, make application for certificate of Substantial Performance. Refer to CCDC 2, General Conditions Article for specifics to application.
- .6 Commencement of Lien and Warranty Periods: date of Owner's acceptance of submitted declaration of Substantial Performance shall be date for commencement for warranty period and commencement of lien period unless required otherwise by lien statute of Place of Work.
- .7 Final Payment: When Consultant consider final deficiencies and defects have been corrected and it appears requirements of Contract have been totally performed, make application for final payment. Refer to CCDC 2. If Work is deemed incomplete by Consultant, complete outstanding items and request reinspection.
- .8 Payment of Holdback: After issuance of certificate of Substantial Performance of Work, submit an application for payment of holdback amount in accordance with CCDC 2.

Part 2 Products

2.1 NOT USED

- .1 Not Used.
- Part 3 Execution
- 3.1 NOT USED
 - .1 Not Used.
Part 1 General

1.1 SECTION INCLUDES

.1 Procedures for demonstration and instruction of equipment and systems to Owner's personnel.

1.2 RELATED SECTIONS

.1 Section 017700 - Closeout Procedures.

1.3 DESCRIPTION

- .1 Demonstrate operation and maintenance of equipment and systems to Owner's personnel two weeks prior to date of substantial performance.
- .2 Owner will provide list of personnel to receive instructions, and will coordinate their attendance at agreed-upon times.

1.4 QUALITY CONTROL

.1 When specified in individual Sections, require manufacturer to provide authorized representative to demonstrate operation of equipment and systems, instruct Owner's personnel, and provide written report that demonstration and instructions have been completed.

1.5 SUBMITTALS

- .1 Submit schedule of time and date for demonstration of each item of equipment and each system two weeks prior to designated dates, for Consultant's approval.
- .2 Submit reports within one week after completion of demonstration, that demonstration and instructions have been satisfactorily completed.
- .3 Give time and date of each demonstration, with list of persons present.

1.6 CONDITIONS FOR DEMONSTRATIONS

- .1 Equipment has been inspected and put into operation.
- .2 Testing, adjusting, and balancing has been performed.
- .3 Provide copies of completed operation and maintenance manuals for use in demonstrations and instructions.

1.7 PREPARATION

- .1 Verify that conditions for demonstration and instructions comply with requirements.
- .2 Verify that designated personnel are present.

1.8 DEMONSTRATION AND INSTRUCTIONS

- .1 Demonstrate start-up, operation, control, adjustment, trouble-shooting, servicing, and maintenance of each item of equipment at the equipment location.
- .2 Instruct personnel in all phases of operation and maintenance using operation and maintenance manuals as the basis of instruction.
- .3 Review contents of manual in detail to explain all aspects of operation and maintenance.
- .4 Prepare and insert additional data in operations and maintenance manuals when the need for additional data becomes apparent during instructions.

Part 2 Products

2.1 NOT USED

- .1 Not Used.
- Part 3 Execution

3.1 NOT USED

.1 Not Used.

END OF SECTION

RESTRICTIONS ON SOURCE OF CONCRETE

O.P.S.S. Form 1350 shall apply for the mixing and transporting of concrete except that all Portland cement concrete supplied by the Contractor in accordance with the requirements of this Contract shall be obtained from a Ready-Mixed Concrete Operation approved by the Engineer.

CORRECTION AFTER COMPLETION

Subject to any Special Provisions in the Contract, the Contractor shall remedy any defects due to faulty materials or workmanship appearing within one year from the date of acceptance of the work, as certified by the Engineer under Section GC 8.02.03.06 of the General Conditions of the Contract, and shall pay for any damage or other work resulting therefrom which appears within such period and neither the final certificate nor payment thereunder shall relieve the Contractor from responsibility thereunder. This Section shall not be deemed to restrict any liability of the Contractor arising out of any law in force in the Province of Ontario.

GRANULAR BACKFILL CULVERTS

This work shall be performed as a distinctly separate operation. No material shall be placed upon the completed backfill until the latter has been approved by the Engineer and the costs of any delays so arising shall be borne by the Contractor.

STORAGE AREAS

The Contractor shall obtain the approval of the Engineer prior to designating areas within the site for storage of his equipment and materials and the erection of offices and sheds.

If additional property outside the site is required for such purposes, the Contractor shall make his own arrangements at no additional cost to the Owner.

COMPACTION EQUIPMENT

Compaction equipment shall be approved by the Engineer before being used for work under this Contract.

DUST CONTROL

The Contractor shall take such steps as may be required to prevent dust nuisance resulting from his operations either within the right-of-way or elsewhere or by public traffic where it is the Contractor's responsibility to maintain a roadway through the work. Such steps may include the supply and placing of water and/or calcium chloride as deemed necessary by the Engineer.

Where the work requires the sawing of asphalt or the sawing or grinding of concrete, blades and grinders of the wet type shall be used with sufficient water to prevent the incidence of dust, wherever dust would affect traffic or wherever dust would be a nuisance to residents of the area where the work is being carried out.

The cost of all such preventative measures shall be borne by the Contractor.

DISPOSAL OF SURPLUS OR UNSUITABLE EXCAVATED MATERIAL FROM GRADING AND ALL OTHER OPERATIONS FOR WHICH EXCAVATION IS REQUIRED

All materials, including rubble and debris resulting from demolitions, excavated in carrying out the work of the various tender items included in this Contract and which is unsuitable for or which is surplus to the requirements for backfill or embankment construction, shall be disposed of at locations arranged for by and at the sole expense of the Contractor. Such sites shall be subject to the approval of the Engineer and the Ministry of the Environment. The Contractor shall provide the Engineer with written confirmation of approval by the Ministry of the Environment.

The price bid for the Contract items requiring such work shall be full compensation for loading, hauling, placing, trimming and for all other work which may be required to dispose of the unsuitable or surplus material.

ENVIRONMENTAL PROTECTION

The Contractor shall conduct his operations in an environmentally acceptable manner, which means a manner which complies with the requirements of the Environmental Protection Act, R.S.O. 1980.

RESTORATION

Restoration of areas unnecessarily damaged by the Contractor's operations shall be at the Contractor's expense.

Prior to restoration of Asphalt or Concrete entrances all loose, broken or disturbed material along the edges shall be removed and all edges of the existing entrances shall be sawed or otherwise cut in straight lines as directed by the Engineer. No additional payment shall be made for this work.

UTILITIES

The Contractor shall be required to co-operate with telephone, cable, hydro, gas or any other utility company where plant may be affected to permit these agencies to maintain services and to re-arrange plant during construction, where required.

The location, depth, type, and configuration of underground utilities and services shown on the Contract Drawings are based on the investigations made by the Engineer, but are not guaranteed. The Contractor shall contact the utility companies to confirm the exact location, type and configuration of these utilities. The Contractor shall exercise the necessary care in construction operations and take such other precautions as are necessary to safeguard the utilities from damage.

No heavy construction equipment will be allowed to operate over the existing gas mains. The Contractor will be responsible for replacing any sand padding, which is removed from around gas mains during excavation operations and no additional payment shall be made as a result of work necessary to satisfy this requirement.

The Contractor shall be responsible for any unauthorized disruptions of service and any damage to utilities arising out of his work. The cost of protective measures, together with the cost of restoring the lines to their original state and location, will be at the expense of the Contractor, and will be billed to him by the utility authority.

The Contractor shall be responsible for supporting existing watermains, gas mains and telephone ducts and concrete conduit structure where they are encountered crossing or adjacent to underground service trenches. The method of support shall be as detailed in the Contract Drawings or as stipulated by the utility companies and, payment for support measures shall be deemed to be included in the Contract prices for the underground services being installed.

No additional compensation shall be made for delay or other alterations to the Contractor's schedule caused by the utility company operations.

It is the Contractor's responsibility as "constructor" under the provisions of the Occupational Health and Safety Act to co-ordinate the activities of all employees and workers operating within the Contract limits to ensure that the requirements of the Occupational Health and Safety Act are satisfied. The Contractor shall ensure that each utility company operating within the Contract limits is included in this process.

CORRUGATED STEEL PIPE

Should the Contractor choose to supply a universal dimple coupler or any other coupler which does not follow the contour of the corrugated steel pipe sections to be joined, he shall, as part of the work at the Contract price for the appropriate tender item, supply and install polyethylene gaskets at all joints where such couplers are used.

Gaskets shall consist of a strip 2 m wide of 150 um polyethylene and shall be folded so as to produce a strip 1 m wide and of sufficient length to equal the circumference of the pipe plus a minimum of 300 mm overlap. This band shall be so placed that it is symmetrical about the pipe joint and shall be placed before installing the coupler.

NO OPEN BURNING

Open fires shall not be located within the limits of this contract.

TRAFFIC CONTROL, FLAGGING

Flagging for traffic control on this Contract shall be in conformance with the procedure outlined in the Ministry of Transportation Temporary Conditions Manual, latest edition.

EMERGENCY AND MAINTENANCE MEASURES

Whenever the construction site is unattended by the general superintendent, the name, address and telephone number of a responsible official of the contracting firm, shall be given to the Engineer. This official shall be available at all times and have the necessary authority to mobilize workmen and machinery and to take any action as directed by the Engineer in case emergency or maintenance measures are required regardless whether the emergency or requirement for maintenance was caused by the Contractor's negligence, act of God, or any cause whatsoever.

Should the Contractor be unable to carry out immediate remedial measures required, the Owner will carry out the necessary repairs, the costs for which shall be charged to the Contractor.

CONTRACTOR'S SUPPLY OF CONSTRUCTION SIGNS

The Contractor is responsible for the supply, erection, maintenance and removal of all temporary traffic controls including signs, lights, barricades, delineators, cones, etc, required on the project.

SPILLS REPORTING

Spills or discharges of pollutants or contaminants under the control of the Contractor, and spills or discharges of pollutants or contaminants that are a result of the Contractor's operations that cause or are likely to cause adverse effects shall forthwith be reported to the Engineer. Such spills or discharges and their adverse effects shall be as defined in the Environmental Protection Act R.S.O. 1980.

All spills or discharges of liquid, other than accumulated rain water, from luminaires, internally illuminated signs, lamps and liquid type transformers under the control of the Contractor, and all spills or discharges from this equipment that are a result of the Contractor's operations shall, unless otherwise indicated in the Contract, be assumed to contain PCB's and shall forthwith be reported to the Engineer.

This reporting will not relieve the Contractor of his legislated responsibilities regarding such spills or discharges.

REVIEW OF SHOP/WORKING DRAWINGS

For the portions of the work to be done under this Contract where detail drawings are to be supplied by the Contractor, six (6) copies of same, together with specifications, plus such additional copies as the Contractor and his sub-contractors may require, shall be submitted to the Engineer for review.

The Contractor or his Sub-contractor shall check and initial all shop drawings before submission to the Engineer so as to intercept and correct any major errors or omissions. Shop drawings will not be reviewed by the Engineer unless they have been previously checked by the Contractor.

The review by the Engineer is for the sole purpose of ascertaining conformance with the general design concept. This review shall not mean that the Engineer approves the detail design inherent in the shop drawings, responsibility for which shall remain with the Contractor submitting same, and such review shall not relieve the Contractor of his responsibility for errors or omissions in the shop drawings or of his responsibility for meeting all requirements of the Contract Documents.

The Contractor is responsible for dimensions to be confirmed and correlated at the job site, for information that pertains solely to fabrication processes or to techniques of construction and installation and for co-ordination of the work of all sub-trades.

Work which relates to the shop drawings shall not be carried out before the Engineer's review of the shop drawings is complete.

LAYOUT BY THE CONTRACTOR

Layout of the work shall be performed by the Contractor in accordance with the requirements of Sub-section GC 7.02 of the General Conditions of the Contract.

MANAGEMENT AND DISPOSAL OF MATERIALS

In accordance with O.P.S.S. 180, Forms O.P.S.F. 1800, 1801 and 1803 shall be completed by the Contractor and forwarded to the Owner.

This form to be used with Ontario Provincial Specification 180

SITE SELECTION NOTIFICATION FOR MANAGEMENT AS DISPOSABLE FILL

Contract Information

Contract No.

Owner

The following describes the notification process between the <u>**Owner**</u> of the Contract and the Contractor, wherein the Contractor formally notifies the <u>**Owner**</u> that agreement has been reached with a third party property <u>**Owner**</u> for the disposition of Contract generated excess material. Such excess material, managed as disposable fill shall be limited to one or a combination of: earth; aggregate; swamp material; rock; natural wood and debris from open fires, provided the conditions on management are satisfied.

Site Information

Property <u>Owner(s)</u> for the subject property:	
The subject property:	
Lot, Concession	, Township of
County/Region/District of	, Quantity and type of excess material Used as fill:

This is to notify you, as <u>**Owner**</u>, that permission has been obtained from the property <u>**Owner**</u>(s) named herein for the Management of excess materials from this Contract. The property <u>**Owner**</u> has also been provided with a copy of this form and has been advised that a Property <u>**Owner**</u>'s Release Form, OPSF 1803, will be required. The use of this management site will comply with the following:

Conditions on Management

Bituminous pavement, concrete, masonry, wood which has been treated, coated or glued, and metal, plastic and polystyrene products will not be accepted for management as disposable fill. Swamp material managed as disposable fill will be top covered by a minimum of 300 mm of earth or topsoil. Swamp material managed as disposable fill may be placed:

- a) a minimum of 2m above the level of ground water.
- b) a minimum of 30m from water bodies;
- c) a minimum of 100m from any water wells; and
- d) a minimum of 100m from residences.

These condition do not supercede any constraints imposed on this property by Federal, Provincial or Municipal statute or regulations and bylaws made thereto.

Dated this _____ day of _____20__

Print Contractor's Name & Field Representative's Name

Contractor's Field Representative Signature

Property Owner(s) Signature(s)

cc: Contract Administrator, Property Owner(s), Contractor

OPSF 1800

July 2001

Ontario Provincial Standard Form

This form to be used with Ontario Provincial Specification 180

SITE SELECTION NOTIFICATION FOR MATERIAL STOCKPILING

Contract Information

Contract No.

<u>Owner</u>

The following describes the notification process between the **Owner** of the Contract and the Contractor, wherein the Contractor formally notifies the **Owner** that agreement has been reached with a third party property **Owner** for the disposition of Contract generated excess material. Such excess material, managed as disposable fill shall be limited to one of or a combination of: earth; aggregate; swamp material; rock; natural wood and debris from open fires, provided the conditions on management are satisfied.

Site Information

Property <u>Owner</u> The subject prope	(s) for the subject property: erty:	
Lot:	Concession	, Township of
County/Region/D	District of	_, Quantity and Type of Excess Material Used as Fill:

This is to notify you, as <u>**Owner**</u>, that permission has been obtained from the property <u>**Owner**</u>(s) named herein for the Management of excess materials from this Contract. The property <u>**Owner**</u> has also been provided with a copy of this form and has been advised that a Property <u>**Owner**</u>'s Release Form, OPSF 1803, will be required. The use of this management site will comply with the following:

Conditions on Management

It is understood that materials are stockpiled to be re-used or held for disposal at a certified waste disposal site. Stockpiles of natural wood, manufactured wood, debris from open fires and swamp material may only be located:

- a. a minimum of 2m above the level of ground water.
- b. a minimum of 30m from water bodies;
- c. a minimum of 100m from residences; and
- d. a minimum of 100m from any water wells.

Stockpiles of bituminous pavement, concrete and masonry may only be located:

a. a minimum of 30m from water bodies;

or

- b. a minimum of 100m from residences unless
 - 1. on property with a boundary common to a right-of-way, within the Contract limits, for a period not exceeding 120 calendar days,
 - 2. such stockpiles are located within a provincial or municipal works yard or in a commercially licensed pit or quarry.

These conditions do not supercede any constraints imposed on this property by Federal, Provincial or Municipal statute or regulations and bylaws made thereto.

Dated this _____ day of _____ 20___

Print Contractor's Name and Field Representative's Name

Contractor's Field Representative Signature

Property **Owner**(s) Signature(s)

OPSF 1801

Ontario Provincial Standards Form

This form to be used with Ontario Provincial Standard Specification 180

PROPERTY OWNER'S RELEASE

Work Description:	Contract No:				
I/We	Work Description:				
Township of, and County/Region/District of, verify that the Contractor for the above-noted work has placed excess material from the above noted Contract on my/our property with my/our permission. I/we have been advised by the Contractor of the "Conditions on Management" described in OPS Forms 1800 or 1801, "Site Selection Notification for Management as Disposable Fill", or "Site Selection Notification for Management as Disposable Fill", or "Site Selection Notification for Materials Stockpiling", respectively, or both, and have been assured by the Contractor that these conditions have been met. Where materials are managed as disposable fill, I/We agree to be responsible for any subsequent relocation and management of the material so placed. Where materials are to be stockpiled, I/We agree that the stockpile(s) will be removed by the date(s) herein noted. Dated this day of 20 Print Contractor's Name and Field Representative's Name Contractor's Field Representative Signature		being the <u>Own</u>	<u>er</u> (s) of Lot	, Concession	,
the Contractor for the above-noted work has placed excess material from the above noted Contract on my/our property with my/our permission. I/we have been advised by the Contractor of the "Conditions on Management" described in OPS Forms 1800 or 1801, "Site Selection Notification for Management as Disposable Fill", or "Site Selection Notification for Materials Stockpiling", respectively, or both, and have been assured by the Contractor that these conditions have been met. Where materials are managed as disposable fill, I/We agree to be responsible for any subsequent relocation and management of the material so placed. Where materials are to be stockpiled, I/We agree that the stockpile(s) will be removed by the date(s) herein noted. Dated this day of 20 Print Contractor's Name and Field Representative's Name Contractor's Field Representative Signature	Township of	, and County/I	Region/District of	, verify tha	t
Where materials are managed as disposable fill, I/We agree to be responsible for any subsequent relocation and management of the material so placed. Where materials are to be stockpiled, I/We agree that the stockpile(s) will be removed by the date(s) herein noted. Dated this day of 20	the Contractor for the above-noted work h with my/our permission. I/we have been at OPS Forms 1800 or 1801, "Site Selection Notification for Materials Stockpiling", re conditions have been met.	as placed excess r dvised by the Con Notification for N espectively, or both	naterial from the above tractor of the "Conditio Management as Disposa h, and have been assure	e noted Contract on my/our pro ons on Management" describe able Fill", or "Site Selection and by the Contractor that these	operty d in
Where materials are to be stockpiled, I/We agree that the stockpile(s) will be removed by the date(s) herein noted. Dated this day of 20 Print Contractor's Name and Field Representative's Name Contractor's Field Representative Signature	Where materials are managed as disposabl management of the material so placed.	le fill, I/We agree	to be responsible for a	ny subsequent relocation and	
Dated this day of 20 Print Contractor's Name and Field Representative's Name Contractor's Field Representative Signature	Where materials are to be stockpiled, I/We	e agree that the sto	ockpile(s) will be remo	ved by the date(s) herein notec	1.
Contractor's Field Representative Signature	Dated this day of	20	Print Contractor's Name	and Field Representative's Name	
			Contractor's Field Repre	esentative Signature	
Property <u>Owner</u> (s) Signature(s)			Property <u>Owner(s)</u> Sign	ature(s)	
cc: Contract Administrator, Property <u>Owner(s)</u> , Contractor OPSF 1803	cc: Contract Administrator, Property <u>Owner(s)</u> , Con	tractor		OPSF 1803	

ITEM SPECIAL PROVISIONS FOR SITE WORK

PREPARATION OF SITE - Item No. 1

O.P.S.S. 201 and 510 shall apply to the work under this item except that the Measurement and Basis of Payment provisions thereof shall be amended in that the lump sum price shall be full compensation for the supply of all labour, equipment and material to perform the work.

The Contractor shall base his bid solely on the findings of his site investigation. Any information given hereafter is approximate only.

For the Tendered Price for the above item the Contractor shall perform the following work.

Clearing and Grubbing

Clearing and grubbing shall be done within the right-of-way limits except for those trees indicated on the Contract Drawings which are not to be disturbed or any others designated by the Engineer to be retained.

Where it is impractical to remove tree stumps, the Engineer may direct the Contractor to use a chipping machine in lieu of grubbing. The tree trunks shall be cut off a minimum of 100 mm below adjacent ground level.

All cleared and grubbed material shall be disposed of off site at locations arranged for by and at the expense of the Contractor.

Erosion and Sediment Control

This item shall include all labour, equipment and materials to construct the facilities as shown on the Contract Drawings and to remove and dispose of them upon completion of construction when revegetation has been achieved.

EARTH EXCAVATION (GRADING) – Item No. 2

For the tender price bid for the above item, the Contractor shall excavate and dispose of all pavement, granular, earth and concrete materials for the construction of driveways, parking lot, building, septic system and ditches to the lines and grades shown on the Drawings and as directed by the Engineer.

The cost of the removal and disposal of bituminous pavement shall be deemed to be included in the tender price for the above item.

O.P.S.S. 206 and 510 shall apply to the work under this item except that the Measurement and Basis of Payment provisions thereof shall be amended in that the lump sum price shall be full compensation for the supply of all labour, equipment and material to perform the work regardless of actual quantities of excavation.

HOT MIX H.L. 3 – Item No. 3

Recycled Hot Mix

Reclaimed asphaltic concrete may be used provided the resultant mix design conforms to the requirements of O.P.S.S. 1150.

Deletion of Slab as Aggregate

The use of slag as an aggregate in the manufacture and supply of hot mix asphalt is prohibited.

150mm DIA. WATERMAIN - Item No. 4

The tendered price shall include the cost of excavation, complete installation and backfilling of the watermain including installation of all sleeves, bends, tees, reducers, anodes, and any special fittings required to complete the installation. The installation of a fire hydrant as per drawing details to be included in item. The watermain to be installed in accordance with Water Fill Station Detail Figure 8 on Drawing C1.

GRANULAR 'B' TYPE II (MODIFIED) – Item No. 6

The gradation requirements of O.P.S.S. 1010 shall apply to this item except that the maximum size particle shall be 75 mm.

END OF SECTION

	/ LOAD:	Ss = 2. Sr = 0.4	2 kPa 4 kPa					
ROOF:	DEAD LOAD SNOW LOAD	Is = 1.0 = = 2	0 1.0 kPa 2.48 kPa * REFEF	R TO DRIFT L	OAD			
FLOOR LOADS:	DEAD LOAD	=	2.87 kPa					
WIND LOAD:	LIVE LOAD q $(1/50) = 0.41$ k	= Pa	4.78 kPa (INCLU	DING EXITS)				
SEISMIC:	Iw = 1.0 Sa (0.2)= 0.62	Sa (1.0	(0) = 0.14	PGA= 0.31				
	Sa (0.5)= 0.31 SITE CLASS: "C	Sa (2.0 " ASSUMED)= 0.046	1e = 1.0				
CODE. FACTOR	CADS TO INCLUDE RED LOADS SHOW	E POINT LOAD N ON DRAWIN	GS USE LOAD F	'S AS PER AR 'ACTORS LL =	TICLE 4.1.6. = 1.5 AND DI	L = 1.25 PEF	2012 ONTARIO R ONTARIO BUI	BUILDING ILDING CODE.
ONCRETE:								
TEST CONCRET CONCRETE REQ	NCRETE ELEMENTS E IN ACCORDANC QUIREMENTS:	S SHALL CONF E WITH CSA-A	70RM TO CSA-A 23.3-14.	.23.3-14. PRO	VIDE CONC.	RETE AND	PERFORM WO	RK TO CSA A23.3-14.
LOCATION CONDITION	MIN. DESI Mpa = TYP C = COMP F= FLFXU	GN STR. YE (DAYS) RESSION RAL	<u>CEMENT</u>	<u>AIR</u> <u>M</u> (%)	<u>AX AGG.</u> (mm)	EXP.	<u>SLUMP</u>	
INT. SLAB ON	GRADE 25C (28)	NAL	GU	5-8	20	N	40mm	
EXTEDIOD EX	POSED CONC	35() (28)		GU	5 8	20	C 1	80mm +/ 30mm
- WHERE SPEC	IFIED STRENGTH I	EXCEED THOS	E IMPLIED BY E	EXPOSURE CI	J-8 LASS, SPECI	20 FIED STRE	NGTH GOVERN	80mm +/- 30mm NS.
 ALL CONCRE WATER CEMI DO NOT USE NORMAL POF 	TE TO BE NORMAI ENT RATIOS FOR E ANY ADMIXTURE RTLAND CEMENT	L WEIGHT 2400 XPOSURE CLA CONTAINING FO BE USED FO) KG/CUBIC ME ASSES AS PER T. CHLORIDE FOR DR CONCRETE.	TER ABLES 7 - 9, 0 . CONCRETE `	CAN/CSA-A2 WITH S-2 EX	3.1-14. Posure.		
CONTROL JOIN UNLESS OTHER	TS FOR SLAB ON G WISE NOTED.	RADE: SAWCU	UT AT LOCATIO	NS SHOWN (ON DRAWIN	GS BUT NO	T EXCEEDING	15'-0" SPACING.
NO COLUMN OI OR WALLS.	R WALL FORMS SH	IALL BE REMC	OVED BEFORE C	CONCRETE HA	AS REACHEI	O 10 Mpa F0	OR ARCHITECT	URAL CONCRETE AND 8 Mpa FOR OTHER COLUMNS
NO SLAB FORM	S OR BEAM FORM	S SHALL BE RI	EMOVED BEFOI	RE CONCRET	E HAS REAG	CHED 17 MJ	ba.	
STRENGTH OF C ENGINEER, MA	CONCRETE FOR ST Y BE USED.	RIPPING TO BI	E DETERMINED	BY FIELD-C	URED CYLIN	DERS. AL	TERNATE MET	HODS, IF ACCEPTABLE TO THE STRUCTURAL DESIG
,								
RESHORING TO	BE APPROVED BY	THE ENGINEI	ER PRIOR TO ST	RIPPING.				
RESHORING TO CONCRETE SLA BLANKETS (WH	BE APPROVED BY BS SHALL BE WET IITE). SUBSTITUTIO	THE ENGINEI CURED FOR N ONS ARE NOT	ER PRIOR TO ST NO LESS THAN ' PERMITTED.	TRIPPING. 7 DAYS, WET	CURING SH	ALL BE CO	OMPLETED WIT	TH TERRAFIX 240R NON-WOVEN GEOTEXTILE
RESHORING TO CONCRETE SLA BLANKETS (WH). ALL SLABS, BE	BE APPROVED BY BS SHALL BE WET IITE). SUBSTITUTIO AMS, GIRDERS, ET	THE ENGINE CURED FOR N ONS ARE NOT C. TO BE SHOP	ER PRIOR TO ST NO LESS THAN ' PERMITTED. RED UNTIL CON	TRIPPING. 7 DAYS, WET CRETE REAC	CURING SH	ALL BE CO	OMPLETED WIT	TH TERRAFIX 240R NON-WOVEN GEOTEXTILE
RESHORING TO CONCRETE SLA BLANKETS (WH). ALL SLABS, BE I. BE RESPONSIBI AND CONSULT PLACEMENT.	BE APPROVED BY BS SHALL BE WET IITE). SUBSTITUTIO AMS, GIRDERS, ET LE FOR THE MIX D GENERAL CONTR.	THE ENGINE CURED FOR N ONS ARE NOT C. TO BE SHOF ESIGN. MIX D ACTOR TO DET	ER PRIOR TO ST NO LESS THAN ' PERMITTED. RED UNTIL CON ESIGN SHALL B FERMINE REQU	RIPPING. 7 DAYS, WET CRETE REAC E PROPORTIO IREMENTS.	CURING SH CHES DESIG ONED WITH ADMIXTURI	ALL BE CO N STRENG DUE CONS ES AND AD	OMPLETED WIT TH. SIDERATION TO DITIVES SHAL	TH TERRAFIX 240R NON-WOVEN GEOTEXTILE D EXTREME TEMPERATURES - WINTER OR SUMMER L BE APPROVED BY THE ENGINEER PRIOR TO
RESHORING TO CONCRETE SLA BLANKETS (WH). ALL SLABS, BE 1. BE RESPONSIBI AND CONSULT PLACEMENT. EINFORCING NOT	BE APPROVED BY BS SHALL BE WET IITE). SUBSTITUTIO AMS, GIRDERS, ET LE FOR THE MIX D GENERAL CONTRA	THE ENGINE CURED FOR N ONS ARE NOT C. TO BE SHOF ESIGN. MIX D ACTOR TO DET	ER PRIOR TO ST NO LESS THAN ' PERMITTED. RED UNTIL CON ESIGN SHALL B FERMINE REQU	RIPPING. 7 DAYS, WET CRETE REAC E PROPORTIO IREMENTS.	CURING SH CHES DESIG ONED WITH ADMIXTURI	ALL BE CO N STRENG DUE CONS S AND AD	OMPLETED WIT TH. SIDERATION TO DITIVES SHAL	TH TERRAFIX 240R NON-WOVEN GEOTEXTILE O EXTREME TEMPERATURES - WINTER OR SUMMER L BE APPROVED BY THE ENGINEER PRIOR TO
RESHORING TO CONCRETE SLA BLANKETS (WH). ALL SLABS, BE 1. BE RESPONSIBI AND CONSULT PLACEMENT. EINFORCING NOT REINFORCING S CONFORM TO C	BE APPROVED BY BS SHALL BE WET IITE). SUBSTITUTIO AMS, GIRDERS, ET LE FOR THE MIX D GENERAL CONTRA TES: STEEL: NEW DEFO CAN/CSA G30.18-09,	THE ENGINE CURED FOR N ONS ARE NOT C. TO BE SHOF ESIGN. MIX D ACTOR TO DE ACTOR TO DE ORMED BARS T , GRADE 400W.	ER PRIOR TO ST NO LESS THAN ' PERMITTED. RED UNTIL CON ESIGN SHALL B FERMINE REQU	TRIPPING. 7 DAYS, WET ICRETE REAC BE PROPORTIO IREMENTS. 9 (R2014), "BI IS TO ASTM 4	CURING SH CHES DESIG ONED WITH ADMIXTURI LLET STEEI A307. EPOX	ALL BE CO N STRENG DUE CONS S AND AD BARS FOR Y COATED	OMPLETED WIT TH. SIDERATION TO DITIVES SHAL R CONCRETE R REBAR TO AS	TH TERRAFIX 240R NON-WOVEN GEOTEXTILE D EXTREME TEMPERATURES - WINTER OR SUMMER L BE APPROVED BY THE ENGINEER PRIOR TO EINFORCEMENT", GRADE 400R, BARS TO BE WELDE TM A775. PLACE REBAR TO CAN/CSA-A23.1-14.
RESHORING TO CONCRETE SLA BLANKETS (WH). ALL SLABS, BE 1. BE RESPONSIBI AND CONSULT PLACEMENT. EINFORCING NOT REINFORCING S CONFORM TO C PROVIDE CLEA	BE APPROVED BY BS SHALL BE WET IITE). SUBSTITUTIO AMS, GIRDERS, ET LE FOR THE MIX D GENERAL CONTRA IES: STEEL: NEW DEFO CAN/CSA G30.18-09, R CONCRETE COV	THE ENGINE CURED FOR N ONS ARE NOT C. TO BE SHOF ESIGN. MIX D ACTOR TO DE MED BARS T GRADE 400W. ER OVER REBA	ER PRIOR TO ST NO LESS THAN ' PERMITTED. RED UNTIL CON ESIGN SHALL B FERMINE REQU O CSA/G30.18-0 . ANCHOR BOLT AR AS FOLLOW	TRIPPING. 7 DAYS, WET CRETE REAC E PROPORTIO IREMENTS. 9 (R2014), "BI IS TO ASTM S:	CURING SECTES DESIGNED WITH ADMIXTURI LLET STEEL A307. EPOX	ALL BE CO N STRENG DUE CONS S AND AD BARS FOR Y COATED	OMPLETED WIT TH. GIDERATION TO DITIVES SHAL R CONCRETE R REBAR TO AS	TH TERRAFIX 240R NON-WOVEN GEOTEXTILE O EXTREME TEMPERATURES - WINTER OR SUMMER L BE APPROVED BY THE ENGINEER PRIOR TO EINFORCEMENT", GRADE 400R, BARS TO BE WELDE TM A775. PLACE REBAR TO CAN/CSA-A23.1-14.
RESHORING TO CONCRETE SLA BLANKETS (WH). ALL SLABS, BE 1. BE RESPONSIBI AND CONSULT PLACEMENT. EINFORCING NOT REINFORCING S CONFORM TO C PROVIDE CLEA A) SURFACE P B) FORMED SU C) FORMED SU BEAL COLU	BE APPROVED BY BS SHALL BE WET IITE). SUBSTITUTIO AMS, GIRDERS, ET LE FOR THE MIX D GENERAL CONTR. IES: STEEL: NEW DEFO CAN/CSA G30.18-09, R CONCRETE COV OURED AGAINST O URFACES EXPOSEI URFACES NOT EXF MS (TO STIRRUPS) UMNS (TO VERTIC 35 WALLS	THE ENGINE CURED FOR N ONS ARE NOT C. TO BE SHOF ESIGN. MIX D ACTOR TO DET RMED BARS T GRADE 400W. ER OVER REBA GROUND D TO GROUND D TO GROUND O SED TO GROUND ALS)	ER PRIOR TO ST NO LESS THAN ' PERMITTED. RED UNTIL CON ESIGN SHALL B FERMINE REQU O CSA/G30.18-0 . ANCHOR BOLT AR AS FOLLOW	TRIPPING. 7 DAYS, WET ICRETE REAC E PROPORTIO IREMENTS. 9 (R2014), "BI IS TO ASTM S: 75 mr 40 mr HER: 40 mr 50 mr 20 mr	CURING SH CHES DESIG ONED WITH ADMIXTURI LLET STEEL A307. EPOX	ALL BE CO N STRENG DUE CONS S AND AD BARS FOR Y COATED	OMPLETED WIT FH. GIDERATION TO DITIVES SHAL	TH TERRAFIX 240R NON-WOVEN GEOTEXTILE O EXTREME TEMPERATURES - WINTER OR SUMMER L BE APPROVED BY THE ENGINEER PRIOR TO EINFORCEMENT", GRADE 400R, BARS TO BE WELDE TM A775. PLACE REBAR TO CAN/CSA-A23.1-14.
RESHORING TO CONCRETE SLA BLANKETS (WH). ALL SLABS, BE 1. BE RESPONSIBI AND CONSULT PLACEMENT. EINFORCING NOT REINFORCING S CONFORM TO C PROVIDE CLEA A) SURFACE P B) FORMED SU C) FORMED SU BEAL COLU SLAF D) PARKING S	BE APPROVED BY BS SHALL BE WET IITE). SUBSTITUTION AMS, GIRDERS, ET LE FOR THE MIX D GENERAL CONTRA TES: STEEL: NEW DEFO CAN/CSA G30.18-09, R CONCRETE COV OURED AGAINST O JURFACES EXPOSEI JURFACES EXPOSEI JURFACES NOT EXP MS (TO STIRRUPS) UMNS (TO VERTIC 3S, WALLS URFACES AND EX	THE ENGINE CURED FOR N ONS ARE NOT C. TO BE SHOF ESIGN. MIX D ACTOR TO DET RMED BARS T GRADE 400W. ER OVER REBA GROUND D TO GROUND O TO GROUND O TO GROUND O TO GROUND O TO GROUND O TO GROUND	ER PRIOR TO ST NO LESS THAN ' PERMITTED. RED UNTIL CON ESIGN SHALL B FERMINE REQU CO CSA/G30.18-0 . ANCHOR BOLT AR AS FOLLOW OR WEATHER OUND OR WEATHER	TRIPPING. 7 DAYS, WET ICRETE REAC E PROPORTIO IREMENTS. 9 (R2014), "BI IS TO ASTM S: 75 mr 40 mr HER: 40 mr 50 mr 20 mr 40 mr	CURING SECUES DESIGNONED WITH ADMIXTURI LLET STEEL A307. EPOX n n n n	ALL BE CO N STRENG DUE CONS S AND AD BARS FOR Y COATED	OMPLETED WIT	TH TERRAFIX 240R NON-WOVEN GEOTEXTILE O EXTREME TEMPERATURES - WINTER OR SUMMER L BE APPROVED BY THE ENGINEER PRIOR TO EINFORCEMENT", GRADE 400R, BARS TO BE WELDE TM A775. PLACE REBAR TO CAN/CSA-A23.1-14.
RESHORING TO CONCRETE SLA BLANKETS (WH). ALL SLABS, BE 1. BE RESPONSIBI AND CONSULT PLACEMENT. EINFORCING NOT REINFORCING S CONFORM TO C PROVIDE CLEA A) SURFACE P B) FORMED SU C) FORMED SU BEAI COLU SLAF D) PARKING S	BE APPROVED BY BS SHALL BE WET IITE). SUBSTITUTION AMS, GIRDERS, ET LE FOR THE MIX D GENERAL CONTRA DES: STEEL: NEW DEFO CAN/CSA G30.18-09, R CONCRETE COV OURED AGAINST O JURFACES EXPOSEI JURFACES EXPOSEI JURFACES EXPOSEI JURFACES AND EXE WORK TO BE INSPI THE INSPECTION.	THE ENGINE CURED FOR N ONS ARE NOT C. TO BE SHOF ESIGN. MIX D ACTOR TO DET RMED BARS T GRADE 400W. ER OVER REBA GROUND D TO GROUND O TO GROUND	ER PRIOR TO ST NO LESS THAN ' PERMITTED. RED UNTIL CON ESIGN SHALL B FERMINE REQU O CSA/G30.18-0 . ANCHOR BOLT AR AS FOLLOW OR WEATHER OUND OR WEATHER OF SLAB: E ENGINEER. NO	TRIPPING. 7 DAYS, WET 7 CRETE REAC 9 (R2014), "BI 10 (R2014), "BI 11 (S TO ASTM A) 12 (R2014), "BI 13 (S TO ASTM A) 14 (D m) 14 (D m) 15 (S (D m)) 16 (R m) 17 (D m) 18 (D m) 19 (R2014), "BI 19 (R2014), "BI 10 (R m) 11 (R m) 12 (R m) 13 (R m) 14 (R m) 15 (R m) 16 (R m) 17 (R m) 18 (R m) 19 (R m) 10 (R m) 11 (R m) 12 (R m) 13 (R m) 14 (R m) 14 (R m)	CURING SECHES DESIG ONED WITH ADMIXTURI LLET STEEL A307. EPOX n n n n n NGINEER 24	ALL BE CO N STRENG DUE CONS S AND AD BARS FOR Y COATED	OMPLETED WIT FH. SIDERATION TO DITIVES SHAL & CONCRETE R REBAR TO AST	TH TERRAFIX 240R NON-WOVEN GEOTEXTILE O EXTREME TEMPERATURES - WINTER OR SUMMER L BE APPROVED BY THE ENGINEER PRIOR TO EINFORCEMENT", GRADE 400R, BARS TO BE WELDE TM A775. PLACE REBAR TO CAN/CSA-A23.1-14.
RESHORING TO CONCRETE SLA BLANKETS (WH). ALL SLABS, BE 1. BE RESPONSIBI AND CONSULT PLACEMENT. EINFORCING NOT REINFORCING S CONFORM TO C PROVIDE CLEA A) SURFACE P B) FORMED SU C) FORMED SU BEAI COLU SLAF D) PARKING S REINFORCING V IN PLACE FOR T REBAR LAP SPI BAR SIZE COM	BE APPROVED BY BS SHALL BE WET IITE). SUBSTITUTION AMS, GIRDERS, ET LE FOR THE MIX D GENERAL CONTRA TES: STEEL: NEW DEFO CAN/CSA G30.18-09. R CONCRETE COV OURED AGAINST URFACES EXPOSED URFACES EXPOSED URFACES NOT EXE MS (TO STIRRUPS) UMNS (TO VERTIC 3S, WALLS URFACES AND EX WORK TO BE INSPECTION. LICE LENGTHS (UN MP. TENSIO	THE ENGINEI CURED FOR N ONS ARE NOT C. TO BE SHOF ESIGN. MIX D ACTOR TO DET ACTOR TO DET GRADE 400W. ER OVER REBA GROUND D TO GROUND D TO GROUND O TO GROUND O TO GROUND O TO GROUND D TO G TO	ER PRIOR TO ST NO LESS THAN ' PERMITTED. RED UNTIL CON ESIGN SHALL B TERMINE REQU O CSA/G30.18-0 . ANCHOR BOLT AR AS FOLLOW OR WEATHER OUND OR WEAT OF SLAB: E ENGINEER. NO ON DRAWINGS) ASS B" FOR	RIPPING. 7 DAYS, WET 1 CRETE REAC 1 CRETE REAC 1 CRETE REAC 1 CRETE REAC 1 CRETE REAC 1 CRETE REAC 1 CRETE 1 CR	CURING SECUES DESIGNONED WITH ADMIXTURE LLET STEEL A307. EPOX n n n n NGINEER 24	ALL BE CO N STRENG DUE CONS S AND AD BARS FOR Y COATED HOURS IN	OMPLETED WIT FH. SIDERATION TO DITIVES SHAL & CONCRETE R REBAR TO AS	TH TERRAFIX 240R NON-WOVEN GEOTEXTILE D EXTREME TEMPERATURES - WINTER OR SUMMER L BE APPROVED BY THE ENGINEER PRIOR TO EINFORCEMENT", GRADE 400R, BARS TO BE WELDE TM A775. PLACE REBAR TO CAN/CSA-A23.1-14.
RESHORING TO CONCRETE SLA BLANKETS (WH). ALL SLABS, BE AND CONSULT PLACEMENT. EINFORCING NOT REINFORCING NOT REINFORCING S CONFORM TO C PROVIDE CLEA A) SURFACE P B) FORMED SU C) FORMED SU C) FORMED SU C) FORMED SU BEAL COLU SLAF D) PARKING S REINFORCING V IN PLACE FOR T REBAR LAP SPL <u>BAR SIZE</u> CON SPL	BE APPROVED BY BS SHALL BE WET IITE). SUBSTITUTION AMS, GIRDERS, ET LE FOR THE MIX D GENERAL CONTRA- IES: STEEL: NEW DEFO CAN/CSA G30.18-09 R CONCRETE COV OURED AGAINST O URFACES EXPOSED URFACES NOT EXF MS (TO STIRRUPS) UMNS (TO VERTICA 3S, WALLS URFACES AND EX WORK TO BE INSPI THE INSPECTION. LICE LENGTHS (UN MP. <u>TENSIO</u>	THE ENGINEI CURED FOR N ONS ARE NOT C. TO BE SHOF ESIGN. MIX DI ACTOR TO DET ORMED BARS T GRADE 400W. ER OVER REBA GROUND D TO GROUND D TO GROUND O GROUND O GROUND D TO GROUND O GR	ER PRIOR TO ST NO LESS THAN ' PERMITTED. RED UNTIL CON ESIGN SHALL B TERMINE REQU CO CSA/G30.18-0 . ANCHOR BOLT AR AS FOLLOW OR WEATHER DUND OR WEATHER DUND OR WEATHER DUND OR WEATHER DUND OR WEATHER DUND OR WEATHER DUND OR WEATHER DON DRAWINGS) <u>ASS B"</u> <u>FOR</u> <u>2</u>	RIPPING. 7 DAYS, WET 7 DAYS, WET 10 CRETE REAC 10 E PROPORTION 11 IREMENTS. 9 (R2014), "BI 11 STO ASTM 9 (R2014), "BI 12 STO ASTM 9 (R2014), "BI 13 STO ASTM 9 (R2014), "BI 13 STO ASTM 9 (R2014), "BI 14 STO ASTM 9 (R2014), "BI 15 STO ASTM 9 (R2014), "BI 15 STO ASTM 40 mi 20 mi 40 mi 20 m	CURING SECUES DESIG CHES DESIG ONED WITH ADMIXTURI LLET STEEL A307. EPOX n n n n NGINEER 24 <u>STRENGTHS</u> <u>40 M</u>	ALL BE CO N STRENG DUE CONS S AND AD BARS FOR Y COATED HOURS IN G (mm) Da 20)	OMPLETED WIT TH. SIDERATION TO DITIVES SHAL R CONCRETE R REBAR TO AS ADVANCE. CO	TH TERRAFIX 240R NON-WOVEN GEOTEXTILE O EXTREME TEMPERATURES - WINTER OR SUMMEF L BE APPROVED BY THE ENGINEER PRIOR TO EINFORCEMENT", GRADE 400R, BARS TO BE WELDE TM A775. PLACE REBAR TO CAN/CSA-A23.1-14.
RESHORING TO CONCRETE SLA BLANKETS (WH). ALL SLABS, BE 1. BE RESPONSIBI AND CONSULT PLACEMENT. EINFORCING NOT REINFORCING NOT REINFORCING S CONFORM TO C PROVIDE CLEA A) SURFACE P B) FORMED SU C) FORMED SU C) FORMED SU C) FORMED SU BEAN COLU SLAF D) PARKING S REINFORCING V IN PLACE FOR T REBAR LAP SPI <u>BAR SIZE</u> <u>CON</u> SPL 10M 330 15M 480 20M 580 25M 740	BE APPROVED BY BS SHALL BE WET IITE). SUBSTITUTION AMS, GIRDERS, ET LE FOR THE MIX D GENERAL CONTRA EES: STEEL: NEW DEFO CAN/CSA G30.18-09, R CONCRETE COV OURED AGAINST URFACES EXPOSEI JRFACES EXPOSEI JRFACES NOT EXE MS (TO STIRRUPS) UMNS (TO VERTIC 3S, WALLS URFACES AND EX WORK TO BE INSPI THE INSPECTION. JICE LENGTHS (UN <u>MP. TENSIO</u> <u>170</u> 430 610 740 1170	THE ENGINEI CURED FOR N ONS ARE NOT C. TO BE SHOF ESIGN. MIX DI ACTOR TO DET ORMED BARS T GRADE 400W. ER OVER REBA GROUND D TO GROUND O TO G TO	ER PRIOR TO ST NO LESS THAN ' PERMITTED. RED UNTIL CON ESIGN SHALL B TERMINE REQU 'O CSA/G30.18-0 . ANCHOR BOLT AR AS FOLLOW OR WEATHER OUND OR WEATHER OUND OR WEATHER OUND OR WEATHER OUND OR WEATHER ON DRAWINGS) <u>ASS B"</u> FOR a 10) '90) 65) 1400)	TRIPPING. 7 DAYS, WET 7 CRETE REAC 9 (R2014), "BI 1REMENTS. 9 (R2014), "BI 75 TO ASTM 8: 75 mr 40 mi 50 mi 20 mi 40 mi 510 (600) 510 (660) 610 (815) 990 (1295)	CURING SECUES DESIGNONED WITH ADMIXTURI LLET STEEL A307. EPOX n n n NGINEER 24 <u>STRENGTHS</u> <u>40 MJ</u> 330 (4 880 (7 940 (1)	ALL BE CO N STRENG DUE CONS S AND AD BARS FOR Y COATED HOURS IN HOURS IN 30) 510) 60) 220)	OMPLETED WIT FH. SIDERATION TO DITIVES SHAL & CONCRETE R REBAR TO AST	TH TERRAFIX 240R NON-WOVEN GEOTEXTILE D EXTREME TEMPERATURES - WINTER OR SUMMER L BE APPROVED BY THE ENGINEER PRIOR TO EINFORCEMENT", GRADE 400R, BARS TO BE WELDE TM A775. PLACE REBAR TO CAN/CSA-A23.1-14.
RESHORING TO CONCRETE SLA BLANKETS (WH). ALL SLABS, BE 1. BE RESPONSIBI AND CONSULT PLACEMENT. EINFORCING NOT REINFORCING NOT REINFORCING S CONFORM TO C PROVIDE CLEA A) SURFACE P B) FORMED SU C) FORMED SU C) FORMED SU C) FORMED SU BEAI COLU SLAF D) PARKING S REINFORCING V IN PLACE FOR T REBAR LAP SPL <u>BAR SIZE</u> <u>CON</u> <u>SPL</u> 10M 330 15M 480 20M 580 25M 740	BE APPROVED BY BS SHALL BE WET IITE). SUBSTITUTION AMS, GIRDERS, ET LE FOR THE MIX D GENERAL CONTRA- STEEL: NEW DEFO CAN/CSA G30.18-09. R CONCRETE COV OURED AGAINST O URFACES EXPOSE URFACES EXPOSE URFACES NOT EXF MS (TO STIRRUPS) UMNS (TO VERTIC 3S, WALLS URFACES AND EX WORK TO BE INSPECTION. LICE LENGTHS (UN MP. <u>TENSIO</u> TICES (mm) <u>25 M</u> 430 610 740 1170 E LENGTHS ARE D CRETE POURED BE	THE ENGINEI CURED FOR N ONS ARE NOT C. TO BE SHOF ESIGN. MIX DI ACTOR TO DET ORMED BARS T GRADE 400W. ER OVER REBA GROUND D TO GROUND D TO GROUND D TO GROUND O TO GROUND O TO GROUND O TO GROUND D TO GROUND O TO GROUND D TO GROUND O SED TO GRO ALS) TERIOR TOP O ECTED BY THE LESS NOTED O ON SPLICE "CL Mpa 30 Mp (560) 380 (51 (790) 535 (7 (940) 660 (86 0 (1525) 1065 (1 DENOTED IN BH ELOW THE BAR	ER PRIOR TO ST NO LESS THAN ' PERMITTED. RED UNTIL CON ESIGN SHALL B TERMINE REQU 'O CSA/G30.18-0 . ANCHOR BOLT AR AS FOLLOW OR WEATHER OUND OR WEATHER OUND OR WEATHER OUND OR WEATHER OUND OR WEATHER OUND OR WEATHER ON DRAWINGS) <u>ASS B" FOR</u> a 10) (90) 65) 1400) RACKETS AND S R.	TRIPPING. 7 DAYS, WET 7 CRETE REAC 9 (R2014), "BI IREMENTS. 9 (R2014), "BI 75 mr 40 mr 50 mr 40 mr 50 mr 20 mr 40 mr 510 iFY THE EI 8 CONCRETE 360 (460) 510 (660) 610 (815) 990 (1295) SHOULD BE U	CURING SECUES DESIGNONED WITH ADMIXTURE LLET STEEL A307. EPOX n n n NGINEER 24 <u>STRENGTHS</u> <u>40 MJ</u> 330 (4 480 (6 580 (7 940 (1) JSED WHEN	ALL BE CO N STRENG DUE CONS S AND AD BARS FOR Y COATED HOURS IN <u>5 (mm)</u> Da 30) 100 60) 220) HORIZON	OMPLETED WIT TH. SIDERATION TO DITIVES SHAL R CONCRETE R REBAR TO AST ADVANCE. CO TAL SPLICE BA	CH TERRAFIX 240R NON-WOVEN GEOTEXTILE D EXTREME TEMPERATURES - WINTER OR SUMMER L BE APPROVED BY THE ENGINEER PRIOR TO EINFORCEMENT", GRADE 400R, BARS TO BE WELDE TM A775. PLACE REBAR TO CAN/CSA-A23.1-14.
RESHORING TO CONCRETE SLA BLANKETS (WH). ALL SLABS, BEA AND CONSULT PLACEMENT. EINFORCING NOT REINFORCING NOT REINFORCING S CONFORM TO C PROVIDE CLEA A) SURFACE P B) FORMED SU C) FORMED SU C) FORMED SU C) FORMED SU BEAL COLU SLAF D) PARKING S REINFORCING V IN PLACE FOR T REBAR LAP SPI <u>BAR SIZE</u> <u>CON</u> <u>SPL</u> 10M 330 15M 480 20M 580 25M 740 TOP BAR SPLIC 300mm OF CONO REBAR EMBED	BE APPROVED BY BS SHALL BE WET IITE). SUBSTITUTION AMS, GIRDERS, ET LE FOR THE MIX D GENERAL CONTRA IES: STEEL: NEW DEFO CAN/CSA G30.18-09, R CONCRETE COV OURED AGAINSTO URFACES EXPOSED URFACES EXPOSED URFACES NOT EXF MS (TO STIRRUPS) UMNS (TO VERTICA 3S, WALLS URFACES AND EX WORK TO BE INSPH THE INSPECTION. LICE LENGTHS (UN MP. TENSIO ICES (mm) 430 610 740 1170 E LENGTHS ARE D CRETE POURED BE MENT LENGTHS (U	THE ENGINEI CURED FOR N ONS ARE NOT C. TO BE SHOF ESIGN. MIX D ACTOR TO DET RMED BARS T GRADE 400W. ER OVER REBA GROUND D TO GROUND D TO GROUND C TO GROUND D TO GROUND D TO GROUND D TO GROUND C TO GROUND D TO GROUND C TO GROUND D TO G	ER PRIOR TO ST NO LESS THAN ' PERMITTED. RED UNTIL CON ESIGN SHALL B FERMINE REQU CO CSA/G30.18-0 . ANCHOR BOLT AR AS FOLLOW OR WEATHER OUND OR WEATHER OUND OR WEATHER OUND OR WEATHER OUND OR WEATHER OUND OR WEATHER ON DRAWINGS) <u>ASS B" FOR</u> 1 10) (90) 65) 1400) RACKETS AND S R. D ON DRAWING	RIPPING. 7 DAYS, WET 7 CRETE REAC 9 (R2014), "BI IREMENTS. 9 (R2014), "BI 75 mr 40 mr 50 mr 40 mr 50 mr 20 mr 40 mr 50 mr 30 mr 0TIFY THE EI 2 CONCRETE 360 (460) 510 (660) 610 (815) 990 (1295) SHOULD BE U (S)	CURING SH CHES DESIG ONED WITH ADMIXTURI LLET STEEL A307. EPOX n n n NGINEER 24 <u>STRENGTHS</u> <u>40 MJ</u> 330 (4 480 (6 580 (7 940 (1) JSED WHEN	ALL BE CO N STRENG ⁷ DUE CONS ES AND AD BARS FOR Y COATED HOURS IN G (mm) Da 30) 10) 60) 220) HORIZON	OMPLETED WIT TH. SIDERATION TO DITIVES SHAL R CONCRETE R REBAR TO AS' ADVANCE. CO TAL SPLICE BA	TH TERRAFIX 240R NON-WOVEN GEOTEXTILE D EXTREME TEMPERATURES - WINTER OR SUMMER L BE APPROVED BY THE ENGINEER PRIOR TO EINFORCEMENT", GRADE 400R, BARS TO BE WELDE TM A775. PLACE REBAR TO CAN/CSA-A23.1-14.
RESHORING TO CONCRETE SLA BLANKETS (WH). ALL SLABS, BE AND CONSULT PLACEMENT. EINFORCING NOT REINFORCING NOT CONFORM TO C PROVIDE CLEA A) SURFACE P B) FORMED SU C) FORMED SU	BE APPROVED BY BS SHALL BE WET IITE). SUBSTITUTION AMS, GIRDERS, ET LE FOR THE MIX D GENERAL CONTRA- DES: STEEL: NEW DEFO CAN/CSA G30.18-09, R CONCRETE COV OURED AGAINST OURED AGAINST OURED AGAINST URFACES EXPOSED URFACES NOT EXEMPS UNFACES NOT EXEMPS UNFACES NOT EXEMPS UNFACES AND EX WORK TO BE INSPICIE S, WALLS URFACES AND EX WORK TO BE INSPICE THE INSPECTION. LICE LENGTHS (UN MP. TENSION INFO DES (mm) 25 M 430 610 740 1170 E LENGTHS ARE D CRETE POURED BE MENT LENGTHS (UN INFOLLENGTHS (UN MENT LENGTHS (UN MENT LENGTHS (UN MENT LENGTHS (UN CONCRETE STREM	THE ENGINEI CURED FOR N ONS ARE NOT C. TO BE SHOF ESIGN. MIX DI ACTOR TO DET ACTOR TO DET GROUND O TO GROUND O TO	ER PRIOR TO ST NO LESS THAN ' PERMITTED. RED UNTIL CON ESIGN SHALL B FERMINE REQU CO CSA/G30.18-0 . ANCHOR BOLT AR AS FOLLOW OR WEATHER OUND OR WEAT OF SLAB: E ENGINEER. NO ON DRAWINGS) <u>ASS B"</u> FOR a 10) 190) 65) 1400) RACKETS AND S R. D ON DRAWING	Tension E $(RIPPING.)$ $(TOAYS, WET)$ $(CRETE REAC)$ $(CRETE REAC)$ $(E PROPORTION E)$ $(REMENTS.)$ $(REMENTS.$	CURING SECURING SECUR	ALL BE CO N STRENG DUE CONS S AND AD BARS FOR Y COATED HOURS IN G (mm) Da 30) 10) 60) 220) HORIZON F (mm) 40 Mpa	OMPLETED WIT TH. SIDERATION TO DITIVES SHAL R CONCRETE R REBAR TO AST ADVANCE. CO TAL SPLICE BA	CH TERRAFIX 240R NON-WOVEN GEOTEXTILE D EXTREME TEMPERATURES - WINTER OR SUMMER L BE APPROVED BY THE ENGINEER PRIOR TO EINFORCEMENT", GRADE 400R, BARS TO BE WELDE TM A775. PLACE REBAR TO CAN/CSA-A23.1-14.
RESHORING TO CONCRETE SLA BLANKETS (WH). ALL SLABS, BE AND CONSULT PLACEMENT. EINFORCING NOT REINFORCING NOT CONFORM TO C PROVIDE CLEA A) SURFACE P B) FORMED SU C) FORMED SU BEAL COLU SLAF D) PARKING S REINFORCING V IN PLACE FOR T REBAR LAP SPL <u>BAR SIZE CON</u> SPL 10M 330 15M 480 20M 580 25M 740 TOP BAR SPLIC 300mm OF CONO REBAR EMBED BAR COM SIZE FOR C	BE APPROVED BY BS SHALL BE WET IITE). SUBSTITUTION AMS, GIRDERS, ET LE FOR THE MIX D GENERAL CONTRANNE GENERAL CONTRANNE STEEL: NEW DEFO CAN/CSA G30.18-09, R CONCRETE COV OURED AGAINSTON URFACES EXPOSED URFACES EXPOSED URFACES NOT EXF MS (TO STIRRUPS) UMNS (TO VERTICANNE) URFACES AND EX WORK TO BE INSPH THE INSPECTION. LICE LENGTHS (UN MP. <u>TENSION</u> (ICE LENGTHS (UN MP. <u>TENSION</u> ICES (mm) <u>25 M</u> 430 610 740 170 E LENGTHS ARE D CRETE POURED BE MENT LENGTHS (UN MENT LENGTHS (UN 0) 230 (280) 200 50) 300 (400) 275 35) 380 (485) 360 10) 485 (635) 450 40) 585 (740) 535 20) 685 (900) 635	THE ENGINEI CURED FOR N ONS ARE NOT C. TO BE SHOF ESIGN. MIX D ACTOR TO DET ACTOR TO DET GROUND D TO GROUND D TO G	ER PRIOR TO ST NO LESS THAN ' PERMITTED. RED UNTIL CON ESIGN SHALL B FERMINE REQU CO CSA/G30.18-0 . ANCHOR BOLT AR AS FOLLOW OR WEATHER OUND OR WEATT OF SLAB: E ENGINEER. NO ON DRAWINGS) <u>ASS B" FOR</u> 10) '90) 65) 1400) RACKETS AND S R. D ON DRAWING SR. D ON DRAWING SR. D ON DRAWING SR.	RIPPING. 7 DAYS, WET 7 CRETE REAC SE PROPORTIGINEMENTS. 9 (R2014), "BI IREMENTS. 9 (R2014), "BI STO ASTM S: 75 mr 40 mr 50 mi 20 mi 40 mi 510 (660) 610 (815) 990 (1295) SHOULD BE U (S) TENSION E R CONCRETE 305 (380) 430 (530) 510 (660) 840 (1070) 90 (1270) 170 (1525)	CURING SECUES DESIG CHES DESIG ONED WITH ADMIXTURE LLET STEEL A307. EPOX n n n NGINEER 24 STRENGTHS 40 MJ 330 (4 480 (6 580 (7 940 (1 JSED WHEN CSTRENGT 35 Mpa 80 (360) 80 (510) 80 (610) 760 (990) 15 (1170) 090 (1420)	ALL BE CO N STRENG ⁷ DUE CONSES AND AD BARS FOR Y COATED HOURS IN S (mm) Da 30) 10) 60) 220) HORIZON F H (mm) 40 Mpa 50 (330) 360 (480) 60 (585) 10 (940) 40 (1120) 1015 (132)	DMPLETED WIT	CH TERRAFIX 240R NON-WOVEN GEOTEXTILE
RESHORING TO CONCRETE SLA BLANKETS (WH). ALL SLABS, BEA AND CONSULT PLACEMENT. EINFORCING NOT REINFORCING NOT CONFORM TO C PROVIDE CLEA A) SURFACE P B) FORMED SU C) FORMED SU C) FORMED SU C) FORMED SU C) FORMED SU C) FORMED SU BEAL COLU SLAH D) PARKING S REINFORCING V IN PLACE FOR T REBAR LAP SPL <u>BAR SIZE CON</u> SPL 10M 330 15M 480 20M 580 25M 740 TOP BAR SPLIC 300mm OF CONO REBAR EMBED BAR COM SIZE FOR CONO REBAR EMBED BAR COM SIZE FOR CONO REBAR EMBED BAR COM SIZE FOR CONO REBAR EMBED BAR SIZE CON CON CONO REBAR EMBED BAR COM SIZE FOR CONO REBAR EMBED CON CONO REBAR COM SIZE FOR CONO CON CONO REBAR EMBED CON CONO REBAR EMBED CON CONO REBAR DEVE CON F THAN 200	BE APPROVED BY BS SHALL BE WET IITE). SUBSTITUTION AMS, GIRDERS, ET LE FOR THE MIX D GENERAL CONTRAN TES: STEEL: NEW DEFON CAN/CSA G30.18-09, R CONCRETE COV OURED AGAINSTON URFACES EXPOSED URFACES EXPOSED URFACES NOT EXF MS (TO STIRRUPS) UMNS (TO VERTICA 3S, WALLS URFACES AND EX WORK TO BE INSPH THE INSPECTION. LICE LENGTHS (UN <u>MP.</u> <u>TENSION</u> ICES (mm) <u>25 N</u> 430 610 740 170 E LENGTHS ARE D CRETE POURED BE MENT LENGTHS (UN MENT LENGTHS (UN 0) 230 (280) 200 50) 300 (400) 275 35) 380 (485) 360 10) 485 (635) 450 40) 585 (740) 535 20) 685 (900) 635 LOPMENT LENGTH	THE ENGINEI CURED FOR N ONS ARE NOT C. TO BE SHOF ESIGN. MIX D ACTOR TO DET ACTOR TO DET GROUND D TO GROUND D TO G	ER PRIOR TO ST NO LESS THAN ' PERMITTED. RED UNTIL CON ESIGN SHALL B FERMINE REQU CO CSA/G30.18-0 . ANCHOR BOLT AR AS FOLLOW OR WEATHER OUND OR WEAT OR WEATHER OUND OR WEAT ON DRAWINGS) <u>ASS B"</u> FOR a 10) '90) 65) 1400) RACKETS AND S R. D ON DRAWINGS EPGE 330 (430) 460 (610) 560 (735) 915 (1170) 1070 (1400) 1295 (1675	TIPPING. 7 DAYS, WET 7 CRETE REAC 8 PROPORTIGINEMENTS. 9 (R2014), "BI 10 REMENTS. 9 (R2014), "BI 11 REMENTS. 9 (R2014), "BI 12 TO ASTM 13 S: 75 mr 40 mr 50 mr 20 mr 40 mr 50 mr 20 mr 40 mr 50 mr 20 mr 40 mr 51 MPa 360 (460) 510 (660) 610 (815) 990 (1295) SHOULD BE U 305 305 (380) 430 (530) 510 (660) 840 (1070) 90 (1270) 170 (1525)	CURING SECUES DESIGNED WITH ADMIXTURI LLET STEEL A307. EPOX n n n NGINEER 24 STRENGTHS 40 MJ 330 (4 480 (6 580 (7 940 (1) JSED WHEN CSTRENGTI 35 Mpa 80 (360) 80 (510) 80 (610) 760 (990) 15 (1170) 090 (1420) ULD BE USE	ALL BE CO N STRENG ⁷ DUE CONS ES AND AD BARS FOR Y COATED HOURS IN S (mm) Da 30) 10) 60) 220) HORIZON F H (mm) 40 Mpa 50 (330) 360 (480) 60 (585) 10 (940) 40 (1120) 1015 (132) D WHEN H	OMPLETED WIT FH. SIDERATION TO DITIVES SHAL & CONCRETE R REBAR TO AS ADVANCE. CO FAL SPLICE BA 0) IORIZONTAL B	CH TERRAFIX 240R NON-WOVEN GEOTEXTILE D EXTREME TEMPERATURES - WINTER OR SUMMER L BE APPROVED BY THE ENGINEER PRIOR TO EINFORCEMENT", GRADE 400R, BARS TO BE WELDE TM A775. PLACE REBAR TO CAN/CSA-A23.1-14.
RESHORING TO CONCRETE SLA BLANKETS (WH). ALL SLABS, BE AND CONSULT PLACEMENT. EINFORCING NOT REINFORCING NOT CONFORM TO CO PROVIDE CLEA A) SURFACE P B) FORMED SU C) FORMED SU SU SU C) FORMED SU SU SU C) FORMED SU SU C) FORMED SU SU SU C) FORMED SU SU SU C) FORMED SU SU SU SU SU SU SU SU SU SU SU SU SU S	BE APPROVED BY BS SHALL BE WET IITE). SUBSTITUTION AMS, GIRDERS, ET LE FOR THE MIX D GENERAL CONTRA DES: STEEL: NEW DEFO CAN/CSA G30.18-09, R CONCRETE COV OURED AGAINST O URFACES EXPOSED URFACES EXPOSED URFACES NOT EXEMNS (TO STIRRUPS) UMNS (TO VERTIC 3S, WALLS URFACES AND EX WORK TO BE INSPI- THE INSPECTION. LICE LENGTHS (UN MP. <u>TENSION</u> (MP. <u>TENSION</u> (ICES (mm) <u>25 M</u> 430 610 740 1170 E LENGTHS ARE D CRETE POURED BE MENT LENGTHS (UN MENT LENGTHS (UN 0) 230 (280) 200 50) 300 (400) 275 35) 380 (485) 360 10) 485 (635) 450 40) 585 (740) 535 00) 685 (900) 635 LOPMENT LENGTHS	THE ENGINEI CURED FOR N ONS ARE NOT C. TO BE SHOF ESIGN. MIX DI ACTOR TO DET ACTOR TO DET GROUND D'OGROUND D'OGROUND D'OGROUND D'OGROUND D'OGROUND D'OGROUND D'OGROUND D'OGROUND D'OGROUND D'OGROUND D'OGROUND D'OGROUND D'OGROUND C'OGROUND D'OGROUND D'OGROUND D'OGROUND D'OGROUND D'OGROUND D'OGROUND D'OGROUND C'OGROUND D'OGROUND C'OGROUND C'OGROUND D'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND C'OGROUND	ER PRIOR TO ST NO LESS THAN $^{\prime}$ PERMITTED. RED UNTIL CON ESIGN SHALL B TERMINE REQU CO CSA/G30.18-0 . ANCHOR BOLT AR AS FOLLOW OR WEATHER OUND OR WEAT OF SLAB: E ENGINEER. NO ON DRAWINGS) ASS B" FOR a 10) 90) 65) 1400) RACKETS AND S R. D ON DRAWING SC ASS B" FOR a 10) 90) 65) 1400) RACKETS AND S R. D ON DRAWING EFOR 25 Mpa 330 (430) 460 (610) 560 (735) 915 (1170) 1070 (1400) 1295 (1675) FED IN BRACKE	Tension 7 DAYS, WET 7 DAYS, WET 9 (R2014), "BI 10 REMENTS. 9 (R2014), "BI 11 REMENTS. 9 (R2014), "BI 12 TO ASTM A 5: 75 mr 40 mi 50 mi 20 mi 30 mi 360 (460) 510 (660) 610 (815) 990 (1295) SHOULD BE U (S) TENSION E R CONCRETI 305 (380) 430 (530) 510 (660) 840 (1070) 90 (1270) 170 (1525) TTS AND SHO 4: 2 - 15M EAG	CURING SECURING SECUR	F H (mm) $\frac{6}{100}$ $\frac{6}{100}$ $\frac{6}{100}$ $\frac{6}{100}$ $\frac{6}{100}$ $\frac{100}{100}$ $\frac{6}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}{100}$ $\frac{100}$	OMPLETED WIT FH. SIDERATION TO DITIVES SHAL & CONCRETE R REBAR TO AST ADVANCE. CO TAL SPLICE BA O) ORIZONTAL B	TH TERRAFIX 240R NON-WOVEN GEOTEXTILE D EXTREME TEMPERATURES - WINTER OR SUMMER L BE APPROVED BY THE ENGINEER PRIOR TO EINFORCEMENT", GRADE 400R, BARS TO BE WELDE TM A775. PLACE REBAR TO CAN/CSA-A23.1-14.
RESHORING TO CONCRETE SLA BLANKETS (WH). ALL SLABS, BE AND CONSULT PLACEMENT. EINFORCING NOT REINFORCING NOT CONFORM TO C PROVIDE CLEA A) SURFACE P B) FORMED SU C) FORMED SU C) FORMED SU C) FORMED SU C) FORMED SU BEAI COLU SLAF D) PARKING S REINFORCING V IN PLACE FOR T REBAR LAP SPLIC <u>BAR SIZE</u> <u>CON</u> <u>SPL</u> 10M 330 15M 480 20M 580 25M 740 TOP BAR SPLIC 300mm OF CONO REBAR EMBED BAR <u>COM</u> SIZE <u>FOR C</u> 20 Mp 10M 250(33 15M 360 (45 20M 430 (55 25M 535 (71 30M 635 (84 35M 760 (95 TOP BAR DEVE MORE THAN 30 MIN. REINFORCE	BE APPROVED BY BS SHALL BE WET IITE). SUBSTITUTION AMS, GIRDERS, ET LE FOR THE MIX D GENERAL CONTRA- STEEL: NEW DEFO CAN/CSA G30.18-09. R CONCRETE COV OURED AGAINST O URFACES EXPOSED URFACES EXPOSED URFACES NOT EXE MS (TO STIRRUPS) UMNS (TO VERTIC 3S, WALLS URFACES AND EX WORK TO BE INSPECTION. LICE LENGTHS (UN MP. TENSION INS PECTION. LICE LENGTHS (UN MP. TENSION ICES (mm) 25 M 430 610 740 1170 E LENGTHS ARE D CRETE POURED BE MENT LENGTHS (UN MENT LENGTHS (UN 0) 230 (280) 200 50) 300 (400) 275 35) 380 (485) 360 10) 485 (635) 450 40) 585 (740) 535 40) 685 (900) 635 LOPMENT LENGTH O mm OF CONCRET ING AROUND OPE L BE PLACED BEFO	THE ENGINEI CURED FOR N ONS ARE NOT C. TO BE SHOF ESIGN. MIX DI ACTOR TO DET ACTOR TO DET (GRADE 400W) ER OVER REBA GROUND D TO GROUND O TO G TO GROUND O TO GROUND O TO G TO G O	ER PRIOR TO ST NO LESS THAN ' PERMITTED. RED UNTIL CON ESIGN SHALL B TERMINE REQU CO CSA/G30.18-0 . ANCHOR BOLT AR AS FOLLOW OR WEATHER OUND OR WEAT E ENGINEER. NO ON DRAWINGS) <u>ASS B" FOR</u> 10) '90) 65) 1400) RACKETS AND S R. D ON DRAWINGS ASS B" FOR 10) '90) 65) 1400) RACKETS AND S R. D ON DRAWING E S Mpa 330 (430) 460 (610) 560 (735) 915 (1170) 1070 (1400) 1295 (1675) FED IN BRACKE	TRIPPING. 7 DAYS, WET 7 CRETE REAC 9 (R2014), "BI 1REMENTS. 9 (R2014), "BI 75 mr 40 mr 51 40 mr 50 mr 20 mr 40 mr 50 mr 20 mr 40 mr 510 (660) 610 (815) 990 (1295) SHOULD BE U 63) TENSION E AOMPA 305 (380) 430 (530) 510 (660) 840 (1070) 90 (1270) 170 (1525) TS AND SHO 41 2 - 15M EAC 2 EMPLATES S	CURING SECUES DESIGNED WITH ADMIXTURE LLET STEEL A307. EPOX n n n n NGINEER 24 STRENGTHS 40 MJ 330 (4 480 (6 580 (7 940 (1) JSED WHEN STRENGT 35 Mpa 80 (360) 80 (510) 80 (610) 760 (990) 15 (1170) 090 (1420) ULD BE USE CH SIDE OF 4 SHALL BE USE	ALL BE CO N STRENG DUE CONS S AND AD BARS FOR Y COATED HOURS IN G (mm) Da 30) 10) 60) 220) HORIZON F H (mm) 40 Mpa 50 (330) 360 (480) 60 (585) 10 (940) 40 (1120) 1015 (132) D WHEN H OPENING, T SED TO EN	OMPLETED WIT TH. SIDERATION TO DITIVES SHAL R CONCRETE R REBAR TO AS' ADVANCE. CO FAL SPLICE BA O) IORIZONTAL B EXTENDED 600 SURE CORREC'	CH TERRAFIX 240R NON-WOVEN GEOTEXTILE D EXTREME TEMPERATURES - WINTER OR SUMMER L BE APPROVED BY THE ENGINEER PRIOR TO EINFORCEMENT", GRADE 400R, BARS TO BE WELDE TM A775. PLACE REBAR TO CAN/CSA-A23.1-14.

WOOD

1. ALL LUMBER TO BE MIN. NO. 2 SPF TO CSA 086-14 ENGINEERING DESIGN IN WOOD.

2. NAILING TO ONTARIO BUILDING CODE UNLESS NOTED OTHERWISE.

STRUCTURAL STEEL:

- 1. FABRICATE AND ERECT STRUCTURAL STEEL TO CAN/CSA S16.1-14. SUBMIT TWO SETS OF PRINTS OF SHOP DRAWINGS SHOWING ALL DETAILS AND MATERIAL SPECS. FOR REVIEW PRIOR TO FABRICATION. SHOP DRAWINGS WILL NOT BE REVIEWED UNLESS SEALED BY A PROFESSIONAL ENGINEER REGISTERED IN ONTARIO, FOR THOSE CONNECTIONS AND COMPONENTS DESIGNED BY THE FABRICATOR. THIS ENGINEER OR HIS REP. SHALL VISIT THE SITE TO SATISFY HIMSELF THAT THESE CONNECTIONS AND COMPONENTS SUBSTANTIALLY COMPLY WITH HIS SEALED SHOP DRAWINGS. THIS ENGINEER SHALL PROVIDE A LETTER TO THE CONSULTANT TO THIS EFFECT. THE ENGINEER SHALL ALSO PROVIDE SEALED SKETCHES FOR ALL FIELD MODIFICATIONS, MADE TO THIS DESIGN.
- 2. PROVIDE STRUCTURAL STEEL TO CSA G40.21-13 WITH THE FOLLOWING GRADES;

WIDE FLANGE BEAMS & COLUMNS	350 W
CHANNELS	350 W
HSS SECTION (CLASS H)	350 W
ANGLES, BARS & PLATES	300 W
MISCELLANEOUS STEEL	300 W
PIPE COLUMNS	ASTM A35 GR. B

3. PROVIDE ERECTION BOLTS TO ASTM A325, MINIMUM M20. DESIGN BOLTED CONNECTIONS TO ASTM A325 ASSUMING THREADS IN THE SHEAR PLANE.

4. WELD TO CASA W59-18 BY FABRICATORS CERTIFIED TO CSA W47.1-09 WELDING OF REINFORCING BARS SHALL CONFORM TO CSA W186-M1990(R2012).

5. MINIMUM WELDS FOR CONNECTIONS SHALL BE 6mm FILLET WELDS AND WHERE EXPOSED IN FINISHED BUILDING WELDS SHALL BE GROUND SMOOTH.

- 6. ALL STUD ANCHORS AND DEFORMED BAR ANCHORS SHALL BE FUSION WELDED TO PLATES AS PER MANUFACTURERS SPECIFICATIONS AND RECOMMENDATIONS.
 7. CONNECTIONS NOT DETAILED ON THE STRUCTURAL DRAWINGS SHALL BE DESIGNED BY THE STEEL FABRICATOR. MINIMUM BEAM SHEAR IS 80% OF THE TOTAL
- BEAM LOAD CAPACITY AS LISTED IN "CISC MANUAL BEAM LOADS TABLES" FOR THE GIVEN SPAN OF THE BEAM U.N.O. UNUSUAL LOADINGS SHOWN ON PLANS ARE SPECIFIED LOADS. SEE LEGEND FOR EXPLANATION OF THESE LOADS.
- UNLESS OTHERWISE NOTED, ALL CONNECTIONS SHALL BE SIMPLE CONNECTIONS. FOR BEAMS TO FACE OF HSS COLUMN CONNECTIONS PROVIDE DOUBLE ANGLE OR TEE-TYPE CONNECTIONS PER CISC HANDBOOK.

FOR CONNECTIONS NOT DESCRIBED ABOVE NOR DETAILED ON THE STRUCTURAL DRAWINGS (I.E. SMALL FRAMING MEMBERS) USE ANY TYPE OF SIMPLE CONNECTION AND DESIGN FOR THE SPECIFIED LOAD SHOWN.

SIMPLE BEAM TO COLUMN CONNECTIONS SHALL BE DESIGNED TO DELIVER SHEAR ONLY TO THE FACE OF THE COLUMN. SEISMIC AND DRAG STRUT CONNECTIONS SHALL BE DESIGNED TO DELIVER SHEAR ONLY TO THE CENTER LINE OF THE COLUMN.

UNLESS OTHERWISE NOTED, CONNECTIONS ARE TO BE WELDED OR BOLTED WITH HIGH STRENGTH BOLTS IN BEARING TYPE CONNECTIONS (MIN. 2 - 20 DIA. BOLTS).

BOLTED CONNECTIONS FOR DRAG STRUT LINES ARE TO BE PRE-TENSIONED. THE PRIME STRUCTURAL CONSULTANT SHALL HAVE FINAL APPROVAL ON ALL CONNECTIONS.

- 8. TEMPORARY BRACING DURING CONSTRUCTION TO BE DESIGNED BY CONTRACTOR (WHOEVER IS RESPONSIBLE FOR ERECTION). CONTRACTOR IS RESPONSIBLE FOR SAFETY ON SITE.
- 9. COORDINATE WITH MECHANICAL, PLUMBING, AND ELECTRICAL DRAWINGS TO AVOID CONFLICT WITH STRUCTURAL ELEMENTS.

10. NO BURNING OF HOLES SHALL BE ALLOWED IN STRUCTURAL STEEL ANYWHERE.

- 11. FOR MISC. STEEL SUCH AS RAILINGS, AWNINGS AND NON-STRUCTURAL ARCH. STEEL NOT DETAILED ON STRUCTURAL DRAWINGS, STRUCTURAL ENGINEER SHALL CHECK SHOP DRAWINGS AND COMMENT ON THE ABILITY OF THE SHOWN MEMBERS AND CONNECTIONS TO RESIST LOADS AND OTHER EFFECTS REQUIRED BY ONTARIO BUILDING CODE 2012. OVERALL DETAILING TO COMPLY WITH ARCHITECTURAL DRAWINGS AND ARE THE SUB-CONTRACTOR'S RESPONSIBILITY. ALL RAILINGS AND STAIR SHOP DRAWINGS TO BE STAMPED BY P.ENG. OF ONTARIO.
- 12. ALL VISUALLY EXPOSED SURFACES OR SURFACES EXPOSED TO WEATHER AND NOT REQUIRING FIREPROOFING SHALL BE PAINTED WITH ONE COAT OF PRIMER TO CISC/CPMA 1-73A (REFER TO ARCHITECTURAL DRAWINGS). ALL SITE WELD AND WELDING CONNECTIONS TO BE TOUCHED-UP WITH ANTI-RUST PAINT.
- PROVIDE NAIL HOLES (2 MIN.) IN MISC. STEEL CAST INTO CONC. TO FACILITATE NAILING TO FORM WORK.
 CHECK MECHANICAL AND ARCHITECTURAL DRAWINGS FOR OPENINGS, MECHANICAL UNITS, HOLES, ETC. TO BE MADE. OPENINGS SHOWN ON STRUCTURAL DRAWINGS FOR MECHANICAL UNITS, DUCTS AND PIPES ARE APPROXIMATE ONLY IN SIZE AND LOCATION. THE MECHANICAL CONTRACTOR MUST PROVIDE CONFIRMATION OF THE LATEST INFORMATION TO THE GENERAL CONTRACTOR AT THE STRUCTURAL STEEL AND METAL DECK SHOP DRAWING APPROVAL STAGE OF THE PROJECT.
- 15. THE STEEL STRUCTURE IS A NON-SELF-SUPPORTING STEEL FRAME AND IS DEPENDENT UPON DIAPHRAGM ACTION THE DECK FLOORS AND ATTACHMENT TO THE WALL SYSTEM FOR STABILITY AND FOR RESISTANCE TO WIND AND SEISMIC FORCES. PROVIDE ALL TEMPORARY SUPPORTS REQUIRED FOR STABILITY AND FOR RESISTANCE TO WIND AND SEISMIC FORCES UNTIL THESE ELEMENTS ARE COMPLETE AND ARE CAPABLE OF PROVIDING THIS SUPPORT.
- 16. THE FABRICATOR IS RESPONSIBLE FOR THE DESIGN OF ALL CONNECTIONS. CONNECTIONS SHOWN ON THE STRUCTURAL DRAWINGS ARE SCHEMATIC AND ARE ONLY INTENDED TO SHOW THE RELATIONSHIP OF MEMBERS CONNECTED. CONNECTION DETAILS INDICATED ON THE DRAWINGS SHALL BE INCORPORATED INTO FABRICATOR'S CONNECTION DESIGN. SEE SPECIFICATIONS. ALL SHOP DRAWINGS SHALL BE SIGNED AND SEALED BY THE FABRICATOR'S ENGINEER WITH THE ENGINEER'S SEAL FOR THE PROVINCE WHERE THE STRUCTURE IS LOCATED. ENGINEER'S SEAL MAY BE QUALIFIED "FOR DESIGN OF CONNECTIONS ONLY".
- 17. REFER TO SCHEDULE ON DWG FOR NON-BEARING WALL LINTELS NOT SHOWN ON STRUCTURAL DWG. REFER TO ARCH. & MECH. DWG. FOR OPENING SIZES AND LOCATIONS.
- 18. PROVIDE HOLES IN STEEL MEMBER FOR ATTACHMENT OF OTHER MATERIALS EXCEPT AT CRITICAL TENSILE SECTIONS OF BEAMS.
- 19. NO SPLICES IN COLUMNS AND BEAMS ARE ALLOWED WITHOUT THE ENGINEER'S APPROVAL. 100% BUTT WELDS IN SPLICES ARE TO BE ULTRASONICALLY TESTED OR EQUAL AND ACCEPTED BY A WELDING INSPECTION COMPANY.

SNOW DRIFT DIAGRAM

4	B.O"B	2023 02 26	
3			FOR TENDER/PERMIT
2	в.0'В В.0'В	2023 02 14 2023 01 26	FOR TENDER/PERMIT FINAL REVIEW FOR COORDINATION
2 1 No.	B.O'B B.O'B B.O'B. By	2023 02 14 2023 01 26 2023 12 12 Date	FOR TENDER/PERMIT FINAL REVIEW FOR COORDINATION FOR REVIEW Revisions
2 1 No.	B.O'B B.O'B B.O'B. By drawings, sp e Engineer	2023 02 14 2023 01 26 2023 12 12 Date	FOR TENDER/PERMIT FINAL REVIEW FOR COORDINATION FOR REVIEW Revisions
2 1 No.	B.O'B B.O'B B.O'B By drawings, sp drawings, sp e Engineer ecifications, a	2023 02 14 2023 01 26 2023 12 12 Date Decifications and relate and must be returned and related documents Engineers' wr tor must check and ve	FOR TENDER/PERMIT FINAL REVIEW FOR COORDINATION FOR REVIEW Revisions ed documents are the copyright property upon request. Reproduction of drawings, in part or whole is forbidden without the itten permission. erify all dimensions on the job prior to
2 1 No.	B.O'B B.O'B B.O'B. By drawings, sp he Engineer ecifications, a The contrac	2023 02 14 2023 01 26 2023 12 12 Date Decifications and relate and must be returned Engineers' wr tor must check and ve start of c	FOR TENDER/PERMIT FINAL REVIEW FOR COORDINATION FOR REVIEW Revisions ed documents are the copyright property upon request. Reproduction of drawings, in part or whole is forbidden without the itten permission. erify all dimensions on the job prior to onstruction. NOT TO BE SCALED
2 1 No.	B.O'B B.O'B B.O'B. By drawings, sp he Engineer actifications, a The contract	2023 02 14 2023 01 26 2023 12 12 Date Decifications and related and must be returned and related documents Engineers' wr tor must check and ve start of c DRAWINGS ARE	FOR TENDER/PERMIT FINAL REVIEW FOR COORDINATION FOR REVIEW Revisions ed documents are the copyright property upon request. Reproduction of drawings, in part or whole is forbidden without the itten permission. erify all dimensions on the job prior to onstruction. NOT TO BE SCALED
2 1 No.	B.O'B B.O'B B.O'B. By drawings, sp he Engineer ecifications, a The contract	2023 02 14 2023 01 26 2023 12 12 Date Decifications and relate and must be returned Engineers' wr tor must check and ve start of c DRAWINGS ARE	FOR TENDER/PERMIT FINAL REVIEW FOR COORDINATION FOR REVIEW Revisions ed documents are the copyright property upon request. Reproduction of drawings, in part or whole is forbidden without the itten permission. erify all dimensions on the job prior to onstruction. NOT TO BE SCALED
2 1 No.	B.O'B B.O'B B.O'B. By drawings, sp the Engineer ecifications, a The contract	2023 02 14 2023 01 26 2023 12 12 Date Decifications and relate and must be returned Engineers' wr tor must check and ve start of c DRAWINGS ARE	FOR TENDER/PERMIT FINAL REVIEW FOR COORDINATION FOR REVIEW Revisions ad documents are the copyright property upon request. Reproduction of drawings, in part or whole is forbidden without the itten permission. arify all dimensions on the job prior to onstruction. NOT TO BE SCALED MOT TO BE SCALED MOT FOR ESSION B. D. CAMPBELL 100172021
2 1 No.	B.O'B B.O'B B.O'B. By drawings, sp he Engineer acifications, a The contract	2023 02 14 2023 01 26 2023 12 12 Date Decifications and relate and must be returned Engineers' wr tor must check and ve start of c DRAWINGS ARE	FOR TENDER/PERMIT FINAL REVIEW FOR COORDINATION FOR REVIEW Revisions ad documents are the copyright property upon request. Reproduction of drawings, in part or whole is forbidden without the itten permission. arify all dimensions on the job prior to onstruction. NOT TO BE SCALED MOT TO BE SCALED MOT FESSION B. D. CAMPBELL UD172021 2024 03 07 B. D. CAMPBELL
2 1 No.	B.O'B B.O'B B.O'B. By drawings, sp ecfications, a The contract	2023 02 14 2023 01 26 2023 12 12 Date Decifications and relate and must be returned Engineers' wr tor must check and ve start of c DRAWINGS ARE	FOR TENDER/PERMIT FINAL REVIEW FOR COORDINATION FOR REVIEW Revisions ad documents are the copyright property upon request. Reproduction of drawings, in part or whole is forbidden without the itten permission. arity all dimensions on the job prior to onstruction. NOT TO BE SCALED MOT TO BE SCALED MOT FOR ESSION B. D. CAMPBELL UD172021 2024 03 07 B. D. CAMPBELL UD172021 2024 03 07 B. D. CAMPBELL
2 1 No.	B.O'B B.O'B B.O'B. By drawings, sp he Engineer a scifications, a The contract	2023 02 14 2023 01 26 2023 12 12 Date Decifications and relate and must be returned Engineers' wr tor must check and ve start of c DRAWINGS ARE	FOR TENDER/PERMIT FINAL REVIEW FOR COORDINATION FOR REVIEW Revisions ad documents are the copyright property upon request. Reproduction of drawings, in part or whole is forbidden without the itten permission. who are the copyright property upon request. Reproduction of drawings, in part or whole is forbidden without the itten permission. NOT TO BE SCALED
2 1 No.	B.O'B B.O'B B.O'B. By drawings, sp he Engineer a scifications, a The contract	2023 02 14 2023 01 26 2023 12 12 Date Decifications and relate and must be returned Engineers' wr tor must check and ve start of c DRAWINGS ARE	FOR TENDER/PERMIT FINAL REVIEW FOR COORDINATION FOR REVIEW Revisions ad documents are the copyright property upon request. Reproduction of drawings, in part or whole is forbidden without the itten permission. TO TO BE SCALED MONTO BE SCALED MONTO BE SCALED MONTO BE SCALED
2 1 No.	B.O'B B.O'B B.O'B. By drawings, sp he Engineer a scifications, a The contract	2023 02 14 2023 01 26 2023 12 12 Date Decifications and relate and must be returned Engineers' wr tor must check and ve start of c DRAWINGS ARE DRAWINGS ARE	FOR TENDER/PERMIT FINAL REVIEW FOR COORDINATION FOR REVIEW Revisions ad documents are the copyright property upon request. Reproduction of drawings, in part or whole is forbidden without the itten permission. TO TO BE SCALED MONTO BE SCALED MONTO BE SCALED COMPRESSION B. D. CAMPBELL UD172021 2024 03 07 B. D. CAMPBELL UD172021 2024 03 07 B. D. CAMPBELL UD172021 COLOR OF CONTINUES RING GROUP INC. TNG ENGINEERS
2 1 No.	B.O'B B.O'B B.O'B By drawings, sp he Engineer f actifications, a The contract	2023 02 14 2023 01 26 2023 12 12 Date Decifications and relate and must be returned Engineers' wr tor must check and ve start of c DRAWINGS ARE DRAWINGS ARE	FOR TENDER/PERMIT FINAL REVIEW FOR COORDINATION FOR REVIEW Revisions ad documents are the copyright property upon request. Reproduction of drawings, in part or whole is forbidden without the itten permission. NOT TO BE SCALED MARKED NOT TO BE SCALED MARKED RING GROUP INC. ING ENGINEERS Telephone: (613) 345-0400 Facsimile: (613) 345-0400 Facsimile: (613) 345-0400
2 1 No.	B.O'B B.O'B B.O'B By drawings, sp he Engineer f actifications, a The contract	2023 02 14 2023 01 26 2023 12 12 Date Decifications and related and related documents Engineers' wr tor must check and ve start of c DRAWINGS ARE DRAWINGS ARE	FOR TENDER/PERMIT FINAL REVIEW FOR COORDINATION FOR REVIEW Revisions ad documents are the copyright property upon request. Reproduction of drawings, in part or whole is forbidden without the itten permission. NOT TO BE SCALED
2 1 No.	B.O'B B.O'B B.O'B By drawings, sp he Engineer f ecifications, a The contract	2023 02 14 2023 01 26 2023 12 12 Date Decifications and related and related documents Engineers' wr tor must check and ve start of c DRAWINGS ARE DRAWINGS ARE DRAWINGS ARE NGINEEF CONSULT Vger Blvd. K6V 5J9	FOR TENDER/PERMIT FINAL REVIEW FOR COORDINATION FOR REVIEW Revisions ad documents are the copyright property upon request. Reproduction of drawings, in part or whole is forbidden without the itten permission. NOT TO BE SCALED
2 1 No.	B.O'B B.O'B B.O'B By drawings, sp the Engineer f ecifications, a The contract	2023 02 14 2023 01 26 2023 12 12 Date Decifications and related and must be returned Engineers' wr tor must check and ve start of c DRAWINGS ARE DRAWINGS ARE DRAWINGS ARE NGINEEF CONSULT Vger Blvd. K6V 5J9 NORTH S MUNICIP	FOR TENDER/PERMIT FINAL REVIEW FOR COORDINATION FOR REVIEW Revisions ad documents are the copyright property upon request. Reproduction of drawings, in part or whole is forbidden without the itten permission. TO TO BE SCALED FOR FESSION B. D. CAMIPBELL UDITZ021 2024 03 07 00000000000000000000000000000000000
2 1 No. All of ti spe 207 Broce Projece	B.O'B B.O'B B.O'B By drawings, sp the Engineer - scifications, a The contract	2023 02 14 2023 01 26 2023 12 12 Date Date Decifications and relate and related documents Engineers' wr tor must check and ve start of c DRAWINGS ARE DRAWINGS ARE DRAWINGS ARE DRAWINGS ARE NGINEEF CONSULT vger Blvd. K6V 5J9 NORTH S MUNICIPA 57 COCKBU	FOR TENDER/PERMIT FINAL REVIEW FOR COORDINATION FOR REVIEW Revisions ad documents are the copyright property upon request. Reproduction of drawings, s in part or whole is forbidden without the itten permission. NOT TO BE SCALED
2 1 No.	B.O'B B.O'B B.O'B. By drawings, sp the Engineer scifications, a The contract NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH N	2023 02 14 2023 01 26 2023 12 12 Date Decifications and relate and related documents Engineers' wr tor must check and ve start of c DRAWINGS ARE DRAWINGS ARE DRAWINGS ARE NGINEEF CONSULT Vger Blvd. K6V 5J9 NORTH S MUNICIPA 57 COCKBU BERWICK	FOR TENDER/PERMIT FINAL REVIEW FOR COORDINATION FOR REVIEW Revisions ad documents are the copyright property upon request. Reproduction of drawings, in part or whole is forbidden without the itten permission. NOT TO BE SCALED
2 1 No.	B.O'B B.O'B B.O'B By drawings, sp be Engineer scifications, a The contract NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NOR	2023 02 14 2023 01 26 2023 12 12 Date Decifications and relate and related documents Engineers' wr tor must check and ve start of co DRAWINGS ARE DRAWINGS ARE DRAWINGS ARE NGINEEF CONSULT Vger Blvd. K6V 5J9 NORTH S MUNICIPA 57 COCKBU BERWICK	FOR TENDER/PERMIT FINAL REVIEW FOR COORDINATION FOR REVIEW Revisions ad documents are the copyright property upon request. Reproduction of drawings, in part or whole is forbidden without the itten permission. NOT TO BE SCALED
2 1 No. All of ti spe 207 Broce Project	B.O'B B.O'B B.O'B By drawings, sp the Engineer scifications, a The contract NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NO	2023 02 14 2023 01 26 2023 12 12 Date Decifications and relate and related documents Engineers' wr tor must check and ve start of c DRAWINGS ARE DRAWINGS ARE NGINEEF CONSULT Vger Blvd. K6V 5J9 NORTH S MUNICIPA 57 COCKBU BERWICK	POR TENDER/PERMIT FINAL REVIEW FOR COORDINATION FOR REVIEW Revisions ad documents are the copyright property upon request. Reproduction of drawings, is in part or whole is forbidden without the itten permission. NOT TO BE SCALED
2 1 No. All of ti spe 207 Brojec Projec	B.O'B B.O'B B.O'B B.O'B. By drawings, sp be Engineer scifications, a The contract NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NO	2023 02 14 2023 01 26 2023 12 12 Date Decifications and relate and related documents Engineers' wr tor must check and ve start of c DRAWINGS ARE DRAWINGS ARE NGINEEF CONSULT Vger Blvd. K6V 5J9 NORTH S MUNICIPA 57 COCKBU BERWICK	FOR TENDER/PERMIT FINAL REVIEW FOR COORDINATION FOR REVIEW Revisions ad documents are the copyright property upon request. Reproduction of drawings, is in part or whole is forbidden without the itten permission. artify all dimensions on the job prior to onstruction. NOT TO BE SCALED Image: State of the state of the copyright property and the state of
2 1 No. All of ti spe 207 Broce Project	B.O'B B.O'B B.O'B B.O'B. By drawings, sp e Engineer scifications, a The contract NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NOR	2023 02 14 2023 01 26 2023 12 12 Date Decifications and relate and must be returned Engineers' wr tor must check and ve start of c DRAWINGS ARE DRAWINGS ARE DRAWINGS ARE NGINEEF CONSULT Vger Blvd. K6V 5J9 NORTH S MUNICIP S7 COCKBU BERWICK	FOR TENDER/PERMIT FINAL REVIEW FOR COORDINATION FOR REVIEW Revisions ad documents are the copyright property upon request. Reproduction of drawings, in part or whole is forbidden without the itten permission. NOT TO BE SCALED
2 1 No. All of ti spe 207 Broce Projece Drawin Brown Brown Brown Comparison	B.O'B B.O'B B.O'B By drawings, sp the Engineer f ecifications, a The contract NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH NORTH	2023 02 14 2023 01 26 2023 12 12 Date Decifications and relate and must be returned Engineers' wr tor must check and ve start of c DRAWINGS ARE DRAWINGS ARE DRAWINGS ARE ORAVINGS ARE NGINEEF CONSULT Vger Blvd. K6V 5J9 NORTH S MUNICIP S7 COCKBU BERWICK	FOR TENDER/PERMIT FINAL REVIEW FOR COORDINATION FOR REVIEW Revisions ad documents are the copyright property upon request. Reproduction of drawings, in part or whole is forbidden without the itten permission. NOT TO BE SCALED







	4 B.O"B 2023 02 26 FOR TENDER/PERMIT 3 B.O'B 2023 02 14 FINAL REVIEW 2 B.O'B 2023 01 26 FOR COORDINATION 1 B.O'B. 2023 12 12 FOR REVIEW No. By Date Revisions All drawings, specifications and related documents are the copyright property of the Engineer and must be returned upon request. Reproduction of drawings, specifications, and related documents in part or whole is forbidden without the Engineers' written permission. The contractor must check and verify all dimensions on the job prior to start of construction. DRAWINGS ARE NOT TO BE SCALED
5" T#G PLYWOOD 2"XG"@ I G" c.c. FLOOR JOISTS	Image: Non-State State
	Project Title: NORTH STORMONT MUNICIPAL OFFICE 57 COCKBURN STREET, BERWICK, ONTARIO Drawing Title: ROOF FRAMING PLAN AND STAGE CONSTRUCTION DETAILS
<u>M M M M M M</u> "DIA. "c.c	BDC BDC 11200 Drawn: Checked: Date: Contract No.: B.O'B. BDC Date: Contract No.: Scale: Drawing No.: Drawing No.: Horizontal: AS SHOWN REV. DATE:3/7/2024



MECHANICAL NOTES MECHANICAL DRAWINGS SHALL BE READ IN CONJUNCTION WITH ALL OTHER DRAWINGS FOR THIS TRADES. PROJECT. 1 GENERAL CONFORM WITH APPLICABLE REQUIREMENTS OF THE MINISTRY OF LABOUR, AND THE OCCUPATIONAL HEALTH AND SAFETY ACT AND REGULATIONS FOR CONSTRUCTION PROJECTS. DO COMPLETE INSTALLATION IN ACCORDANCE WITH THE FOLLOWING: 6 PIPING AND ESCUTCHEONS: .1 ONTARIO BUILDING CODE (OBC); NATURAL GAS AND PROPANE INSTALLATION CODE (GAS CODE); ASHRAE; SMACNA; NFPA ALL OTHER RELEVANT CODES AND STANDARDS, AS APPLICABLE. 7 ACCESS DOORS: OBTAIN ALL PERMITS REQUIRED FOR THE INSTALLATION OF MECHANICAL TRADES WORK, ARRANGE FOR INSPECTIONS AND TESTS, AND PAY ALL FEES AND COSTS FOR THE PERMITS, INSPECTIONS AND FEES. OBTAIN PERMITS IMMEDIATELY AFTER NOTIFICATION OF AWARD OF CONTRACT. PROVIDE DIGITAL AND HARD COPY OF COMPLETE OPERATING AND MAINTENANCE INSTRUCTIONS FOR EQUIPMENT FURNISHED UNDER THIS CONTRACT. BIND INSTRUCTIONS IN 3-RING BINDERS. 8 PIPE INSULATION: .1 INCLUDE THE FOLLOWING: .2 SCHEMATIC DIAGRAM OF ELECTRICAL SYSTEMS. CONTROL SHOP DRAWINGS AND OPERATING SEQUENCE INCLUDING WIRING OF COMPONENTS. WIRING DIAGRAM OF CONTROL PANELS. .2 OPERATING INSTRUCTIONS, INCLUDING START-UP AND SHUT-DOWN PROCEDURE. MAINTENANCE INSTRUCTIONS INCLUDING PREVENTIVE MAINTENANCE INSTRUCTIONS .5 FOR COMPONENTS OF THE EQUIPMENT. .1 COMPLETE PARTS LIST OF ASSEMBLIES AND THEIR COMPONENT PARTS, SHOWING MANUFACTURER'S NAME, CATALOGUE NUMBER, AND NEAREST REPLACEMENT SOURCE. LIST OF RECOMMENDED SPARE PARTS AND QUANTITY OF EACH ITEM TO BE STOCKED. OUTER JACKET: MANUFACTURERS' WARRANTIES AND GUARANTEES. .6 .1 CLEAN ALL MECHANICAL SYSTEMS AT PROJECT COMPLETION. .2 COMPLETE AS-BUILT DRAWINGS SHOWING ALL CHANGES AS WORK PROGRESSES. **2 CONTRACTOR QUALIFICATIONS:** ALL WORK TO BE CARRIED OUT IN ACCORDANCE WITH THE "TRADE QUALIFICATION AND APPRENTICESHIP ACT" AND REGULATIONS, BY PERSONS WHO HOLD THE FOLLOWING CERTIFICATES OF QUALIFICATION .2 (AS APPLICABLE): RETAIN AND PROTECT ALL EXISTING SANITARY VENTS. RE-ROUTE AS NECESSARY TO SUIT NEW FLOOR PLAN AND CEILINGS. CONNECT NEW SANITARY VENTS TO EXISTING IN .1 CEILING SPACE. CONDITIONS. DISCONNECT AND REMOVE EXISTING PLUMBING FIXTURES, AND ALL OBSOLETE PIPING. CONCEAL AND CAP ALL OTHER PLUMBING IN WALLS, CEILINGS AND FLOORS WHICH ARE .2 TO BE RETAINED. .3 ABOVE GROUND: .4 DISPOSE OF ALL OBSOLETE PLUMBING FIXTURES AND EQUIPMENT EXISTING SANITARY PIPING: PERFORM A CAMERA INSPECTION OF THE EXISTING SANITARY SERVICE TO CONFIRM EXISTING SANITARY PIPE SIZE, LOCATION AND CONDITION. REPORT ANY PIPE .2 BLOCKAGES, INADEQUATE SLOPES, LOW SPOTS, AND POOR CONDITION TO ENGINEER, FOR COMMENT AND DIRECTION. FLOOR CUTTING: .2 CONDUCT THERMAL IMAGING OF THE FLOOR IN ALL AREAS OF FLOOR CUTTING .5 AND REMOVAL, TO LOCATE BURIED ELECTRICAL SERVICES (IF ANY). CAREFULLY SAWCUT FLOOR TO PERMIT INSTALLATION OF NEW SANITARY PIPING REINSTATE FLOOR TO ORIGINAL CONDITION, FOLLOWING INSTALLATION OF .3 NEW PLUMBING CUTTING AND PATCHING: EXECUTE CUTTING, FITTING AND PATCHING REQUIRED TO MAKE THE WORK FIT .2 .1 PROPERLY TOGETHER. CUT AND PATCH FOR PROCESS, MECHANICAL AND ELECTRICAL WORK. COORDINATE WORK WITH OTHER TRADES SO THAT THERE IS A MINIMUM OF CUTTING, .3 FITTING AND PATCHING. .1 DRILLING, CUTTING, FITTING AND PATCHING AND MAKING GOOD WHERE NECESSARY .4 DUE TO FAILURE TO DELIVER ITEMS TO BE BUILT IN TIME OR INSTALLATION IN WRONG .5 LOCATION, SHALL BE EXECUTED AS DIRECTED AT NO COST TO THE OWNER.

- DRILLING AND CUTTING OF LOAD BEARING STRUCTURAL MEMBERS SHALL BE DONE ON PRIOR EXPRESS WRITTEN PERMISSION OF THE ENGINEER FOR EACH INSTANCE.
- CUT HOLES ACCURATELY, WITH SMOOTH, TRUE, CLEAN EDGES. FIT UNITS TO
- TOLERANCES TO BEST STANDARD PRACTICE FOR APPLICABLE WORK.
- HOLES IN BLOCK AND CONCRETE WORK SHALL BE SAWCUT OR CORE-DRILLED, AND
- SHALL NOT BE MADE WITH A HAMMER GUN. PATCHED WORK SHALL BE INVISIBLE, SIZE HOLES AND OPENINGS FOR PIPES SO AS TO
- ALLOW FOR EXPANSION AND CONTRACTION OF SUCH PIPES.

4 FIXTURES AND EQUIPMENT:

PROVIDE SHOP DRAWINGS AND PRODUCT DATA FOR ALL MECHANICAL FIXTURES AND

- EQUIPMENT FOR APPROVAL, PRIOR TO PROCUREMENT.
- HVAC EQUIPMENT SHALL NOT USED FOR CONSTRUCTION HEATING. INSTALL ALL MECHANICAL FIXTURES AND EQUIPMENT IN ACCORDANCE WITH
- MANUFACTURER'S INSTRUCTIONS.
- EQUIPMENT AND MATERIAL TO BE CANADIAN GAS ASSOCIATION (CGA) CERTIFIED. WHERE THERE IS NO ALTERNATIVE TO SUPPLYING EQUIPMENT WHICH IS NOT CGA CERTIFIED, OBTAIN TSSA FIELD APPROVAL.

5 EQUIPMENT SUPPLIED BY OTHERS:

- GENERAL CONTRACTOR SHALL ASSUME FULL REPONSIBILITY FOR COORD SERVICES AND CONNECTIONS FOR ALL EQUIPMENT, SUPPLIED BY MECHA
- MAKE ALL MECHANICAL SERVICE CONNECTIONS TO EQUIPMENT SUPPLIE CONFIRM ALL SERVICE CONNECTIONS WITH MANUFACTURER AND SUPPL
- INSTALLATION. THIS SHALL INCLUDE ALL CONNECTION SIZES, LOCATIONS SHALL TAKE INTO ACCOUNT EQUIPMENT CLEARANCES AND INSTALLATIO
- PROVIDE DIELECTRIC UNIONS AT ALL PIPING LOCATIONS WHERE DISSIMI JOINED.
- .2 PROVIDE ESCUTCHEONS ON ALL PIPES PASSING THROUGH WALLS, PARTI CEILINGS,
- CHROME, NICKEL PLATED BRASS OR TYPE 302 STAINLESS STEEL
- SUPPLY ACCESS DOORS, AS REQUIRED IN DUCTWORK AND WALL/CEILING CONCEALED MECHANICAL EQUIPMENT AND OPERATING DEVICES. ACCES WALL/CEILING ASSEMBLIES TO BE INSTALLED BY OTHER TRADES. ACCESS DOORS SHALL BE FIRE-RATED TYPE, WHERE USED IN FIRE-RATED
- SHALL MATCH THE RATING OF THE ASSEMBLY.

- INSTALL IN ACCORDANCE WITH THERMAL INSULATION ASSOCIATION OF NATIONAL STANDARDS.
- MAX. FLAME SPREAD RATING: 25.
- MAX. SMOKE DEVELOPED RATING: 50. DOMESTIC COLD WATER (DCW):
 - 1" RIGID MOULDED MINERAL FIBRE WITH VAPOUR RETARDER JAC INSULATE ALL PIPING IN FLOORS, WALLS AND CEILINGS, TO POIN
- CONNECTIONS. DOMESTIC HOT WATER (DHW):
- 1" RIGID MOULDED MINERAL FIBRE FOR PIPING UP TO 1-1/4" SIZ
- 1-1/2" RIGID MOULDED MINERAL FIBRE FOR PIPING 1-1/2" TO 3" INSULATE ALL PIPING IN FLOORS, WALLS AND CEILINGS, TO POIN
- CONNECTIONS.
- CONCEALED LOCATIONS: ALL SERVICE JACKET. EXPOSED LOCATIONS: PVC JACKET.
- MECHANICAL/SERVICE ROOMS: PVC JACKET.
- 9 WATER SERVICE AND WATER SUPPLY PIPING: .1 INSIDE BUILDING: COPPER TUBE, HARD DRAWN, TYPE L. CAN. OR US MA
- INCLUDING FITTINGS. LEAD-FREE SOLDER. WATER SUPPLY PIPING IS SHOWN SCHEMATICALLY. ALL PIPING SHALL BE
- OTHERWISE NOTED.
- **<u>10</u>** DRAINAGE, WASTE AND VENT PIPING: APPROXIMATE SUB-FLOOR PIPING ELEVATIONS HAVE BEEN INDICATED O GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR SETTING FINAL INVE
- BELOW GROUND/FLOOR:
- .1 PVC DWV, TYPE SDR26 SDR35.
- .1 PVC DWV SOLID WALL SCHEDULE 40, CERTIFIED TO CAN/CSA STA NONCOMBUSTIBLE CONSTRUCTION (FLAME-SPREAD RATING NO CAN/ULC-S102.2).
- PVC DWV SOLID WALL SCHEDULE 40, CERTIFIED TO CAN/CSA STA NONCOMBUSTIBLE CONSTRUCTION (FLAME-SPREAD RATING NO
- SMOKE DEVELOPED CLASSIFICATION NOT MORE THAN 50 PER CA PROVIDE CLEANOUTS AS REQUIRED BY THE ONTARIO BUILDING CODE.
- VENT COMPLETE PLUMBING SYSTEM IN ACCORDANCE WITH THE ONTARI

11 NATURAL GAS PIPING:

- .1 COORDINATE NATURAL GAS SERVICE UPGRADE AND INSTALLATION, AS F
 - .1 MECHANICAL CONTRACTOR SHALL ASSUME FULL RESPONSIBILITY OF NATURAL GAS SERVICE WITH THE SUPPLY AUTHORITY;
 - INCLUDE DETAILED REVIEW OF EXISTING NATURAL GAS LOADS FO BUILDING TOTAL LOAD;
 - COORDINATE ALL SERVICE, METER AND EQUIPMENT PRESSURES STEEL PIPE, SCHEDULE 40, SEAMLESS, SCREWED FITTINGS.
- SUPPLY AND INSTALL:
- EXPANSION CONTROL LOOPS ON PIPES SLOPE PIPING DOWN IN DIRECTION OF FLOW TO LOW POINTS.
- ALL NATURAL GAS PIPING AND FITTINGS SHALL BE:
- CLEANED AFTER ASSEMBLY; .1
- PAINTED WITH ONE BASE LAYER OF METAL PRIMER; .2
- PAINTED WITH ONE TOP COAT OF EXTERIOR ENAMEL PAINT; .3
- COLOUR ON EXTERIOR WALL TO MATCH WALL .4
- COLOUR ON ROOF AND INTERIOR OF BUILING YELLOW. .5
- .6 TEST SYSTEM IN ACCORDANCE WITH NATURAL GAS AND PROPANE INSTA

12 DUCTWORK: .1 RECTANGULAR DUCT:

- RIGID GALVANIZED STEEL, LOCK FORMING QUALITY TO ASTM A65 .1 THICKNESS, FABRICATION, REINFORCEMENT AND SUPPORT/ATTA .2 OR SMACNA.
- .2 ROUND DUCT: RIGID GALVANIZED STEEL, LOCK FORMING QUALITY TO ASTM A65
- THICKNESS, FABRICATION, REINFORCEMENT AND SUPPORT/ATTA OR SMACNA. .3
- FLEXIBLE BRANCH DUCT (PERMITTED WITHIN 1m/3ft FROM OUTI .1 ALL METAL TYPE: TRIPLE LOCK, ALUMINUM CORRUGATE MANUFACTURED USING AN ALUMINUM STRIP, WHICH IS

INATING MECHANICAL		.1 .2	FABRICATION: TO SMACNA. RADIUSED ELBOWS.	.2	MECHAN CONNE(
ANICAL OR ANY OTHER			.1 RECTANGULAR: STANDARD WITH CENTRELINE RADIUS 1.5 TIMES DUCT DIMENSION, WITH		SMACNA ONTARI
ED BY OTHERS.			SINGLE THICKNESS TURNING VANES.	.3	FOLLOW
LIER, PRIOR TO		_	.2 ROUND: FIVE PIECE WITH CENTRELINE RADIUS 1.5 TIMES DIAMETER.		REVIEW
S AND DETAILS, AND	5	.3 BRANC	MITRED ELBOWS, RECTANGULAR: WITH DOUBLE THICKNESS TURNING VANES.	.4	CONTRA
n negonemento.		.1	RECTANGULAR MAIN AND BRANCH: WITH RADIUS ON BRANCH 1.5 TIMES WIDTH OF	17 E	
LAR METALS ARE		.2	ROUND MAIN AND BRANCH: ENTER MAIN DUCT AT 45 DEGREES WITH CONICAL	.1	ALL MEC
TIONS. FLOORS AND		З	CONNECTION. PROVIDE VOLUME CONTROL DAMPER IN BRANCH DUCT NEAR CONNECTION TO MAIN		SUPPOR
		.5	DUCT.	.2	PIPE HA
	<i>c</i>	.4	MAIN DUCT BRANCHES: WITH SPLITTER DAMPER.		MSS STA
	.6	TRANS	DIVERGING: 20 DEGREES MAXIMUM INCLUDED ANGLE	2	
G ASSEMBLIES, TO ALL		.2	CONVERGING: 30 DEGREES MAXIMUM INCLUDED ANGLE.		REQUIR
SS DOORS IN	.7	FIRE S	TOPPING		STEEL CO
ASSEMBLIES AND		.1	RETAINING ANGLES AROUND DUCT, ON BOTH SIDES OF FIRE SEPARATION IN	10 C	
		.2	FIRE STOPPING MATERIAL AND INSTALLATION MUST NOT DISTORT DUCT.	<u>.1</u>	INFORM
	.8	DAMP	'ERS:		
ΓΑΝΑΠΑ (ΤΙΑΓ)		.1	MANUFACTURE TO SMACNA STANDARDS.	n	
		.2	.1 FABRICATE FROM SAME MATERIAL AS DUCT, BUT ONE SHEET METAL THICKNESS	.2	DRAWIN
			HEAVIER. V-GROOVE STIFFENED.		ARRANG
			.2 SIZE AND CONFIGURATION TO RECOMMENDATIONS OF SMACNA.		
CKET.			INSULATION THICKNESS, IF REQUIRED).		AND ALL
T OF FIXTURE			.4 INSIDE AND OUTSIDE NYLON END BEARINGS.		INTERFE
			.5 CHANNEL FRAME OF SAME MATERIAL AS ADJACENT DUCT, COMPLETE WITH	.3	CONTRA
'E	9	DUCT	ANGLE STOP. I FAKAGE: IN ACCORDANCE WITH SMACNA HVAC AIR DUCT I FAKAGE TEST MANUAL		ΔΟΓΟΜΙ
' SIZE.	.10	ALL DU	JCT AND SEAL MATERIALS TO HAVE A FLAME SPREAD RATING OF LESS THAN 25 AND A	.4	COORDI
T OF FIXTURE		SMOK	E DEVELOPED CLASSIFICATION OF LESS THAN 50.	WIRIN	IG, WITH
	.11	PROVI	DE FLEXIBLE CONNECTIONS AT ALL EQUIPMENT DUCT CONNECTION POINTS.		ELECTRI
	<u>13 I</u>	DUCT INSU	ULATION:	<u>19 S</u>	TART-UP, (
	.1	REFER	TO DRAWING FOR DUCT THAT IS IDENTIFIED TO BE INSULATED.	.1	COMMIS
	.2		LL IN ACCORDANCE WITH THERMAL INSULATION ASSOCIATION OF CANADA (TIAC)		.1
	.3	MAX.	FLAME SPREAD RATING: 25.		
NUFACTURE,	.4	MAX. S	SMOKE DEVELOPED RATING: 50.		.2
CONCEALED UNLESS	.5	THERN 1	/IAL INSULATION - RECTANGULAR DUCT: 1" (R4-3) RIGID MINERAL FIBRE BOARD WITH VAPOUR RETARDER JACKET		
		.2	ALUMINUM JACKET WITH MOISTURE BARRIER.		
	.6	THERN	AL INSULATION - ROUND DUCT:		_
IN THE DRAWINGS.		.1	REFER TO ARCHITECTURAL DRAWINGS, TO VERIFY LOCATION OF ALL FIRE SEPARATIONS		.2
		.2	PROVIDE DRAWINGS FROM HILTI AND/OR 3M FOR FIRE PROTECTION OF ALL PIPING,		.3
			DUCT AND MECHANICAL ITEMS PENETRATING OR PASSING THROUGH A FIRE		
		3	SEPARATION OR FIRE-RATED ASSEMBLY, FOR REVIEW BY ARCHITECT AND ENGINEER,		.4
NDARD B181.2, FOR		.5	WITH FIRESTOPPING MATERIAL AT ALL FIRE SEPARATIONS AND FIRE-RATED	.3	DEMON
T MORE THAN 25 PER	-		MEMBRANES.		.1
NDARD B181.2. FOR	.2	ALL PII	PING SHALL BE TIGHTLY FITTED AND SEALED WITH FIRESTOPPING MATERIAL AT ALL FIRE		2
T MORE THAN 25 AND	.3	FIRE D	AMPERS:		.2
N/ULC-S102.2).		.1	FIRE DAMPERS SHALL BE CAN/ULC-S112 (STANDARD METHOD OF FIRE TEST OF FIRE		
		2	DAMPER ASSEMBLIES) LISTED AND LABELLED. FIRE DAMPERS SHALL BE NEPA 80 (STANDARD FOR FIRE DOORS AND OTHER OPENING		.3
		.2	PROTECTIVES), NFPA 90A (STANDARD FOR THE INSTALLATION OF AIR-CONDITIONING		.4
		_	AND VENTILATING SYSTEMS), AND NFPA 101 (LIFE SAFETY CODE) COMPLIANT.		
OLLOWS:		.3	DUCTWORK SHALL BE FITTED WITH FIRE DAMPERS AT ALL FIRE SEPARATIONS AND FIRE-		
		.4	SUPPLY AND INSTALL ACCESS DOORS IN ARCHITECTURAL FINISH (WALL, CEILING OR		
OR SUMMATION OF		_	FLOOR) TO ACCESS DUCT, IN COMMON AREA WHERE POSSIBLE.		
		.5	SUPPLY AND INSTALL TIGHTLY-FITTED ACCESS DOOR IN DUCT TO ACCESS, INSPECT AND		
AND REGULATORS.		.6	TYPES: DYNAMIC - FOR USE IN AIR HANDLING SYSTEMS THAT DO NOT SHUTDOWN		
			UPON FIRE ALARM.		
	Л	.7 EIRE D	RATING: 1-1/2 HR (30MIN TO 2HR FIRE RESISTANCE RATING).		
	.4	REQUI	REMENTS, AND SHALL BE SEALED WITH FIRESTOPPING MATERIAL.		
	.5	ALL M	ECHANICAL MATERIALS USED WITHIN CEILING RETURN AIR PLENUMS SHALL FLAME-		
		SPREA	D RATING NOT MORE THAN 25 AND SMOKE DEVELOPED CLASSIFICATION NOT MORE		
	.6	MOCK	-UPS:		
		.1	PREPARE MOCK-UPS OF TYPICAL FIRESTOP INSTALLATION OF THE FOLLOWING, FOR		
ALLATION CODE.			REVIEW AND APPROVAL BY THE OWNER, ENGINEER AND MUNICIPAL BUILDING		
			.1 SANITARY PIPING – WALL AND CEILING/FLOOR FIRE SEPARATION;		
			.2 DCW AND DHW PIPING – WALL AND CEILING/FLOOR FIRE SEPARATION;		
53/A653M ACHMENT TO ASHRAE		7	.3 FIRE DAMPER INSTALLATION – WALL AND CEILING/FLOOR FIRE SEPARATION.		
		.∠	APPROPRIATE PRODUCT INSTALLATION INSTRUCTIONS, AND THE REFERENCED UL/ULC		
		_	LISTING AND/OR TEST STANDARD.		
53/A653M		.3	SUPPLY A COPY OF THE PRODUCT INSTALLATION INSTRUCTIONS WITH ULC LISTING		
		.4	MOCK-UP MAY REMAIN AS PART OF WORK.		
LET):					
D DUCT,	15 1		CALIDENTIFICATION: IEV MECHANICAL FOURDMENT WITH LAREL STATING - NUMBER AND NAME		
	.1 .2	LABEL	ALL PIPING AT LEAST ONCE IN EVERY ROOM, AND AT NO MORE THAN 25 FT CENTERS.		

- NICAL ELEMENTS AND COMPONENTS (EQUIPMENT, PIPES, DUCTS, ETC.), AND THEIR CTIONS TO THE BUILDING SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE A/ANSI SEISMIC RESTRAINT MANUAL OR OTHER GUIDELINE REFERENCED IN THE IO BUILDING CODE.
- VING PROJECT COMPLETION, SEISMIC ENGINEER SHALL PROVIDE A LETTER OF FINAL SITE
- ACTOR SHALL CARRY THE COST OF THE SEISMIC ENGINEERING, INCLUDING SITE S, DESIGN AND SHOP DRAWING PREPARATION.

<u>FAND MATERIALS SUPPORT</u>

- CHANICAL EQUIPMENT, PIPING, DUCTWORK, AND RELATED ITEMS SHALL BE SECURELY RTED, ATTACHED AND FASTENED TO BUILDING STRUCTURE, AND SHALL NOT BE ED TO THE ROOF DECK.
- NGERS AND SUPPORTS SHALL BE FABRICATED AND INSTALLED IN ACCORDANCE WITH ANDARD SP-58, PIPE HANGERS AND SUPPORTS – MATERIALS, DESIGN, MANUFACTURE, ON, APPLICATION, AND INSTALLATION.
- RMS SHALL BE FABRICATED FROM STRUCTURAL GRADE STEEL MEETING THE EMENTS OF THE ONTARIO BUILDING CODE, INCLUDING CSA STANDARD W59 WELDED
- ONSTRUCTION, AND THE REQUIREMENTS OF THE CANADIAN WELDING BUREAU. ATION INVOLVING ACCURATE DIMENSIONING OF THE BUILDING SHALL BE TAKEN FROM
- SITE BY ACTOR.
 - NGS ARE IN DIAGRAMMATIC FORM, INTENDED TO CONVEY THE SCOPE OF WORK AND GENERAL
 - GEMENT FOR EQUIPMENT. COORDINATE PHYSICAL LOCATION OF ALL EQUIPMENT WITH OTHER TRADES
 - LOW FOR ANY ADDITIONAL PIPING, DUCTING, FITTINGS, SUPPORTS, ETC., IN ORDER TO AVOID
 - ERENCE AND FACILITATE THE WORK. ACTOR TO MAKE ANY NECESSARY MODIFICATIONS OR ADDITIONS, WITHOUT CHARGE,
 - IMODATE SITE CONDITIONS AND COORDINATION.
- INATE ALL MECHANICAL EQUIPMENT WIRING, INCLUDING LOW VOLTAGE CONTROL
- ICAL TRADES.
- COMMISSIONING AND TRAINING:
 - ISSIONING: START-UP AND COMMISSION THE FOLLOWING SYSTEMS:
 - PLUMBING FIXTURES; .2 HVAC.
 - PERFORM SYSTEMATIC TESTS, PROCEDURES AND CHECKS ON SYSTEMS, AS FOLLOWS:
 - TO VERIFY OPERATION IN ACCORDANCE WITH CONTRACT DOCUMENTS, .1 DESIGN CRITERIA AND INTENT, AND MANUFACTURER'S REQUIREMENTS;
 - TO ENSURE APPROPRIATE DOCUMENTATION IS PROVIDED; .2
 - TAB PROCEDURE SHALL BE COMPLETED IN ACCORDANCE WITH ASHRAE STANDARD 111, MEASUREMENT, TESTING, ADJUSTING AND BALANCING OF BUILDING HVAC SYSTEMS.
 - EXTERNAL STATIC PRESSURES SHALL BE MEASURED AFTER FILTER ON RETURN AIR AND BEFORE AC COIL AND SUPPLY AIR.
 - PROVIDE DETAILED REPORT AT END OF TAB, IN ACCORDANCE WITH THE REPORTING PROCEDURES OF ASHRAE STANDARD 111.
- **ISTRATION AND TRAINING:** DEMONSTRATE OPERATION AND MAINTENANCE OF EQUIPMENT AND SYSTEMS TO
- OWNER'S PERSONNEL ONE WEEK PRIOR TO DATE OF FINAL INSPECTION PRIOR TO DEMONSTRATION AND TRAINING, ENSURE THAT EQUIPMENT HAS BEEN INSPECTED AND PUT INTO OPERATION, INCLUDING COMPLETION OF COMMISSIONING AND TESTING, ADJUSTING, AND BALANCING.
- DEMONSTRATE START-UP, OPERATION, CONTROL, ADJUSTMENT, TROUBLE-SHOOTING, SERVICING, AND MAINTENANCE OF EACH ITEM OF EQUIPMENT.
- INSTRUCT PERSONNEL IN PHASES OF OPERATION AND MAINTENANCE USING OPERATION AND MAINTENANCE MANUALS AS BASIS OF INSTRUCTION. REVIEW CONTENTS OF MANUAL IN DETAIL TO EXPLAIN ASPECTS OF OPERATION AND MAINTENANCE.



											- E	XHAUST FAN (CABINET) S	SCHEDULE					
UNIT DESCRIPTION	.E		SIZE			ACCE	PTABLE PRODUCT		Ν	IOTES			FAN FLOW ESP DRIVE	DUCT SONES CONN VOL	ELECTRICAL ACCEPTAB	LE PRODUCT NOTES		
	(in)	/ASTE VEI (in) (in	NT DCV) (in)	/ DHW (in)								EF-1 EXHAUST FAN	39 L/s 3 mm DIRECT	(V) 2.3 254 x 83 mm 120	(W) 0 1 39 PENN BARR	Y DIM - L x W x D - 318 x 232 x 232 mm, 12.5 x 9	9.125 x 9.125 in	III MORRIS III
WC-1 WATER CLOSET - TANK	(mm) (I INT	(mm) (mr 3" 2'	n) (mm ' 1/2') (mm) -	WATERCL	OSET - AMERIC	AN STANDARD #246	2 (CADET)	PRESSURE ASSISTED, ELONGATE	D WHITE	-	٤ ٤	83 CFM 0.125 in	10 x 3.25 in	#Z3 GREENHECH	GRILLE - 280 x 337 mm, 11 x 13.25 in CONTROL - WALL SWITCH		
		75 50) 13	-	SEAT - CE	ENTOCO #820STS OVED EQUAL	8		HEAVY DUTY, OPEN FRONT SEAT MAX. WATER CONSUMPTION - 6.0	& COVER, SS HINGE Lpf, 1.6 gpf					OR APPROV	ED EQUAL GRILLE - POLYMER WALL CAP - STEEL, PAINTED TO MATCH WA	ALL	📗 Engineering Ltd. 📗
									DIM L x W x H - 768 x 521 x 743 mm RIM HEIGHT - 381 mm, 15 in	, 30.25 x 20.5 x 29.25 in						LINED HOUSING, BACKDRAFT DAMPER		Brockville, Ontario 613-349-0555
									FLOOR FLANGE, FLANGE BOLTS 8 ISOLATING VALVE - BRASS W CHF	GASKET ROME FINISH,	F	REGISTER, GRILLE & DIFFUUNITDESCRIPTION	CONSTRUCTION	CONFIGURATION	N FRAME	FINISH ACCEPTABLE PRODUCT	NOTES	
									WALL-MOUNTED, SCREWDRIVER	STOP			PA	ATTERN BLADE SPACING	DEFLECTION (deg)			
WC-2 WATERCLOSET - TANK BARRIER FREE	INT	3" 2' 75 50	' 1/2') 13	-	WATERCLO	OSET - AMERIC NTOCO #820STS	AN STANDARD #246 S	7 016 (CADET)	PRESSURE ASSISTED, ELONGATE HEAVY DUTY, OPEN FRONT SEAT	D WHITE & COVER, SS HINGE		S1 SA DIFFUSER CEILING	STEEL 4	CONE - FIXED	- LAY-IN INVER DRY WALL FLA	TED T WHITE EH PRICE ANGE #SCD STEEL		
					OR APPRO	OVED EQUAL			MAX. WATER CONSUMPTION - 6.0 DIM L x W x H - 768 x 521 x 781 mm	Lpf, 1.6 gpf , 30.25 x 20.5 x 30.75 in		SQUARE CONE	AIR	PATTERN		OR APPROVED EQUAL		
									RIM HEIGHT - 419 mm, 16.5 in SEAT HEIGHT - 430 to 485 mm, 17 to	o 19 in (OBC 3.8.3.9)	_	S2 LOUVRED SA GRILLE WALL	STEEL S	INGLE 19mm, 3/4 in LECTION PARALLEL	ADJUSTABLE STANDAR 32mm, 1.25	D WHITE EH PRICE Sin #510 STEEL SINGLE		
									FLOOR FLANGE, FLANGE BOLTS & ISOLATING VALVE - BRASS W CHF	GASKET ROME FINISH,	_							
									WALL-MOUNTED, SCREWDRIVER	STOP	-	CEILING		20 GRID 12x12x25mm 1/2x1/2x1in	0 LAY-IN INVER DRYWALL FLA	ANGE #81		
LA-1 LAVATORY COUNTERTOP	1-1/2 1- 38	I-1/2" 1-1/ 38 32	4" 1/2 2 13	1/2" 13	AMERICAN #9494 LAV	N STANDARD /ATORY			WHITE, POP-UP DRAIN OVERALL DIM - W x FTB x D - 533 x	: 445 x 165mm, 21 x 17.5 x 6.5 in								
					#7385 SINC	GLE LEVER FAU	ICET		BOWL DIM - W x FTB x D - 441 x 27 MAX. WATER CONSUMPTION - 8.35	9 x 133mm, 17.375 x 11 x 5.25 in 5 Lpm, 2.2 gpm		CEILING/WALL	DEF	LECTION PARALLEL	32mm, 1.25	5in #530 STEEL SINGLE		
LA-2 LAVATORY	1-1/2" 1	-1/2" 1-1/	4" 1/2	1/2"	OR APPRO	OVED EQUAL			INSULATE AND COVER ALL SAN, D WHITE, POP-UP DRAIN	OCW & DHW PIPE						OR APPROVED EQUAL		
WALL HUNG	38	38 32	2 13	13	#0954 (MUI #7385 SINC	IRRO) LAVATOR` GLE LEVER FAU	Y W EVERCLEAN		OVERALL DIM - W x FTB x D - 540 x BOWL DIM - W x FTB x D - 394 x 34	x 520 x 406mm, 21.25 x 20.5 x 16 in 3 x 127mm, 15.5 x 13.5 x 5 in	-							
					WATTS #C	CA-411 FLOOR-M Y CARRIER	OUNTED, CONCEAI	ED ARM	MAX. WATER CONSUMPTION - TO O	OBC BC & ARCH DWGS								
					P-TRAP - 1 ISOLATING	1-1/4 (32) TRAP, G VALVE - BRAS	CHROME PLATED E S W CHROME FINIS	RASS H,										
					WALL-MOU	UNTED, SCREW	DRIVER STOP)							EXHAUST FAN			
					OR APPRO	OVED EQUAL									HOOD			
LA-3 LAVATORY WALL HUNG	1-1/2" 1- 38	I-1/2" 1-1/ 38 32	4" 1/2 2 13	1/2" 13	AMERICAN #0954 (MU	N STANDARD IRRO) LAVATOR'	Y W EVERCLEAN		WHITE, POP-UP DRAIN OVERALL DIM - W x FTB x D - 540 x	: 520 x 406mm, 21.25 x 20.5 x 16 in					Ň			
BARRIER FREE					#7385 SINC	GLE LEVER FAU CA-411 FLOOR-M	ICET OUNTED, CONCEAI	.ED ARM	BOWL DIM - W x FTB x D - 394 x 34 MAX. WATER CONSUMPTION - TO	3 x 127mm, 15.5 x 13.5 x 5 in OBC								
					LAVATORY P-TRAP - 1	Y CARRIER 1-1/4 (32) TRAP,	CHROME PLATED E	RASS	INSTALLATION DIMENSIONS - TO O	BC & ARCH DWGS								
					ISOLATING	G VALVE - BRAS	S W CHROME FINIS DRIVER STOP	iΗ,										
					PORCELAI	IN SHROUD/KNE	E CONTACT GUARI)										
SK-1 KITCHEN SINK	1-1/2" 1	-1/2" 1-1/	4" 1/2	1/2"	OR APPRO	OVED EQUAL KINDRED #LB640	7 SINK		STAINLESS STEEL, LEVER HANDLI	ES	-							11
SINGLE BOWL WITH LEDGE	38	38 32	2 13	13	AMERICAN	N STANDARD #6	270 FAUCET		OVERALL DIM - W x FTB x D - 794 x BOWL DIM - W x FTB x D - 355 x 40	: 520 x 178mm, 31.25 x 20.5 x 7 in 6 x 178mm, 14 x 16 x 7 in	-							
SK-2 KITCHEN SINK	1-1/2" 1	-1/2" 1-1/	4" 1/2	1/2"	OR APPRO	OVED EQUAL KINDRED #LBD64	107 SINK		MAX. WATER CONSUMPTION - 8.35 STAINLESS STEEL, LEVER HANDL	i Lpm, 2.2 gpm ES	-							
DOUBLE BOWL WITH LEDGE	38	38 32	2 13	13	AMERICAN	N STANDARD #6	270 FAUCET		OVERALL DIM - W x FTB x D - 794 x BOWL DIM - W x FTB x D - 355 x 40	: 520 x 178mm, 31.25 x 20.5 x 7 in 6 x 178mm, 14 x 16 x 7 in								
CW CLOTHESWASHER	2"	2" 1-1/	2" 1/2	1/2"	OR APPRO	OVED EQUAL R EQUAL			MAX. WATER CONSUMPTION - 8.35 PROVIDE RECESSED WALL BOX	Epm, 2.2 gpm	-					EX. ROOF		
FIRE-RATED	50	50 38	3 13	13					FOR SAN., DCW, DHW									
FCO FLOOR CLEANOUT ROUND	- S	SIZE - PER	_	-	WATTS CC ZURN	D-200			SUIT FLOOR FINISH CAST IRON BODY							EXHALIST FAN		
	P	PIPE			OR APPRO	OVED EQUAL			NICKEL BRONZE TOP, GASKET BRASS CLEANOUT PLUG, GASKET							HOOD DETAIL		1 B.O'B. 2024 03 19 FOR PERMIT & TENDER 0 B.O'B. 2024 03 01 FOR PERMIT & TENDER
WCO WALL CLEANOUT ROUND	- S	SIZE - PER		-	WATTS CC ZURN	D-380			SUIT WALL FINISH CAST IRON FERRULE		-					SCALE: $ \frac{1}{2} ' = -O '$		No By Date Bevisions
	P	PIPE			OR APPRO	OVED EQUAL			BRASS PLUG STAINLESS STEEL COVER									
ROOFTOP HVAC UNIT SCHEDU	ILE																	All drawings, specifications and related documents are the copyright property of the Engineer and must be returned upon request. Reproduction of drawings, specifications, and related documents in part or whole is forbidden without the
UNIT DESCRIPTION	SUPPLY AIR		R EFF.	TEMF	DOLING P TC	INPUT OUTF	ING PUT GAS VOL	ELECTRICAL	ACCEPTABLE PRODUC		NOTES							Engineers' written permission. The contractor must check and verify all dimensions on the job prior to
RTU-1 PACKAGED	(cfm) (ESP) 2200 0.6) (cfm) 300	(SEEF 14	2) (deg.F 80 DE	-) (Mbtu/hr) 3 60) (Mbtu/hr) (Mbtu 115 93	/hr) (in) 1/2 208	3 29	40 CARRIER	BASE UNIT:		_						start of construction. DRAWINGS ARE NOT TO BE SCALED
RTU-2 ROOFTOP HVAC UNIT RTU-3 ELECTRIC COOLING				67 WI 95 AM	B				LENNOX TRANE	SEISMIC ROOF CURB HOT GAS REHEAT DEHUMID	FICATION							
RTU-4 NATURAL GAS HEATING RTU-5										POWER EXHAUST FAN W BA COIL/HAIL GUARDS								PROFESSION 41
																		2024-3-19 R
										COOLING SYSTEM: HIGH EFFICIENCY								S M. A. MORRIS S
										LOW AMBIENT OPERATION T	HROUGH ECONOMIZER							3
											۲۷۵)	-1						INCE OF ON T
											P	-1						
											TENSION	_						ASTERN
												-						
												-1						CONSULTING ENGINEERS
										BLOWER PROVING SWITCH		_						Apex BuildingTelephone: (613) 345-0400207 - 100 Strowger Blvd.Facsimile: (613) 345-0008Brookaille.Oct. (612) 12
												_						Project Title:
										MERV 8 FILTERS								NORTH STORMONT
												-						MUNICIPAL OFFICE
										ELECTRICAL:	HERPROOF DISC. SWITCH	-						57 COCKBURN STREET,
										NEW WEATHERPROOF DISC GFCI SERVICE OUTLET WITH	ONNECT SWITCH	-						BERWICK, ON Drawing Title:
										PHASE/VOLTAGE PROTECTION	N							
										CONTROLS: DEMAND CONTROL VENTILA	TION WITH CO2 SENSOR	-						SCHEDULES & DETAILS
										7-DAY DIGITAL PROGRAMMA TO MEET ASHRAE 90.1	BLE THERMOSTAT	_						<i> </i>
										- 7 DAY SCHEDULE - 10 HR POWER LOSS								Design: Checked: Approved: Project No.: MM MM 11200-M&F
										- 2 HR MANUAL OVERRIDE - SETBACK TO 55F (13C)		_						Drawn: Checked: Date: Contract No.: B.O'B. MM 2023 11 30 Contract No.:
										- SETUP TO 90F (32C) REMOTE TSTAT WITH ROOM	SENSORS	_						Scale: 0 10'-0" 20'-0" Drawing No.:
										MICROPROCESSOR CONTRO BACnet COMMUNICATIONS IN	DLS ITERFACE	_						Horizontal: 1/16" = 1'-0"
	1		-	•	- •	I	I	I	· · ·			_						Vertical: 1/16" = 1'-0" REV DATE: 3/19/2024













ELECTRICAL NOTES

ELECTRICAL DRAWINGS SHALL BE READ IN CONJUNCTION WITH ALL OTHER DRAWINGS FOR THIS <u>PROJECT.</u>

1 GENERAL:

8

- .1 CONFORM WITH APPLICABLE REQUIREMENTS OF THE MINISTRY OF LABOUR, AND THE OCCUPATIONAL HEALTH AND SAFETY ACT AND REGULATIONS FOR CONSTRUCTION PROJECTS.
- DO COMPLETE INSTALLATION IN ACCORDANCE WITH THE FOLLOWING: .2
- ONTARIO ELECTRICAL SAFETY CODE; .1 ELECTRICAL SAFETY AUTHORITY:
- ELECTRICAL SUPPLY AUTHORITY.
- SUBMIT TO ELECTRICAL SAFETY AUTHORITY AND SUPPLY AUTHORITY NECESSARY NUMBER OF
- DRAWINGS AND SPECIFICATIONS FOR APPROVAL PRIOR TO COMMENCEMENT OF WORK. GENERAL CONTRACTOR AND ELECTRICAL CONTRACTOR SHALL ASSUME FULL RESPONSIBILITY FOR COORDINATING AND OBTAINING ELECTRICAL SERVICE LAYOUT FROM THE SUPPLY AUTHORITY.
- PAY ALL ELECTRICAL PERMIT AND INSPECTION FEES.
- GROUND COMPLETE SYSTEM IN ACCORDANCE WITH THE ONTARIO ELECTRICAL SAFETY CODE AND ELECTRICAL SAFETY AUTHORITY.
- IDENTIFICATION AND LABELLING: .1
- IDENTIFY ELECTRICAL EQUIPMENT WITH LAMICOID NAMEPLATES, INCLUDING AMPERAGE, VOLTAGE, PHASE AND POWER SOURCE.
- PROVIDE TYPEWRITTEN PANEL DIRECTORIES.
- PROVIDE ADHESIVE LABEL ON ALL SWITCH, RECEPTACLE AND DEVICE COVER PLATES INDICATING SUPPLY CIRCUIT DESIGNATION.
- PROVIDE DIGITAL AND HARD COPY OF COMPLETE OPERATING AND MAINTENANCE INSTRUCTIONS FOR

EQUIPMENT FURNISHED UNDER THIS CONTRACT. BIND INSTRUCTIONS IN 3-RING BINDERS. INCLUDE THE

- FOLLOWING:
- SCHEMATIC DIAGRAM OF ELECTRICAL SYSTEMS. CONTROL SHOP DRAWINGS AND OPERATING SEQUENCE INCLUDING WIRING OF .2 COMPONENTS.
- WIRING DIAGRAM OF CONTROL PANELS.
- OPERATING INSTRUCTIONS, INCLUDING START-UP AND SHUT-DOWN PROCEDURE. MAINTENANCE INSTRUCTIONS INCLUDING PREVENTIVE MAINTENANCE INSTRUCTIONS FOR COMPONENTS OF THE EQUIPMENT.
- COMPLETE PARTS LIST OF ASSEMBLIES AND THEIR COMPONENT PARTS, SHOWING MANUFACTURER'S NAME, CATALOGUE NUMBER, AND NEAREST REPLACEMENT
- SOURCE. LIST OF RECOMMENDED SPARE PARTS AND QUANTITY OF EACH ITEM TO BE STOCKED. MANUFACTURERS' WARRANTIES AND GUARANTEES.
- CLEAN ALL ELECTRICAL SYSTEMS AT PROJECT COMPLETION.
- .10 COMPLETE AS-BUILT DRAWINGS SHOWING ALL CHANGES AS WORK PROGRESSES.
 - COORDINATE WORK WITH OTHER TRADES SO THAT THERE IS A MINIMUM OF CUTTING, FITTING AND PATCHING.
 - DRILLING, CUTTING, FITTING AND PATCHING AND MAKING GOOD WHERE NECESSARY 3 DUE TO FAILURE TO DELIVER ITEMS TO BE BUILT IN TIME OR INSTALLATION IN WRONG LOCATION, SHALL BE EXECUTED AS DIRECTED AT NO COST TO THE OWNER.
 - DRILLING AND CUTTING OF LOAD BEARING STRUCTURAL MEMBERS SHALL BE DONE ON PRIOR EXPRESS WRITTEN PERMISSION OF THE ENGINEER FOR EACH INSTANCE.
 - CUT HOLES ACCURATELY, WITH SMOOTH, TRUE, CLEAN EDGES. FIT UNITS TO .5 TOLERANCES TO BEST STANDARD PRACTICE FOR APPLICABLE WORK.
 - HOLES IN BLOCK AND CONCRETE WORK SHALL BE SAWCUT OR CORE-DRILLED, AND .6 SHALL NOT BE MADE WITH A HAMMER GUN.
 - PATCHED WORK SHALL BE INVISIBLE, SIZE HOLES AND OPENINGS FOR PIPES SO AS TO ALLOW FOR EXPANSION AND CONTRACTION OF SUCH PIPES.

4 FIXTURES AND EQUIPMENT:

PROVIDE SHOP DRAWINGS AND PRODUCT DATA FOR ALL ELECTRICAL FIXTURES AND

- EQUIPMENT FOR APPROVAL, PRIOR TO PROCUREMENT.
- INSTALL ALL ELECTRICAL FIXTURES AND EQUIPMENT IN ACCORDANCE WITH MANUFACTURER'S INSTRUCTIONS.
- EQUIPMENT AND MATERIAL TO BE CSA CERTIFIED. WHERE THERE IS NO ALTERNATIVE TO SUPPLYING EQUIPMENT WHICH IS NOT CSA CERTIFIED, OBTAIN SPECIAL APPROVAL FROM ELECTRICAL SAFETY AUTHORITY.

5 EQUIPMENT SUPPLIED BY OTHERS:

- GENERAL CONTRACTOR SHALL ASSUME FULL REPONSIBILITY FOR COORDINATING ELECTRICAL SERVICES AND CONNECTIONS FOR ALL EQUIPMENT, INCLUDING EQUIPMENT SUPPLIED BY TRADES OTHER THAN ELECTRICAL.
- ELECTRICAL CONTRACTOR SHALL TAKE FULL REPONSIBILITY FOR MAKING ALL ELECTRICAL SERVICE CONNECTIONS TO EQUIPMENT SUPPLIED BY OTHERS, INCLUDING:
- REVIEW OF ALL SHOP DRAWINGS FOR EQUIPMENT SUPPLIED BY OTHERS, WHICH .1 REQUIRE ELECTRICAL CONNECTIONS.
- .2 VERIFY AND CONFIRM ALL SERVICE CONNECTIONS WITH MANUFACTURER, SUPPLIER AND OTHER TRADES, PRIOR TO PROCUREMENT OF ELECTRICAL PANELS, BREAKERS, WIRE/CABLE, DISCONNECT SWITCHES, MOTOR STARTERS, RECEPTACLES AND RELATED
- EQUIPMENT. REVIEW OF EQUIPMENT SUPPLIED BY OTHERS, SHALL INCLUDE ALL CONNECTION SIZES, LOCATIONS AND DETAILS, AND SHALL TAKE INTO ACCOUNT EQUIPMENT CLEARANCES AND INSTALLATION REQUIREMENTS.

6 CONDUITS:

- RIGID GALVANIZED STEEL, WITH THREADED FITTINGS, WHERE SUBJECT TO MECHANICAL INJURY, IN SERVICE AREAS ONLY.
- ELECTRICAL METALLIC TUBING (EMT), HOT DIPPED GALVANIZED STEEL, WITH THREADED CONNECTORS AND COUPLINGS, WHERE NOT SUBJECT TO MECHANICAL INJURY, IN SERVICE AREAS ONLY.
- RIGID PVC CONDUIT BELOW FLOOR AND IN CORROSIVE AREAS.

7 WIRES AND CABLE:

- .3 CEILING RETURN AIR PLENUMS – TYPE AC90.
- ALL WIRING, CABINETS AND BOXES SHALL BE CONCEALED IN WALLS AND CEILINGS, UNLESS .4 OTHERWISE NOTED OR APPROVED. SURFACE-MOUNTED WIRING IS NOT PERMITTED.

8 SERVICE EQUIPMENT:

- ELECTRICAL SERVICE EQUIPMENT, PANELBOARDS AND DISCONNECT SWITCHES SHALL BE PRODUCT OF ONE MANUFACTURER THROUGHOUT PROJECT. CIRCUIT BREAKERS:
- SUPPLY AND INSTALL GROUND FAULT & ARC-FAULT CIRCUIT PROTECTION, AS
- REQUIRED BY THE OESC. WORKING SPACE ABOUT ELECTRICAL EQUIPMENT SHALL BE PROVIDED IN ACCORDANCE WITH .3 THE ONTARIO ELECTRICAL SAFETY CODE, INCLUDING THE FOLLOWING: .1
- WORKING SPACE OF 3'4" (1m) WITH SECURE FOOTING; MINIMUM HEADROOM OF 7'3" (2.2m). .2
- 9 WIRING DEVICES:
- .1 OUTLET BOXES:
 - GANG BOXES WHERE WIRING DEVICES ARE GROUPED. .2 BLANK COVER PLATES FOR BOXES WITHOUT WIRING DEVICES.
- .2 SWITCHES:
 - HEAVY DUTY, 20A/120V;
- SINGLE POLE, AND THREE-WAY, AS APPLICABLE; COLOUR: SELECTED BY OWNER/ARCHITECT.
- DUPLEX RECEPTACLES: .3 EXTRA HARD USE, CSA TYPE 5-15 R, 15A/125V;
- GFI (GROUND FAULT CIRCUIT INTERRUPTER) WITH DETECT AND TRIP ON
- TAMPER-RESISTANT WHERE REQUIRED BY CODE;
- COLOUR: SELECTED BY OWNER/ARCHITECT. .4 COVER PLATES:
- .1 STAINLESS STEEL.

10 LIGHTING:

.1

.3

.4

.5

- GENERAL LIGHTING: SUPPORT ALL LIGHTING IN ACCORDANCE WITH THE ONTARIO ELECTRICAL SAFETY CODE .1 AND
- BULLETINS. LIGHT FIXTURES SUPPORTED BY SUSPENDED CEILING SYSTEMS SHALL HAVE ADDITIONAL .2 SUPPORT TO
- BULLETIN #30-4-11. .2 FUNCTIONAL TESTING OF LIGHTING CONTROL, IN ACCORDANCE WITH ASHRAE 90.1 (9.4.3):
- LIGHTING CONTROL DEVICES AND CONTROL SYSTEMS SHALL BE TESTED TO ENSURE 1 THAT CONTROL HARDWARE AND SOFTWARE ARE CALIBRATED, ADJUSTED, PROGRAMMED, AND IN PROPER WORKING CONDITION IN ACCORDANCE WITH THE
- CONSTRUCTION DOCUMENTS AND MANUFACTURER'S INSTALLATION INSTRUCTIONS. EXIT AND EMERGENCY LIGHTING: REFER TO ARCHITECTURAL DRAWINGS, TO VERIFY LOCATION OF ALL FIRE SEPARATIONS
- AND FIRE-RATED MEMBRANES. .2 PROVIDE DRAWINGS FROM HILTI AND/OR 3M FOR FIRE PROTECTION OF ALL
- ELECTRICAL MATERIALS, INCLUDING PANELS, BOXES, CABLE, WIRE, CONDUIT AND OUTLETS PENETRATING OR PASSING THROUGH A FIRE SEPARATION OR FIRE-RATED ASSEMBLY, FOR REVIEW BY ARCHITECT AND ENGINEER, ALL ELECTRICAL MATERIALS, INCLUDING PANELS, BOXES, CABLE, WIRE, CONDUIT AND .3
- OUTLETS SHALL BE TIGHTLY FITTED AND SEALED WITH FIRESTOPPING MATERIAL AT ALL FIRE SEPARATIONS AND FIRE-RATED MEMBRANES.
- ALL CABLING AND CONDUIT SHALL BE TIGHTLY FITTED AND SEALED WITH FIRESTOPPING .2

- .2 PLENUMS (OBC 3.6.4.3):
- .1 THAN 25 AND A
- ELECTRICAL WIRES
- AND CABLES. .3
- SMOKE CHARACTERISTICS OF ELECTRICAL WIRING AND CABLES.
- MOCK-UPS: PREPARE MOCK-UPS OF TYPICAL FIRESTOP INSTALLATION OF THE FOLLOWING, FOR .1 REVIEW AND APPROVAL BY THE OWNER, ENGINEER AND MUNICIPAL BUILDING
- INSPECTOR: .1 ELECTRICAL PANELS, BOXES AND OUTLETS – FIRE-RATED WALL; CONDUIT AND CABLING – WALL AND CEILING/FLOOR FIRE SEPARATION. .2
- .2 ALL FIRESTOP INSTALLATIONS SHALL BE COMPLETED IN ACCORDANCE WITH THE APPROPRIATE PRODUCT INSTALLATION INSTRUCTIONS, AND THE REFERENCED UL/ULC
- LISTING AND/OR TEST STANDARD. SUPPLY A COPY OF THE PRODUCT INSTALLATION INSTRUCTIONS WITH ULC LISTING .3
- AND/OR TEST STANDARD REFERENCE, FOR EACH INSTALLATION. MOCK-UP MAY REMAIN AS PART OF WORK. .4

12 EARTHQUAKE LOAD:

AND EFFECTS REQUIRED BY THE ONTARIO BUILDING CODE. ELECTRICAL ELEMENTS AND COMPONENTS (FIXTURES, EQUIPMENT, CONDUIT, ETC.), AND THEIR .2 CONNECTIONS TO THE BUILDING SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE SMACNA/ANSI SEISMIC RESTRAINT MANUAL OR OTHER GUIDELINE REFERENCED IN THE

- MATERIAL AT ALL FIRE SEPARATIONS AND FIRE-RATED MEMBRANES. .3 THE FOLLOWING CONDUCTORS SHALL BE PROTECTED IN ACCORDANCE WITH OBC 3.2.7.10(2), AND SHALL CONFORM TO ULC-S139 "FIRE TEST EVALUATION OF INTEGRITY OF ELECTRICAL CABLES", TO PROVIDE A CIRCUIT INTEGRITY RATING OF NOT LESS THAN 1 HOUR (2 HOUR FOR TALL BUILDINGS OR CONTAINED USE AREAS OR INTERCONNECTED FLOOR SPACES): ELECTRICAL FEEDER CONDUCTORS WHICH SERVE THE COMMERCIAL ELECTRICAL PANELS; BRANCH CIRCUIT CONDUCTORS WHICH SERVE EXIT AND EMERGENCY LIGHTING.
 - ALL MATERIALS WITHIN THE PLENUM SHALL A FLAME-SPREAD RATING NOT MORE
 - SMOKE DEVELOPED CLASSIFICATION NOT MORE THAN 50.
 - WIRE AND CABLE WITH AN FT6 RATING TO CSA C22.2 NO. 0.3, TEST METHODS FOR
 - NON-METALLIC RACEWAYS WITH AN FT6 RATING TO CAN/ULC- S102.4, FIRE AND

.1 WIRING DEVICES OF ONE MANUFACTURER THROUGHOUT PROJECT – HUBBELL OR LEVITON:

GROUND FAULT, STATUS INDICATOR LIGHT AND TEST SWITCH;

BUILDING STRUCTURE IN ACCORDANCE WITH ONTARIO ELECTRICAL SAFETY CODE

ALL ELECTRICAL WORK SHALL BE COMPLETED IN ACCORDANCE WITH THE EARTHQUAKE LOAD

ONTARIO BUILDING CODE AND ONTARIO ELECTRICAL SAFETY CODE.

.3 PLATFORMS SHALL BE FABRICATED FROM STRUCTURAL GRADE STEEL MEETING THE REQUIREMENTS OF THE ONTARIO BUILDING CODE, INCLUDING CSA STANDARD W59 WELDED STEEL CONSTRUCTION, AND THE REQUIREMENTS OF THE CANADIAN WELDING BUREAU.

14 COORDINATION:

.1

- INFORMATION INVOLVING ACCURATE DIMENSIONING OF THE BUILDING SHALL BE TAKEN FROM SITE BY CONTRACTOR.
- DRAWINGS ARE IN DIAGRAMMATIC FORM, INTENDED TO CONVEY THE SCOPE OF WORK AND GENERAL ARRANGEMENT FOR EQUIPMENT. COORDINATE PHYSICAL LOCATION OF ALL EQUIPMENT WITH OTHER TRADES AND ALLOW FOR ANY ADDITIONAL CONDUIT, WIRING, FITTINGS, SUPPORTS, ETC., IN ORDER TO AVOID
- INTERFERENCE AND FACILITATE THE WORK. CONTRACTOR TO MAKE ANY NECESSARY MODIFICATIONS OR ADDITIONS, WITHOUT CHARGE, TO .3 ACCOMMODATE SITE CONDITIONS AND COORDINATION.
- COORDINATE AND VERIFY ALL ELECTRICAL BRANCH CIRCUIT REQUIREMENTS FOR EQUIPMENT SUPPLIED BY .4 OTHERS, PRIOR TO MATERIAL PROCUREMENT OR INSTALLATION.
- PROVIDE ALL WIRING TO ALL MECHANICAL EQUIPMENT, INCLUDING WIRING BELOW 50V. COORDINATE ALL MECHANICAL EQUIPMENT WIRING WITH MECHANICAL TRADES. .6 ALL DEVICE AND OUTLET LOCATIONS SHALL BE CAREFULLY COORDINATED WITH THE GENERAL CONTRACTOR OR
- OWNER, TO ACCOMMODATE ALL FEATURES, INCLUDING PLUMBING FIXTURES, EQUIPMENT AND MILLWORK.

15 START-UP, COMMISSIONING AND TRAINING:

- START-UP AND COMMISSION THE FOLLOWING SYSTEMS: MAIN ELECTRICAL SERVICE EQUIPMENT;
- GENERAL LIGHTING;
- EXIT AND EMERGENCY LIGHTING.
- .2 PERFORM SYSTEMATIC TESTS, PROCEDURES AND CHECKS ON SYSTEMS, AS FOLLOWS: TO VERIFY OPERATION IN ACCORDANCE WITH CONTRACT DOCUMENTS, DESIGN CRITERIA AND INTENT, AND MANUFACTURER'S REQUIREMENTS;
 - TO ENSURE APPROPRIATE DOCUMENTATION IS PROVIDED;
 - TO EFFECTIVELY TRAIN BUILDING OPERATIONAL STAFF.
- SYSTEMS ARE TO BE OPERATED AT FULL CAPACITY, WITH CORRECTION OF ALL DEFICIENCIES AND ADJUSTMENTS .3 TO MEET OPTIMUM PERFORMANCE.
- .4 PROVIDE WRITTEN REPORT AT END OF COMMISSIONING OUTLINING EQUIPMENT OPERATIONAL CONDITIONS AND PARAMETERS.

ELECTR	RICAL LEGEND							
NOTE: HEIGH LINE (IT IS FROM FINISHED FLOOR TOP TO DF EQUIPMENT, UNLESS OTHERWISE NOTE	ĒD	HEIGHT					
DESIGI	NATIONS							
GFCI AFCI	GROUND FAULT CIRCUIT INTERRUPTER ARC FAULT CIRCUIT INTERRUPTER							
AC AFF	ABOVE COUNTER ABOVE FINISHED FLOOR							
DISTRIE	SUTION							
	DISTRIBUTION PANEL		72"/1825mm (TOP)					
\$ \$.	SINGLE POLE TOGGLE SWITCH - 20A/120	35.5" / 900mm TO						
\$м	MOTION SENSOR CONTROL - (SWITCH)		43.3 / 1 1 00mm					
•	MOTION SENSOR CONTROL - (CEILING)							
₩	MOTION SENSOR & DAYLIGHT PHOTOCE	LL CONTROL - (CEILING)	2"/3∩0mm					
₩ ₩	DUPLEX RECEPTACLE (SPLIT) - 15A/120V	/	1 2"/300mm					
\bigcirc	NON-STANDARD RECEPTACLE		AS NOTED					
	DIRECT EQUIPMENT CONNECTION		AS NOTED					
	NON-FUSED DISCONNECT SWITCH		54"/1370mm					
	FUSED DISCONNECT SWITCH BRANCH CIRCUIT		54"/1370mm					
	BRANCH CIRCUIT, SWITCHED							
	BRANCH CIRCUIT, HOMERUNS TO PANEL	L						
	NG							
F F	FLUORESCENT LIGHT FIXTURE - RECESS							
F	FLUORESCENT LIGHT FIXTURE - SURFA							
ф	LIGHT FIXTURE F - FLUORESCENT							
φ	H - HIGH INTENSITY DISCHARGE L - INCANDESCENT							
DATA								
V	TELEPHONE OUTLET (WALL)		l 2"/300mm					
	TELEPHONE OUTLET (FLOOR)	ROVIDE 3/4" CONDUIT ROM BACK BOX TO						
	DATA OUTLET (WALL) SI DATA OUTLET (FLOOR) SI	USPENDED CEILING PACE ROUGH-IN ONLY	12"/300mm					
V	DATA ∉ TELEPHONE OUTLET (WALL)		l 2"/300mm					
∇	TELEVISION OUTLET (WALL)		l 2"/300mm					
	SPEAKER (WALL / CEILINC)							
6	WIRELESS TRANSMITTER / RECEVER							
EXIT &	EMERGENCY LIGHTING	,						
E ₁	EXIT LIGHT, SURFACE MOUNTED, SING	GLE FACE	90"/2300mm					
E ₂	EXIT LIGHT, END OR CEILING MOUNTED	D, SINGLE FACE	90"/2300mm					
E	EXIT LIGHT, END OR CEILING MOUNTED	D, DOUBLE FACE	90"/2300mm					
	EXIT LIGHT, SURFACE MOUNTED. SING	SLE FACE						
	EMERGENCY LIGHT, BATTERY PACK		90"/2300mm					
EL3	EMERGENCY LIGHT, DOUBLE REMOTE		90"/2300mm					
ÆEL4	EMERGENCY LIGHT, SINGLE REMOTE		90"/2300mm					
FIRE A	LARM							
∇								
ب	FIRE ALARM HORN / STROBE		ALL FIRE ALARM					
∑15cd	FIRE ALARM HORN / BELL WITH STROE	BE LIGHT	NEVICES SHALL BE MOUNTED AND					
	FIRE ALARM PULL STATION - (47" / 12	200mm)	ACCORDANCE WITH CAN/ULC - 5524					
Ø	FIRE ALARM HEAT DETECTOR							
0	FIRE ALARM SMOKE DETECTOR							



	N						
	511						-
OTHER TYPES OF OCCUPANCY (OESC 8-210)							
BASIC LOAD			AREA	AREA	BASIC LOAD		D
			(sq.ft.)	(sq.m)	(W/sq.m.)		E
OFFICE BUILDING			8700	808	50		
DAYCARE			7560	702	25		
ADDITIONAL LOAD		QTY	LOAD	LOAD	VOLTAGE	PHASE	D
			(W)	(Amp)	(V)	FACTOR	E/
WATER HEATER		1	3000				
AR CONDITIONING:							
- Library		5		29	208	1.73	
TOTAL LOAD							
TOTAL LOAD	VOLTAGE	PHASE					
	(V)	FACTOR					
AMPERAGE	600	1.73					
MAIN SERVICE SIZE (DE-RATED TO 80%)							
NOTES:							
1. ELECTRICAL LOAD CALCULATION IS BASE	O ON THE CALCULATION F	PROCEDURES	S FOR MININ	UMCIRCU	IT AMPACITY OF THE		
SERVICE, AS OUTLINED IN THE ONTARIO E	ECTRICAL SAFETY CODE	SECTION 8.	SERVICE AN		RS		

LIGHT	IXTURE SCHEDULE								
UNIT	DESCRIPTION	NOM.	LAMP	COLOUR	WATTS	MEAN	VOLTAGE	ACCEPTABLE PRODUCT	N
		DIM'N		TEMP		LUMENS			
		(in)		(K)					
F1	LED	W - 3.2	LED	4000	24	3000	120	BJTAKE	DIMMABLE
	LINEAR STRIP FIXTURE	L - 32						#BLSP	
		(NOM 4FT)						STANPRO	
								OR APPROVED EQUAL	
F24	LED	W - 24	LED	4000	36	4000	120	BJ TAKE #BLR	DIMMABLE
	RECESSED	L - 48						STANPRO	FLANGE FOR DRY
								OR APPROVED EQUAL	

LIGH	TING CONTROL SCHEDULE			
UNIT	DESCRIPTION	ELECTRICAL	ACCEPTABLE PRODUCT	NOTES
	WALL SWITCH	120V	LEVITON	PASSIVE INFRARED (PIR) AND ULTRASONIC (U
	MOTION SENSOR		#OSSMT-MAW	
	WALL SWITCH	120V	LEVITON #AW	
	MOTION SENSOR AND DIMMER		SENSOR SWITCH #WSX-D	
			OR APPROVED EQUAL	
	MOTION SENSOR		LEVITON	PASSIVE INFRARED (PIR) AND ULTRASONIC (U
	CEILING MOUNTED		#OSC05-M0W (500 SF)	24 VDC
			#OSC10-M0W (1,000 SF)	INFRARED SENSITIVITY, ULTRASONIC SENSITIV
			#OSC20-M0W (2,000 SF)	TIME DELAY CONTROL
				POWER PACK AS REQUIRED

EXIT &	EMERGENCY LIGHT	FIXTURE S	CHEDULE			
UNIT	DESCRIPTION	LAMP	HOUSING	VOLTAGE	ACCEPTABLE PRODUCT	NOTES
E1	EXIT LIGHT	LED	ALUMINUM	120VAC	EMERGI-LITE #EA	EXTRUDED ALUMINUM HOUSING
	SINGLE FACE		WHITE	12 VDC	STANPRO	AND FACE PLATE
	SELF-POWERED					GREEN PICTOGRAM
						DIRECTION ARROW (WHERE REQUIRED)
					OR APPROVED EQUAL	END OR CEILING MOUNTED
E2	EXIT AND EMERGENCY	2x6W	ALUMINUM	120VAC IN	EMERGI-LITE #EAC	LONG LIFE SEALED LEAD
	LIGHT COMBINATION	LED	WHITE	12VDC OUT	STANPRO	LED EXIT
	UNIT BATTERY PACK					PUSH TO TEST SWITCH
	2 LAMPHEADS					AC "ON" PILOT LIGHT
	SELF-POWERED					GREEN PICTOGRAM EXIT SIGN
					OR APPROVED EQUAL	DIRECTION ARROW (WHERE REQUIRED)
EL1	EMERGENCY LIGHT	2x6W	OFF-WHITE	120VAC IN	EMERGI-LITE #ESL	LONG LIFE SEALED LEAD
	BATTERY PACK WITH	LED	STEEL	12VDC OUT	STANPRO	AC LINE CORD
	WITH 2 LAMPHEADS					PUSH TO TEST SWITCH
					OR APPROVED EQUAL	AC "ON" PILOT LIGHT
EL2	EMERGENCY LIGHT	2x6W	OFF-WHITE	12VDC	EMERGI-LITE #EF9D	
	DOUBLE REMOTE HEAD	LED			STANPRO	
					OR APPROVED EQUAL	
EL3	EMERGENCY LIGHT	1x6W	OFF-WHITE	12VDC	EMERGI-LITE #EF9	
	SINGLE REMOTE HEAD	LED			STANPRO	
					OR APPROVED EQUAL	

ELECTRIC HEATER SCHEDULE								
UNIT	DESCRIPTION	FAN	DIM'N	ELECTRICAL			ACCEPTABLE PRODUCT	NOTES
		CFM		WATTS	VOLT	PHASE		
EUH-1	FAN FORCED HEATER	160	16.75W	1125	208	1	DIMPLEX #RFI	WHITE
	COMMERCIAL GRADE		21.5H				STELPRO	CONTROL:
								- BUILT-IN TSTAT
							OR APPROVED EQUAL	RECESSED

1.00		(W) 3000
1.00		3000
1.00		52177
1.00		521/7
	(W)	109108
	(A)	105

NOTES

YWALL

I/S)

//S)

rivity and

3

Image: Image of the second
0 B.O'B. 2024 02 01 FOR REVIEW
No. By Date Revisions
All drawings, specifications and related documents are the copyright property of the Engineer and must be returned upon request. Reproduction of drawings, specifications, and related documents in part or whole is forbidden without the Engineers' written permission. The contractor must check and verify all dimensions on the job prior to start of construction. DRAWINGS ARE NOT TO BE SCALED
PROFESSIONAL FRANKER
ASTERN ASTERN NGINEERING GROUP INC. CONSULTING ENGINEERS Apex Building 207 - 100 Strowger Blvd. Brockville, Ont. K6V 5J9 Telephone: (613) 345-0400 Facsimile: (613) 345-0400 Facsimile: (613) 345-0400 Strowger Blvd. Brockville, Ont. K6V 5J9
Project Title: NORTH STORMONT MUNICIPAL OFFICE 57 COCKBURN STREET, BERWICK, ON
Drawing Title: ELECTRICAL SCHEDULES
Design: Checked: Approved: Project No.: 11200-M&E Drawn: Checked: Date: 2023 11 30 Contract No.: B.O'B. MM Date: 2023 11 30 Contract No.: Scale: 0 10'-0" 20'-0" Drawing No.: Drawing No.: Horizontal: 1/16" = 1'-0" 0 10'-0" 20'-0" EOOO2

SHOWN OFF CENTER FOR JUNCTION BOX CLARITY EXTERIOR DOME 103mm x103mm			
LIGHT SHOWN AS HIDDEN TO BE INSTALLED ON			
CENTER LINE OF DOOR	R :- STANLEY MA	AGIC-FORCE	
ROUTE CONDUIT IN CEILING SPACE TO			
B/F W/C STALL	STANCE		
	IE LIGHT		
In the event of an emergency button and intervent of an emergency button an emergency button and intervent of an emergency button and interven	ZER		
ACTIVATE ACT			
INTERIOR PUSH PLATE	ALL ABOVE BUTTO	ON IN BF W/C STAL	LL
	R OPERATION DE	VICES WITH	
ت السلم المحمد المحم المحمد المحمد المحم المحمد المحمد المحم المحمد ا	DOOR IS CLOSE TION.	D IN THE EVENT	
FLOOR LEVEL	Т.		
COORDINATE WITH DOOR HARDW.	ARE SUPPLIER		
NOTES:-			
 POWER SUPPLY TO BE MOUNTED IN THE CEILING. ALL WALL MOUNTED MATERIAL IS TO HAVE WIRING BROUGHT BACK TO THE POWER SUPPLY BOX 			
3. LOW VOLTAGE AND HIGH VOLTAGE WIRING ARE NOT TO BE RUN TOGETHER.			
4. ONE 15A CIRCUIT IS NEEDED FOR THE POWER SUPPLY BOX.			
5. BUTTON LOCATIONS ARE TO BE CENTERED 1100mm FROM FINISHED FLOOR LEVEL.			
 DOME LIGHT AND BUZZER ARE TO BE CENTERED 2500mm FROM FINISHED FLOOR LEVEL. PRIOR TO INSTALLATION CONFIRM LOCATIONS WITH OWNER. 			
8. DOME LIGHT STANDARD OF ACCEPTANCE:- DUKANE 18A524 (TWO LAMP) CORRIDOR LIGHT WITH ONE LAVATORY CALL LIGHT, FAST FLASHING RED ((60ppm) FOR USE	AS	
INSIDE AND OUTSIDE LIGHT, OR APPROVED EQUIVALENT. BUZZER STANDARD OF ACCEPTANCE:- MALLORY SONALERT SC628A C/W 103mm x130mm (4"x4") SURFACE MOUNT BACK BOX OR APPROVE EQUIVAL	ENT.		
POWER SUPPLY STANDARD OF ACCEPTANCE:- LAB-PS241F 12-24V DC / 1A POWER SUPPLY C/W BUILT IN GEL CELL BATTERY CHARGER, AUTOMATIC	SWITCHOVER TO	C	
TRANSFORMER STANDARD OF ACCEPTANCE:- TP4016 PLUG-IN TRANSFORMER 120/16V AC 40Va, OR APPROVED EQUIVALENT.			
9. BACKBOXES, CONDUITS AND 120V CIRCUIT BY ELECTRICIAN.			
EMERGENCY CALL ASSIST SYSTEM			
SCALE: NIS			
Г			
	Location:	ELECTRICAL RO	OOM
	Rated Amp:	600A	
	Manufacturer:	Square D I-Line	
	Cabinet:	Trim, Lockable D	Door
	TVSS:	-	
	Lo Watte	ad	
	walls	Description	
	51000	NEW	
	51000	NEW ELEC PNL	
	51000	NEW ELEC PNL P1	
	51000 51000 51 51	NEW ELEC PNL P1 I KW I KW	
	51000 51000 51 51 Location: Rated Amp:	NEW ELEC PNL P1 I NEW ELEC RM 200A	
	51000 51000 51 51 Location: Rated Amp: Voltage: Monufacturar:	NEW I NEW I P1 I P1 I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I	
	51000 51000 51000 51 51 Location: Rated Amp: Voltage: Manufacturer: Cabinet:	NEW 1 P1 1 P1	
	51000 51000 51 51 51 51 51 51 51 51 51 51 51 51 51	NEW 1 NEW 1 P1 1 P1 1 NEW 1 P1 1 NEW 1 P1 1 NEW 1 NEW 1 P1 1 NEW 1	Door
	51000 51000 51 51 Location: Rated Amp: Voltage: Manufacturer: Cabinet: TVSS: Lo	NEW 1 NEW 1 P1 1 P1 1 NEW 1 P1 1 NEW 1 P1 1 NEW 1 NEW 1 P1 1 NEW 1	Door
	51000 51000 51 51 51 51 51 51 51 51 51 51 51 51 51	NEW 1 NEW 1 P1 1 P1 1 P1 1 P1 1 NEW 1 P1 1 NEW 1 P1 1 NEW 1 NEW 1 P1 1 NEW 1 <t< td=""><td>Door</td></t<>	Door
	51000 51000 51 51 51 51 51 51 51 51 51 51 51 51 51	NEW 1 NEW 1 P1 <	Door
	51000 51000 51000 51 51 51 51 51 51 51 51 51 51 51 51 51	NEW 1 NEW 1 P1 1 P2 1 P2 1 P2 1 P2 <	
	51000 51000 51 51 51 51 51 51 51 51 51 51 51 51 51	NEW 1 NEW 1 P1 1 P2 1 P2 2 P2 2 P2 <	
	51000 51000 51000 51 51 51 51 51 51 51 51 51 51 51 51 51	NEW 1 NEW 1 P1 1 P2 1 P2 1 P2 1 P3 <	
	51000 51000 51000 51 51 51 51 51 51 51 51 51 51 51 51 51	NEW 1 P1 1 P2 1 P2 1 P2 1 P3 <t< td=""><td></td></t<>	
	51000 51000 51000 51 51 51 51 51 51 51 51 51 51 51 51 51	Description I NEW I P1 I P1 I P1 I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I </td <td></td>	
	51000 51000 51000 51 51 51 51 51 51 51 51 51 51 51 51 51	Description I NEW I P1 I P1 I P1 I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I </td <td></td>	
	51000 51000 51000 51 51 51 51 51 51 51 51 51 51 51 51 51	NEW 1 NEW 1 P1 1 P1<	
	51000 51000 51000 51 51 51 51 51 51 51 51 51 51 51 51 51	NEW 1 NEW 1 P1 1 P1<	
	51000 51000 51000 51 51 51 51 51 51 51 51 51 51 51 51 51	Decemption I NEW I ELEC PNL I P1 I P1 I I I KW I I I I I KW I I I KW I I I I I KW I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I	
	51000 51000 51000 51 51 51 51 51 51 51 51 51 51 51 51 51	NEW 1 NEW 1 ELEC PNL 1 P1 1 P1 1 NEW 1 P1 1 NE 1 NE 1 P1 1 NE 1 NE 1 P1 1 NE 1	
	51000 51000 51000 51 51 51 51 51 51 51 51 51 51 51 51 51	NEW 1 NEW 1 ELEC PNL 1 P1 1 P1 1 I 1 I 1 I 1 I 1 I 1 I 1 I 1 I 1 I 1 I 1 I 1 I 1 I 1 I 1 I 1 I 1 I 1 I 1 I 1 I 1 I 1 I 1 I 1 I 1 I 1 I 1 I 1 I 1 I 1 I 1 I 1 I 1 I 1 I 1 I 1 I 1 I 1 I 1 I 1 I 1	
	51000 51000 51000 51 51 51 51 51 51 51 51 51 51 51 51 51	Description I NEW I ELEC PNL I P1 I I I P1 I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I <td></td>	
	51000 51000 51000 51 51 51 51 51 51 51 51 51 51 51 51 51	DescriptionINEWIELEC PNLIP1IP1IIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIII <t< td=""><td></td></t<>	
	51000 51000 51 51 51 51 51 51 51 51 51 51 51 51 51	Description I NEW I ELEC PNL I P1 I P1 I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I I <td></td>	

		ELE	CTF	RICA		PANE	L 'F	2' (NEW)			Brockville , O	DRRIS eering Ltd. ntario 613-349-0555
Location:	LUNCH ROOM					Mountin	ng:	~ (
Rated Amp: Voltage:	200A 120/208V					Mains A Phase,	Amp: Wire:		200 A MAIN BREAKER 3PH, 4W				
Manufacturer: Cabinet:	Square D Trim, Lockable	Door				Bus: Breaker	s:		Aluminum Bolt-On				
TVSS:	- oad	Description		Break	er	Isolated	Grou Break	ind: (er	- Description	Lo	ad		
Watts 560	Description F1, 13F24	LIGHTS - 123, 124, 125, 126, 127	Am p	Pole	No.	No.	Pole	Am p	LIGHTS - 128 129 130 131	Description 12F24	Watts 480		
480	12F24	LIGHTS - 122, 122, 122, 122, 127	15	1	3	4	1	15	LIGHTS - 134,135,136,137	12F24	480		
480 400	12F24 F1,9F24	LIGHTS - 138,139,140,141,142 LIGHTS - 145,146,147,154,155	15 15	1	5 7	6 8	1	15 15	LIGHTS - 143,144,148 LIGHTS - 136,149,150,151,152,153	11F24 6F1,5F24	440 440		
800	20F24	LIGHTS - 156 SPARE	20 15	1	9 11	10 12	1	15	LIGHTS - 157,158	8F24	320		
1200	6REC	RECEP - 123,124	15	1	13	14	1	15	RECEP - 125,126	5REC	1000		
400	REC	RECEP - 128 RECEP - 128 COUNTER	15	1	15	18	1	15	RECEP - 129 RECEP - 130	5REC	1000		
800 600	4REC 3REC	RECEP - 131 RECEP - 132	15 15	1	19 21	20 22	1	15 15	RECEP - 133 PRINTER RECEP - 133 PRINTER	REC REC	600 600	1 B.O'B. 2024 03 19	FOR PERMIT & TENDER
600	3REC	RECEP - 132	15	1	23	24	1	15	RECEP - 133 PRINTER	REC	600	0 B.O'B. 2024 02 01	FOR REVIEW
400	2REC REC	RECEP - 134 RECEP - 134 COUNTER	15 15	1	25 27	26 28	1	15 15	RECEP - 133 PRINTER RECEP - 133	2REC	400 400	No. By Date	Revisions
800 800	4REC 4REC	RECEP - 135 RECEP - 137	15 15	1	29 31	30 32	1	15 15	RECEP - 136 RECEP - 138	4REC REC	800 200	All drawings, specifications a	nd related documents are the copyright property
800	4REC	RECEP - 139	15	1	33	34	1	15	RECEP - 138 PRINTER	REC	200	of the Engineer and must be specifications, and related do Engi	eturned upon request. Reproduction of drawings, ocuments in part or whole is forbidden without the neers' written permission.
800	4REC 4REC	RECEP - 140 RECEP - 141	15	1	35	30	1	15	RECEP - 138 PRINTER RECEP - 142	4REC	800	The contractor must chec	k and verify all dimensions on the job prior to start of construction.
800 400	4REC REC	RECEP - 143 RECEP - 143 COUNTER	15 15	1	39 41	40 42	1	15 15	RECEP - 144 RECEP - 144	3REC 3REC	600 600	DRAWIN	GS ARE NOT TO BE SCALED
600	3REC	RECEP - 148	15	1	43	44	1	15	RECEP - 149,150,151,152,153	5REC	1000		
400	3REC 3REC	RECEP - 148 COUNTER	15	1	45 47	40	1	15	RECEP - 145	4REC	800		O PROFESSION AL
400 500	3REC REC	RECEP - 148 COUNTER RECEP - 148 REFRIG	15 15	1	49 51	50 52	1	15 15	RECEP - 147,154 RECEP - 155	2REC 3REC	400 600		2024-3-19 Top
200	RH	RANGE HOOD	15	1	53	54	1	15	RECEP - 155	2REC	400		S M. A. MORRIS
0000	KEU		40	2	55 57	56 58	1	15	RECEP - UCKNIDOK	3REC 4REC	800		13 200
800	4REC 4REC	RECEP - 157	15 15	1	59 61	60 62	1	15 15	RECEP - 156 WALL RECEP - 156 FLOOR BOX	4REC 2REC	800 400		NCE OF ON
			+		63 65	64	1	15	RECEP - 156 FLOOR BOX	2REC	400		
			+	+	67	68	1					ASTE	RN
					69 71	70 72	1	15 15	WASHROOM - EMERG CALL WASHROOM - AUTO DOOR		200 200		
23.22	kW	CONNECTED LOA D							CONNECTED LOAD TOTAL CONNECTED LOAD	kW kW	18.76 41.98	COM	ISULTING ENGINEERS
												Apex Building 207 - 100 Strowger Blvd.	Telephone: (613) 345-0400 Facsimile: (613) 345-0008
1.0 DEVICES:		EL DEVICE QUANTITIES ARE APPROXIM	.EC	TRIC	CAL	PAN	EL	NO	TES			Brockville, Ont. K6V 5J9 Project Title: NORT MUN	WWW.EastEng.com
		DEVICES SHOWN ON FLOOR PLANS	3 <mark>SHA</mark> L	L SUF	ERSE	DE.						B	ERWICK, ON
2.0 IDENTIFICA	TION:			AME, A	MP, V	OLT, PHA	SE, V	I RE				Drawing Title:	
3.0 EQUIPMEN	IT SUPPLIED BY	TYPEWRITTEN CIRCUITING DIRECT OTHERS: ELECTRICAL CONTRACTOR SHALL FOR ALL EQUIPMENT SUPPLIED BY		ME FU RS	LL RE	SPONSIE	BILITY	FORS	ERMCING REQUIREMENTS			EL	LECTRICAL DETAILS
NOTATIONS:		ELECTRICAL CONTRACTOR SHALL ELECTRICAL CONTRACTOR SHALL V SHALL PROVIDE A NEW CIRCUITING FOR APPROVAL BY OWNER AND ENO THIS CIRCUITING STUDY SHALL INCL	COOR 'ERIFY LEGEN GINEER .UDE A	dinat and C d c, prio	E ALL Onfir R to F	EQUIPM M ALL CI PROCEEE CUITS.	ENT V RCUIT	MRING ING, A	WTH OTHER TRADES.			Design: Checked: MM MM Drawn: Checked: B.O'B. MM Scale: 0 10 ^{-0^s} Horizontal: 1/16 ^s = 1 ¹ -0 ^s	Approved: Project No.: 11200-M&E Date: 2023 11 30 Drawing No.: Project No.: Contract No.: Drawing No.:
WP TBD		WEATHERPROOF TO BE DETERMINED AND VERIFIED	WTH (OTHE	R TRAI	DES						0 10'-0" 2 Vertical: 1/16" = 1'-0"	

ELECTRICAL DISTRIBUTION PANEL 'DP1' (EXISTING)

			Мо	untin	g:		SURFACE						
				Ма	ins A	mp:		400 A MAIN BREAKER					
				Pha	ase, V	Wire:		1 PH, 3W					
				Bus	s:			Aluminum					
				Breakers:				Bolt-On					
				Iso	lated	Grour	nd:	_					
Description	Breaker			Breaker			er	Description	Load				
	Am p	Pole	No.		No.	Pole	Amp	-	Description	Watts			
			1		2	3	200	ELECTRICAL PNL P2	NEW				
			3		4				ELEC PNL				
			5		6				P2				
DISCONNECT BOILER	200	3	7		8	3	60						
CONNECT TO ELEC PNL P1			9		10								
			11		12								
DISCONNECT	40	3	13		14	3	200	ELECTRICAL PANEL					
GYM WEST HEAT			15		16			HP-2					
MARK SPARE			17		18								
DISCONNECT	40	3	19		20	3	125	ELECTRICAL PANEL					
GYM EAST HEAT			21		22			LP-2					
MARK SPARE			23		24								
ELECTRICAL PANEL	200	3	25		26	3	100	ELECTRICAL PANEL					
HP-1			27		28			LP-1					
			29		30								
CONNECTED LOAD								CONNECTED LOAD	kW	0			
								TOTAL CONNECTED LOAD	kW	51			

ELECTRICAL PANEL 'P1' (NEW)

					10 0 0 00									
				Mo	unting	g:		SURFACE						
				Ma	ins A	mp:		-						
				Ph	ase, N	Nire:		3PH, 4W						
				Bu	s:			Aluminum						
				Bre	eakers	s:		Bolt-On						
				Iso	lated	Groun	nd.	-						
Description	В	Breake	er		Breake		er	Description	Lo	ad				
•	Amp	Pole	No.		No.	Pole	Amp		Description	Watts				
RECEP - ROOF	15	1	1		2	1	15	RECEP - ROOF	3REC	600				
			3		4									
			5		6									
			7		8									
			9		10									
			11		12									
			13		14									
			15		16									
			17		18									
			19		20									
			21		22									
			23		24									
ROOFTOP HVAC UNIT	40	3	25		26									
			27		28									
			29		30									
ROOFTOP HVAC UNIT	40	3	31		32	3	40	ROOFTOP HVAC UNIT	RTU-4	10000				
			33		34									
			35		36									
ROOFTOP HVAC UNIT	40	3	37		38	3	40	ROOFTOP HVAC UNIT	RTU-5	10000				
			39		40									
			41		42									
CONNECTED LOAD								CONNECTED LOAD	kW	20.6				
								TOTAL CONNECTED LOAD	kW	51				

DEMOLITION NOTES – ELECTRICAL

ALL OUTLETS THAT WERE VISIBLE DURING SITE REVIEW HAVE BEEN INDICATED.

ALL OUTLETS IN FLOORS, WALLS & CEILINGS THAT ARE TO BE REMOVED SHALL BE DISCONNECTED & REMOVED, INCLUDING BOX CONDUIT & WIRING, BACK TO SOURCE.

COMMUNICATIONS SYSTEM:

- C1 RETAIN EXISTING SPEAKER
- C2 DISCONNECT AND REMOVE EXISTING SPEAKER OR SCHOOL BELL INCLUDING BOX, CONDUIT AND WIRING BACK TO SOURCE INFILL AND REPAIR WALL OR CEILING

D DATA AND TELEPHONE:

- D1 RETAIN EXISTING DATA OR TELEPHONE OUTLET
- D2 DISCONNECT AND REMOVE EXISTING ELECTRICAL DATA OR TELEPHONE OUTLET INCLUDING BOX, CONDUIT AND WIRING BACK TO SOURCE INFILL AND REPAIR WALL

F FIRE ALARM DEVICES:

- F1 RETAIN EXISTING FIRE ALARM DEVICE
- F2 DISCONNECT, REMOVE AND RELOCATE EXISTING FIRE ALARM DEVICE TO NEW WALL/CEILING
- F3 DISCONNECT AND REMOVE EXISTING FIRE ALARM DEVICE INCLUDING BOX, CONDUIT AND WIRING BACK TO SOURCE INFILL AND REPAIR WALL WHERE APPLICABLE

H ELECTRIC HEATER:

- H1 RETAIN EXISTING ELECTRIC HEATER
- H2 DISCONNECT, REMOVE AND REPLACE EXISTING ELECTRIC HEATER
- H3 DISCONNECT AND REMOVE EXISTING ELECTRIC HEATER INCLUDING BOX, CONDUIT AND WIRING BACK TO SOURCE INFILL AND REPAIR WALL WHERE APPLICABLE

L LIGHT FIXTURES & SWITCHES:

- L1 RETAIN EXISTING LIGHT FIXTURE
- L2 DISCONNECT, REMOVE AND REPLACE EXISTING LIGHT FIXTURE
- DISCONNECT AND REMOVE EXISTING LIGHT FIXTURE L3 INCLUDING BOX, CONDUIT AND WIRING BACK TO SOURCE
- RETAIN EXISTING LIGHT SWITCH LOCATION L4 SUPPLY AND INSTALL A NEW SWITCH AND COVER PLATE
- L5 DISCONNECT, REMOVE AND RELOCATE EXISTING LIGHT SWITCH ALTER BRANCH CIRCUIT WIRING AND SWITCHING TO SUIT OR AS SHOWN
- L6 DISCONNECT AND REMOVE EXISTING LIGHT SWITCH INCLUDING BOX, CONDUIT AND WIRING BACK TO SOURCE INFILL AND REPAIR WALL

R RECEPTACLES:

- R1 RETAIN EXISTING ELECTRICAL RECEPTACLE SUPPLY AND INSTALL NEW DUPLEX RECEPTACLE AND COVER PLATE
- R2 DISCONNECT, REMOVE AND RELOCATE EXISTING ELECTRICAL RECEPTACLE ALTER BRANCH CIRCUIT WIRING TO RETAIN SERVICE TO RELOCATED RECEPTACLE
- R3 DISCONNECT AND REMOVE EXISTING ELECTRICAL RECEPTACLE INCLUDING BOX, CONDUIT AND WIRING BACK TO SOURCE INFILL AND REPAIR WALL









ELECTRICAL - LIGHTING SCALE: $\frac{1}{8}$ = 1'-0"

· |

8	9						((
NEW RUALD	SS ROD(24 AT23 ADMINISTRATION DFF F24 F24	24 ADVINISTRATION	FFICE 2 1	F24 F24 FINANCE 0 F24	F24 F24 F24 F24 F24 F24 F24 F24 F24 F24	F24 /	F24	F24,	F24 F24 MIRKS FROM
5 MD		F24	F24	F24 F24 F24 F24	F24 F1NANCE T MD F1NANCE T MD F24 F24 F24 F24 F24	F24 F138 F1NANCE FLEY AFFA F24 / ME	F24 A142 F24 F24	F24	F24 F24 F24	IDM FI CORRIDO
		Fi24 / Fi	E24 F24	F24	A134 F24 3 C	F24 F24 F24 F24 F24 F24 F24 F24 F24 F24	F24 F24 F24 F24 F24 F24 F24	F24 F24 F24 F24 F24	F24 F24 F24 F24 F24	F3 F3 F3 F3 F3 F3 F3 F3 F3 F3
			F24	F24	F24 BUILDING DEPT.	F24 PEANNUM DE FFICE F24	RPT. DFF1	F24	F24	F3



TOWN TOWNSHIP

18 Required Horizontal Assemblies Li Name of Practice: ALEX WARWICK ARCHITECT FRR (Hours) or De Fire ALEX WARWICK Floors N/A Hours N/A - EXIS Resistance ALEX@WARWICKDESIGNSTUDIO.COM Rating N/A - EXIS Roof 3/4 Hours (416) 697-3008 (FRR) Mezzanine <u>N/A</u> Hours N/A - EXIS Name of Project: TOWNHALL RENOVATIONS FOR NORTH STORMONT Liste FRR of Supporting Des Members Floors N/A Hours N/A - EXIS Location: 57 COCKBURN ST., BERWICK ONTARIO Roof 3/4 Hours N/A - EXIS Mezzanine N/A Hours N/A - EXIS 19 Spatial Separation – Construction of Exterior Walls Item Building Code Reference Wall Area of L.D. L/H or Permitted Ontario Building Code Proposed % EBF (m²) (m) H/L Max. % of of Openings References are to Division B unless noted Data Matrix Parts 3 or 9 Openings [A] for Division A or [C] for Division C. North N/A - EXISTING TO REMAIN Part 9 X Part 11 Part 3 Project Description: New Addition 11.1 to 11.4 1.1.2. [A] 1.1.2. [A] & 9.10.1.3. N/A - EXISTING TO REMAIN igarsimes Change of Use igarsimes Alteration East West N/A - EXISTING TO REMAIN 2 Major Occupancy(s) ASSEMBLY (A2), BUSINESS (D) 3.1.2.1.(1) 9.10.2. 20 Plumbing Fixture Requirements 3 Building Area (m²) Existing <u>1365 SQ</u>. M. New <u>0 SQ. M</u>. Total <u>1365 SQ</u>. M. 1.4.1.2. [A] 1.4.1.2. [A] Existing <u>1365 SQ</u>. M. New <u>0 SQ. M</u>. Total <u>1365 SQ</u>. M. 1.4.1.2. [A] 1.4.1.2. [A] 4 Gross Area 5 Number of Storeys Above grade 1 Below grade 0 1.4.1.2. [A]&3.2.1.1 1.4.1.2[A] & 9.10.4 Male/Female Count @ <u>50</u>% / <u>50</u>%, Occupant 6 Number of Streets/Fire Fighter Access 1 - EXISTING TO REMAIN 3.2.2.10. & 3.2.5. 9.10.20. except as noted otherwise Load 7 Building Classification <u>3.2.2.25 GROUP A, DIVISION 2, UP TO 2 STOREYS</u> 3.2.2.20.-.83 9.10.2. Basement: Occupancy N/A 8 Sprinkler System Proposed entire building 3.2.2.20.-.83 9.10.8.2. Occupancy <u>N/A</u> selected compartments 3.2.1.5. 49 (DESIGN) 3 1st Floor: Occupancy DAYCARE (CHILDREN) 3.2.2.17. selected floor areas 14 (DESIGN) Occupancy DAYCARE (STAFF) \Box basement \Box in lieu of roof rating INDEX INDEX 18 (DESIGN) Occupancy OFFICE N/A EXISTING 🕅 not required 85 (DESIGN) Occupancy TOWNHALL N/A EXISTING 🛛 Yes 🗌 No 9 Standpipe required 3.2.9. N/A 10 Fire Alarm required 🛛 Yes 🛛 No 3.2.4. 9.10.18. 11 Water Service/Supply is Adequate N/A EXISTING 🗆 Yes 🗆 No 3.2.5.7. N/A 12 High Building 🗆 Yes 🛛 🕅 No 3.2.6. N/A (Adjust as Required for Additional Floors or Occupancies) Combustible 13 Construction Restrictions 9.10.6. 21 Other (describe) permitted required □ Non-combustible ⊠ Both Combustible Actual Construction 14 Mezzanine(s) Area m² N/A EXISTING 3.2.1.1.(3)-(8) 9.10.4.1. 15 (Occupant Load - Continued) 15 Occupant load based on m²/person
 X design of building 3.1.17. 9.9.1.3. Floor Occupancy _ Load___ Occupancy N/A Load _____ persons Basement: _Floor Load___ Occupancy _ 1 st Floor Occupancy <u>A2/D</u> Load <u>166</u> persons _Floor Load_ Occupancy _ Occupancy N/A Load persons 2nd Floor __Floor Load___ Occupancy ____ Occupancy N/A Load persons 3rd Floor Floor Load Occupancy _ (Additional floor areas continued on last page) Floor Load___ Occupancy _ ig|Yes \Box No (Explain). Load___ 16 Barrier-free Design 9.5.2. _Floor 38 Occupancy ____ _Floor Load___ Occupancy _ 17 Hazardous Substances □Yes 💢 No 3.3.1.2. & 3.3.1.19. 9.10.1.3.(4) _Floor Occupancy ____ Load___ _____ Floor Occupancy _ Load Building Code Data Matrix, Parts 3 or 9 December, 2013 Building Code Data Matrix, Parts 3 or 9 © Ontario Association of Architects © Ontario Association of Architects

HALL RENOVATION OF NORTH STORMON	١T			
		1. ISSUED FOR T NO. DESCRIPTION REVISIONS	ENDER/ PERMIT	2024.03.08 DATE
Attel Design No. 3.2.2.2.083.8c 9.10.8. String TO REMAIN 9.10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9. 10.9.<	8) 8) 80 AP DIPPENSER 90 ORDICK MODEL NO. 8-2111 (STANLESS STEEL) 90 ORAB BARS 90 DORICK SERIES ''' TYPE B-5195 99 WALL MOUNT SWIND DOWN TYPE B-4999/ BACK HORIZONTAL B-8906 91 ORAB FRASE 92 DORICK SERIES '''' TYPE B-5195 99 WALL MOUNT SWIND DOWN TYPE B-4999/ BACK HORIZONTAL B-8906 91 WAST RECEPTATELE 92 DORICK SERIES ''''''''''''''''''''''''''''''''''''	REVISIONS ALEX WAR Alex Warwick Alex WarwickDesigr (416) 697-3008 2118 Valley St. Moose PROJECT TOWN STORMON R THIS DRAWING, AS AN BY AND IS THE PROPER THE CONTRACTOR SHA FOR ALL DIMENSIONS NOTIFY ARCHITECT OF INFORMATION. ALEX WARWICK ARCH ACCURACY OF THE COI REFER TO APPROPRIAT ELECTRICAL, LANDSC BEFORE PROCEEDING N CONSTRUCTION MUST AND REQUIREMENTS O THE ARCHITECTURAI REPRESENTATION ONL' THIS DRAWING IS NOT	NSTRUMENT OF SERVICE TO FAULT OF AUTHORITIES HAVING JUF AUTHORITIES HAVING JUF CONFORM TO ALL APPLIC OF AUEX WARWICK ARCH AND CONDITIONS ON SITE AND CONDITIONS ON SITE CONFORM TO ALL APPLIC OF AUTHORITIES HAVING JUF L SYMBOLS ARE FO Y. TO BE SCALED.	TH TH N HALL IS PROVIDED HITECTS. ISPONSIBILITY E AND SHALL THE SUPPLIED BLE FOR THE MECHANICAL, T DRAWINGS CABLE CODES RISDICTION. DR GRAPHIC
Image: Construction of the construc	PENETRATING THAT HIGH CEILING MUST BE SMOKE SEALED AND FIRE STOPPED - PATCH AND REPAIR EXISTING 45MIN FIRE RATED HIGH CEILING AS REQUIRED TO COMPLETE NEW WORK WITH 2 LAYERS OF & TYPE X DRYWALL. COVER PAGE, OBC MATRIX, ARCHITECTURAL MATERIAL SPECIFICATIONS A000 SITE PLAN A001 NEW FLOOR PLAN AND DETAILS A100 ROOF PLAN - DEMO AND NEW WORK A101	-	The contractor shall check and verify all c all errors and ommisions to the archite professional whose seal is a fitted to this the drawings.	dimensions and report tect and the design drawing. Do not scale
POUTS I YRENE), I HERMALLY BROKEN C) HARDWARE SUPPLY AND INSTALL COMMERCIAL GRADE HARDWARE AS SPECIFIED. PROVIDE FIRE RATED DOOR/FRAME WHERE NOTED ON SCHEDULE COMPLETE WITH FIRE RATED TAGS AND RELATED FIRE RATED HARDWARE ALL ACOUSTIC LISTED DOORS TO HAVE ACOUSTIC SOUND STRIPPING AND HARDWARE TO STC 48 (MIN). Persons A) FRAMES - HOLLOW METAL - 16 GA. AS SHOWN ON SCHEDULES COMPLETE WITH ALL STANDARD COMPONENTS. EXTERIOR TO BE INSULATED, THERMALLY BROKEN. persons B) WINDOW - ALUMINUM RECEPTION WINDOW FRAMING COMPLETE WITH ALL STANDARD COMPONENTS AS SHOWN ON SCHEDULES AND AS REQUIRED TO EXECUTE WORK AS SHOWN. persons - ALUMINUM - ALUMINUM RECEPTION WINDOW FRAMING COMPLETE WITH ALL STANDARD COMPONENTS AS SHOWN ON SCHEDULES AND AS REQUIRED TO EXECUTE WORK AS SHOWN. Persons - ALUMINUM - SINGLE PANE TEMPERED GLASS FOR ALL EXTERIOR WINDOWS. LOW "E" AND ARGON GAS SHOWN ON SCHEDULES AND AS REQUIRED TO EXECUTE WORK AS SHOWN. persons - EXTERIOR - DOUBLE PANE INSULATED GLAZING UNIT TEMPERED GLASS FOR ALL EXTERIOR WINDOWS. LOW "E" AND ARGON GAS FILLED. UNITS TO PROVIDE A MAX U FACTOR OF 1.42 (AI) 0.25 (IP) persons 7) MILLWOOK TO BE COMPLETE DIMENSION ON EXECUTE DOUBLE PANE INSULATED GLAZING UNIT TEMPERED GLASS FOR ALL EXTERIOR WINDOWS. LOW "E" AND ARGON GAS	DEMO PLANSA200NEW FLOOR FINISH AND RCPA300CEILING DETAILSA301INTERIOR ELEVATIONSA500MILLWORK DETAILSA600	SHEET TITLE COVER PAC DRAWING L SPFCS/ OBI	This drawing shall not be used for constru- issued for construction by the design profe- affixed to this drawing and whose sign issued FOR CONSTRUCTION GE/ ARCHITEC IST/ MATERIAL C MATRIX	uction purposes until essional whose seal is gnature is below. DATE
persons A) ALL MILLWORK TO BE COMMERCIAL GRADE, PLYWOOD CORE. SEE MILLWORK DETAILS. persons B) ALL EXPOSED CABINET FINISH TO BE PRESSURE LAMINATE "BURNT STRANT" 6307 MATTE BY FORMICA persons C) ALL INTERIOR CABINET FINISH (INSIDE CABINETS) TO HAVE MELAMINE FINISH. persons D) ALL COUNTER-TOPS TO TO BE WHITE COLORCORE 2 LAMINATE MATTE 58 BY FORMICA. BEVEL ALL CHANGES IN SURFACE PLANE, FINISH ALL persons E) DOOR PULLS TO BE BRUSHED CHROME "D" TYPE persons E) DOOR PULLS TO BE BRUSHED CHROME "D" TYPE persons E) ADURATE GRADE, PLUL EXTENSION, SELF/ SOFT CLOSING persons G) ALL DRAWER GLIDES TO BE BALL BEARING TYPE, FULL EXTENSION, SELF/ SOFT CLOSING persons December, 2013	MILLWORK DETAILSA601DOOR AND FRAME SCHEDULEA700WINDOW AND ROOM FINISH SCHEDULEA701DIGITAL SAMPLE BOARDA702	- SHEET NO. - A000	DRAWN BY AW SCALE N.T.S	HECKED AW S.



				SOUTH BUILDING			
8 £9'-10 1/8"	9	:32'-1 7/8"		±32'-1 7/8"	11	±32'-0 1/8"	
A126 VEW HOOF ACCESS ROOM	A129 ADMINISTRATION OFFICE 1 C.H.8'0 A301 1 YH A128 A301 1 YH A128 A301 1 YH A128 A301 1 YH A128 A301 1 YH A128 A301 1 YH A128 A301 1 YH A128 A301 1 YH A128 A301 A128 A301 A128 A301 A128 A301 A128 A301 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128 A128	A130 ADMINISTRATION OFFICE 2	A140 FINANCE OFFICE 2 C.H. 8-0 FINANCE OFFICE 1 FINANCE OFFICE 1 C.H. 8-0 FINANCE OFFICE 1	A141 FINANCE OFFICE 3	A146 FINANCE OFFICE 6 C.H.8-0	A156 PUELIC WORKS OFFICE C.H.8-0"	
A123 CORRIDOR D' CH 8-0' A301 2 A124 NEW VESTBULE C.H. 8-0'	SUPPLY AND INSTALL NEW STRAPPING AND 2 LAYERS OF TYPE XDRWAAL TO ALL HIGH CEILING AREAS IMPACTED BY NEW STRUCTURAL WORK - PATOETTO) EXISTING FIRE RATED CEILING RECEPTION AREA C.H.8-0*	A127 CORRIDOR [C.H.B-O] A133 PRINTER ROOM [C.H.B-O] A133 I I I I I I I I I I I I I I I I I I I	PROVIDE 2 LAYERS X DRYWALL ON NE BLOCKING AS RED AROUND ALL SIDE OPENING FROM NE CURB TO EXISTING RATED HIGH CELLIN MAINTAIN FIRE SEF FIRE STOP AND SM ALL PRIMERATION CLH 8-07	S OF IS TYPE WW000 LINED S OF NEW WR00F AdMINN FIRE IS OF NEW STARATION. IOKE SEAL S S INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT INTERPORT	PROVIDE 2 LAYERS OF IT TYPE X DRYWALL ON NEW WOOD BLOCKING AS REQUIRED AROUND ALL SIDES OF NEW OPENING FROM NEW ROOF CURB TO EXISTING 45MIN FIRE RATED HIGH CELLING TO MAINTAIN FIRE SEPARATION. FIRE STOP AND SMOKE SEAL ALL PENETRATIONS. BY-LAW & FIRE FLEX AND OFFICE C.H.8:00 BY-LAW & FIRE OFFICE 2 C.H.8:00 BY-LAW & FIRE OFFICE 2 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C.H.8:00 C		





	M007		
NEW CARPET SHOWN DOTTED NEW PLYWOOD SUBFLOOR ON WOOD FLOOR FRAMING NEW ³ / ₂ SOLID WHITE OAK RISER TRIM (ON ALL RISER SURFACES) ADHERED AND FINISH NAILED TO STUD BEHIND. FILL FINISH NAIL HOLES, SAND AND SEAL OAK RISER TRIM. 2" X 4" WOOD SLEEPERS, SEE STRUCTURAL CONTINUOUS 6 MIL POLY VAPOUR BARRIER (SHOWN DASHED) BETWEEN WOOD STUDS AND EVICTING COMCPECTS 1 AP			
ADDITIONAL BLOCKING AS REQUIRED CONCRETE SLAB		1. ISSUED FOR NO. DESCRIPTIO REVISIONS ALEX WAR Alex Warwick Alex@WarwickDesig (416) 697-3008 2118 Valley St. Mood PROJECT TOW STORMO	TENDER/ PERMIT 2024.03.08 N DATE DATE Image: Contract of the second se
		THIS DRAWING, AS AN BY AND IS THE PROPE THE CONTRACTOR SH FOR ALL DIMENSIONS NOTIFY ARCHITECT O INFORMATION. ALEX WARWICK ARC ACCURACY OF THE CO REFER TO APPROPRI ELECTRICAL, LANDS BEFORE PROCEEDING CONSTRUCTION MUS AND REQUIREMENTS THE ARCHITECTUR REPRESENTATION ON THIS DRAWING IS NOT	N INSTRUMENT OF SERVICE IS PROVIDED RTY OF ALEX WARWICK ARCHITECTS. IALL VERIFY AND ACCEPT RESPONSIBILITY S AND CONDITIONS ON SITE AND SHALL OF ANY VARIATIONS FROM THE SUPPLIED CHITECT IS NOT RESPONSIBLE FOR THE DNSULTANT INFORMATION. ATE SURVEY, STRUCTURAL, MECHANICAL, CAPE, ETC. CONSULTANT DRAWINGS S WITH THE WORK. T CONFORM TO ALL APPLICABLE CODES OF AUTHORITIES HAVING JURISDICTION. AL SYMBOLS ARE FOR GRAPHIC LY. TO BE SCALED.
		NORTH SHEET TITLE MILLWC SHEET NO.	Image: Strain
		A601	SCALE N.T.S.

											DOOR	SCHEDULE				DOOR SCHEDULE	GENERAL NOTES	
			D	OOR				FRAME	S			OBC REQ	UIREMENT		REMARKS	1. ALL DOORS INCLUDING FRAMES REQUIRING A FIRE PROTECT	ON RATING SHALL COMPLY WITH OBC SUBSECTION 3.1.8	
NO.	TYPE		SIZE	MATERIAI	FIRE	FINISH TY			FIRE FIN	ISH DOO	R WEATHER	- BARRIER FREE HARWARE (AUTOMATIC	DOOR CLOSER	DOOR STOP (CONFIRM	1	2. ALL FIRE RATED DOORS, INCLUDING DOORS WITH 0HR RATIN	G, TO BE SELF LATCHING AND SELF CLOSING DEVICES	 DOOR FRAMES INTENDED FOR DRYWAL FLOOR, PROVIDE BLOCKING/ ADDITION/
		WIDTH	HEIGHT 7' - 2 ¹ / ₂ "		RATING				ATING ' "		OLD STRIPPIN	DOOR OPERATOR AND PUSH BUTTONS)		LOCATION ON SITE)		3. ALL DOORS INCLUDING FRAMES REQUIRING A FIRE PROTECT	ON RATING SHALL BE LABELLED INDICATING FIRE RATING AND BE EQUIPPED WITH A	INSTALLATION OF CLOSURES
A101A	A	3' - 2"	(EXISTING)	HM	-	PI			- F		•	•	•	•	INSULATED, THERMALLY BROKEN. CARD READER, PANIC SET, LEVER HARDWARE	LISTED SELF CLOSING DEVICE, A LISTED POSITIVE LATCHING		
A101B	В	3' - 2"	7' - 0"	HM	-	PT 2		M	- F	т		•	•	•	PUSH PLATE / DOOR PULL - NON-LATCHING DOOR	4. DOORS WITH TEMPERATURE RISE RATINGS INDICATING THAT AFTER 1HR OF EXPOSURE [OBC TABLE 3.1.8.15] ARE TO BE PR	THE DOOR HAS A MAXIMUM TEMPERATURE RISE OF 250°C OVIDED IN DOORS TO EXIT STAIRS FROM PARKING GARAGE,	A) BE INSTALLED IN CONFORMAN
A110A	С	3' - 2"	7' - 0"	НМ	-	PT 3		м	- F	т		•	•	•	UNIVERSAL WASHROOM HARDWARE	DOORS LOCATED IN FIRE WALLS, AND DOORS THAT ARE LOCA	TED WITHIN MEASURE-N VESTIBULES	AND WINDOWS" AND B) WHERE REQUIRED TO HAVE A
A110B	С	3' - 2"	7' - 0"	НМ	20 MIN	PT 3		-IM 2	0 MIN F	т		•	•	•	UNIVERSAL WASHROOM HARDWARE	5. ALL FRAMES OF DOORS WITHIN FIRE SEPARATIONS SHALL BE	FIRE STOPPED AND SEALED WITH SAME RATING AS FIRE SEPARATION	CLASSIFICATIONS MARKS TO I
A112	C	2 X 3' - 2"	7' - 0"	НМ		PT 4		нм	- F	т			-			6. ALL FRAMES WITH EITHER POWER DOOR OPERATOR, OR CAR	D READER TO ALSO HAVE ELECTRIC STRIKE FOR PROPER USE. PROVIDE ALL	WHERE A DOOR IS INSTALLED SO THAT
ATTZ	C	2 × 3 - 2	7-0							-			•	•	CARD READER, FANIC SET, LEVER HARDWARE			DAMAGE [OBC 3.1.8.5 (3)]
A117	С	2' - 10"	7' - 0"	HM	0 HR	PI 3							•	•	LOCKSET, LEVER HARDWARE, 0 HR FIRE SEPARATION (SMOKE SEAL)	IF A DOOR SWING IS UNRESTRICTED [OBC 3.1.8.5 (3)]	O INTEGRITY OF A WALL OR FIRE SEPARATION	
A118	В	3' - 2"	7' - 0"	HM	-	PT 3		MH	- F	т				•	LEVER PASSAGE HARDWARE, ACOUSTIC SWEEP/ SOUND STRIPPING (ALL SIDES)	8. ALL DOORS IN AN ACCESS TO EXIT, MEANS OF EGRESS OR EX	IT SHALL COMPLY WITH OBC 3.4.6.10 TO 3.4.6.19 INCLUSIVE	
A123	С	2 X 3' - 2"	7' - 0"	НМ	20 MIN	PT 4		HM 2	0 MIN F	т			•	•	CARD READER, PANIC SET, LEVER HARDWARE	9. ALL DOORS THAT OPEN INTO A CORRIDOR OR OTHER FACILIT	Y PROVIDING ACCESS TO EXIT FROM A SUITE, OR ROOM NOT	
A124A	А	3' - 2" / 2'-8"	$7' - 1\frac{7}{8}"$	НМ	-	PT 5		нм	- F	т	•	•	•	•	INSULATED, THERMALLY BROKEN. CARD READER, PANIC SET, LEVER HARDWARE	10 ALL EXIT DOORS FROM STAIRS AT GRADE LEVEL TO BE PROV		
A124B	^	2 X 3' - 2"	(EXISTING)	нм		PT 4		HM	- F	т			•			11 ALL EXIT DOORS AT GRADE OTHER THAN FROM STAIRS SHAL		COORDINATE ALL DO
	~	220 2								- -		•	•	•		12. DOORS LOCATED WITHIN 2 METERS FROM EXTERIOR GRADE	TO CONFORM TO OBC 3.3.4.10. 9.7.5.2 & 9.7.5.3 "RESISTANCE	SHOP DRAWINGS PRI
A126	С	3' - 2"	7' - 0"	HM	-	PI 3		HM	- F				•	•	LOCKSET, LEVER HARDWARE	TO FORCED ENTRY". THIS INCLUDES SUITE ENTRANCE DOOR	S. DOORS TO HAVE DEADBOLT LOCK AND SOLID BLOCKING	
A129	D	3' - 2"	7' - 0"	HM	-	PT 3		M	- F	т				•	LOCKSET, LEVER HARDWARE, ACOUSTIC SWEEP/ SOUND STRIPPING (ALL SIDES)			CAULKI
A130	D	3' - 2"	7' - 0"	НМ	-	PT 3		м	- F	т				•	LOCKSET, LEVER HARDWARE, ACOUSTIC SWEEP/ SOUND STRIPPING (ALL SIDES)	14 ALL DOORS FOUIPPED WITH AN ELECTRIC STRIKE BEOLIIRED	FOR SECURITY SHALL COMPLY WITH OBC 3 3 1 12	
A131	D	3' - 2"	7' - 0"	НМ	-	PT 3		нм	- F	т				•	LOCKSET, LEVER HARDWARE, ACOUSTIC SWEEP/ SOUND STRIPPING (ALL SIDES)	15. ALL DOORS EQUIPPED WITH AN ELECTROMAGNETIC LOCK SH	ALL COMPLY WITH ARTICLE OBC 3.3.1.12 & 3.4.6.16	
A122A	<u> </u>	3' - 2"	7' - 0"	нм	20 MIN	PT 3		HM 2		т				•		16. ALL STEEL DOORS EQUIPPED W/AN ELECTROMAGNETIC LOCK	TO BE 18 GA. STEEL AND TACK WELD AND FILL EDGES	
ATSSA	C	5-2	7-0		20 10111				-	-			•	•	LOCKSET, LEVER HARDWARE, ACOUSTIC SWEEF, SOUND STRIFFING (ALL SIDES)	17. ALL EXTERIOR DOORS TO BE WEATHER STRIPPED AND TESTE	D TO RESIST OR ACCOMMODATE ALL	
A133B	С	3' - 2"	7' - 0"	HM	-	PT 3		М	- F	Т			•	•	LOCKSET, LEVER HARDWARE	ENVIRONMENTAL LOADS AND EFFECTS OF THESE LOADS DET	ERMINED ACCORDING TO SB-1 OF OBC.	ARIE A
A135	D	3' - 2"	7' - 0"	HM	-	PT 3		HM	- F	т				•	LOCKSET, LEVER HARDWARE, ACOUSTIC SWEEP/ SOUND STRIPPING (ALL SIDES)	18 ALL GLAZING WITHIN EXTERIOR DOORS TO BE DOUBLE GLAZE		
A136	D	3' - 2"	7' - 0"	НМ	-	PT 3		нм	- F	т				•	LOCKSET, LEVER HARDWARE, ACOUSTIC SWEEP/ SOUND STRIPPING (ALL SIDES)	 ALL GLASS IN DOORS AND SIDELITES TO BE MADE OF TEMPER TO CAN/CGSB-12.1-M, LATEST ADDITION [OBC 3.3.1.18] 	ED OR LAMINATED SAFETY GLASS CONFOMING	
A137	D	3' - 2"	7' - 0"	НМ	_	PT 3		нм	- F	т				•	LOCKSET, LEVER HARDWARE, ACOUSTIC SWEEP/ SOUND STRIPPING (ALL SIDES)	20. ALL THRESHOLDS IN A BARRIER-FREE PATH OF TRAVEL TO BE MAXIMUM 13MM IN HEIGHT c/w 1:2 BEVELED SLOPE [OBC 3.8.1.3]		
A129		3' - 2"	Ζ' – Ο"	нм	20 MIN	рт 🤅		-IM 2		т			•	•		21. ALL THRESHOLDS TO BE ALUMINUM UNLESS OTHERWISE NOTED		
A130	Г	5-2	7-0		20 10111					-			•	•		22. DOOR RELEASE HARDWARE TO BE INSTALLED NOT MORE THAN 1200MM ABOVE FINISH FLOOR AND NOT LESS THAN 865MM [OBC 3.3.1.12 (5)]		
A139	D	3' - 2"	7' - 0"	HM	-	PT 3		М	- F	Т				•	LOCKSET, LEVER HARDWARE, ACOUSTIC SWEEP/ SOUND STRIPPING (ALL SIDES)	23. ALL SINGLE USE PUBLIC WASHROOM/BATHROOM DOORS TO B	BE EQUIPPED WITH A PRIVACY LOCK	
A140	D	3' - 2"	7' - 0"	HM	-	PT 3		MH	- F	т				•	LOCKSET, LEVER HARDWARE, ACOUSTIC SWEEP/ SOUND STRIPPING (ALL SIDES)	24. EXCEPT FOR GLASS DOORS, ALL EXTERIOR DOORS TO HAVE	MIN THERMAL RESISTANCE OF RSI 0.7 (R4) AS PER OBC SB-10, CHAPTER 2, 1.1.1.2 (4)	-
A141	D	3' - 2"	7' - 0"	НМ	-	PT 3		нм	- F	т				•	LOCKSET, LEVER HARDWARE, ACOUSTIC SWEEP/ SOUND STRIPPING (ALL SIDES)	25. UNIVERSAL WASHROOM HARDWARE - PRIVACY LOCK/ LEVER INDICATOR ABOVE BOTH SIDES OF DOOR. DOOR LOCKED INDI	HARDWARE, PUSH TO LOCK, EMERGENCY CALL BUTTON SYSTEM / RELEASE/ CATOR	
A142	D	3' - 2"	7' - 0"	НМ	-	PT 3		нм	- F	т				•	LOCKSET, LEVER HARDWARE, ACOUSTIC SWEEP/ SOUND STRIPPING (ALL SIDES)			
A144		3' - 2"	7' - 0"	нм		PT 3		-M	- F	т						At	BREVIATIONS	
A144	D	5-2	7-0							-				•	LOCKSET, LEVER HARDWARE, ACOUSTIC SWEEF, SOUND STRIFFING (ALL SIDES)	ALUM= ALUMINUM	KP = KICK PLATE	EXISTING WALLS
A146	D	3' - 2"	7' - 0"	HM	-	PI 3		HM	- F					•	LOCKSET, LEVER HARDWARE, ACOUSTIC SWEEP/ SOUND STRIPPING (ALL SIDES)	BR = BUZZER RELEASE	LG = LAMINATED GLASS	_
A147	D	3' - 2"	7' - 0"	HM	-	PT 3		HM	- F	т				•	LOCKSET, LEVER HARDWARE, ACOUSTIC SWEEP/ SOUND STRIPPING (ALL SIDES)	CMP = COMPOSITE METAL PANEL	MDH = MAGNETIC DOOR HANDLE	-
A148	F	3' - 2"	7' - 0"	НМ	20 MIN	PT 3		HM 2	0 MIN F	т			•	•	LOCKSET, LEVER HARDWARE	CR = CARD READER (OVERIDE LATCH OR LOCK)	MH = MAGNETIC HOLD	-
A149	С	2 X 3' - 2"	7' - 0"	НМ	-	PT 4		нм	- F	т			•	•	CARD READER, PANIC SET, LEVER HARDWARE		ML = MAGNETIC LOCK	-
A150	E	3' - 2"	7' - 0"	нм	20 MIN	PT 4		-IM 2		т								-
A 100	- F	0 - 2	r - U							·		▼	–	–		FG = FIXED GLASS	(BIRD FRIENDLY) REFER ALSO TO ELEV.	
A151	С	3' - 0"	7' - 0"	HM	-	PI 3		NI	- F	1			•	•	LUCKSET, LEVER PRIVACY HARDWARE, ACOUSTIC SWEEP/ SOUND STRIPPING (ALL SIDES)	FLG = FIRE LITE GLASS	PG = PLATE GLASS	
A152	С	3' - 0"	7' - 0"	HM	-	PT 3		HM	- F	т			•	•	LOCKSET, LEVER PRIVACY HARDWARE, ACOUSTIC SWEEP/ SOUND STRIPPING (ALL SIDES)	FRG = FROSTED GLASS	PT = PRIME AND PAINT	
A153	С	3' - 0"	7' - 0"	HM	-	PT 3		MH	- F	т			•	•	LOCKSET, LEVER PRIVACY HARDWARE, ACOUSTIC SWEEP/ SOUND STRIPPING (ALL SIDES)	GWG = GEORGIAN WIRE GLASS	PS = PRESSED STEEL	1 " "
A154	С	3' - 0"	7' - 0"	НМ	-	PT 3		нм	- F	т			•	•	LOCKSET, LEVER PRIVACY HARDWARE, ACOUSTIC SWEEP/ SOUND STRIPPING (ALL SIDES)	HC = HOLLOW CORE	SC = SOLID CORE	
A155	<u> </u>	3' - 2"	7' - 0"	нм	20 MIN	PT 3		HM 2		т			•	•		HCP = HOLLOW CORE MOLDED PANEL	SCL = SOLID CORE WOOD - LAMINATE FINISH	
7100	_	0-2								·		▼	–	–	SITUEINSAL WASHINGOWINANE, ACCUSING SWEEP SOUND STRIPPING (ALL SIDES)	HCW = HOLLOW CORE WOOD	SCP = SOLID CORE MOLDED PANEL	
A156	F	3' - 2"	7' - 0"	HM	20 MIN	PI 3		-1M 2	U MIN F	1			•	•	LOCKSET, LEVER HARDWARE	HM = HOLLOW METAL	SCW = SOLID CORE WOOD	
A158	С	3' - 2"	7' - 0"	HM	-	PT 3		HM	- F	т			•	•	LOCKSET, LEVER HARDWARE	HMF = HOLLOW METAL FRAME	SG = SHEET GLASS	
A159	D	3' - 2"	7' - 0"	НМ	-	PT 3		HM	- F	т			•	•	LOCKSET, LEVER HARDWARE	HMI = HOLLOW METAL INSULATED	SS = STAINLESS STEEL	
A160A	А	2 X 3' - 2"	7' - 0 "	НМ	_	PT 4		нм	- F	т					PUSH PLATE / DOOR PULL - NON-LATCHING DOOR	HMP = HOLLOW METAL PANEL	ST = STAINED	
A160D		3'_ 0" / 0' 0"	7' - 1 ⁷ / ₈ "					-IM		т –	-		-	-			IG = TEMPERED GLASS	
A100B	A	5-2/2-8	(EXISTING)					IIVI	- F	•	•	•	•		INSULATED, THERMALLY DRUKEN. CARD READER, PANIC SET, LEVER HARDWARE			-
EX	EX	EX	EX	EX	EX	PT E	(EX	EX F	T EX	EX	EX	EX	•	EXISTING DOOR/ FRAME/ HARDWARE TO REMAIN - SAND, PATCH, PREPARE AND MAKE GOOD TO PRIME AND PAINT DOORS AND FRAMES			-
l										I					1			TYPICAL DOOR F



FRAME TYPE A INSULATED, THERMALLY **BROKEN HOLLOW METAL** SINGLE DOOR WITH INSULATED GLAZING UNITS







ī,

HOLLOW METAL SINGLE DOOR WITH NO GLAZING. FIRE RATED WHERE NOTED ON SCHEDULE





ī~





SEE SCHEDULE

HARDWARE AS SPECIFIED



FRAME TYPE E HOLLOW METAL SINGLE DOOR WITH NARROW GLAZING

2"

KP

20 MIN FIRE RATED HOLLOW METAL SINGLE DOOR WITH NARROW GEORGIAN WIRED GLAZING

2"

ALL DOORS AND FRAMES WITHIN ACOUSTIC INSULATED WALLS TO **BE ACOUSTIC HOLLOW METAL** DOORS AND FRAMES (STC 48 MIN) COMPLETE WITH ALL APPROPRIATE ACOUSTIC RATED HARDWARE





2 FRAME TYPE 4 HOLLOW METAL FOR DOUBLE DOOR

SEE SCHEDULE

2"

SEE SCHEDULE



FRAME TYPE 5 INSULATED, THERMALLY BROKEN HOLLOW METAL FOR DOUBLE DOORS WITH REMOVABLE MIDDLE MULLION

FIRE RATED FRAME WHERE SPECIFIED



FLO	OR	BA	ASE	NORT	HWALL	SOUTI	H WALL	WEST	WALL	EAST	WALL		CEILING		DEMADIZO
FERIAL	FINISH	MATERIAL	FINISH	HEIGHT	REWARKS										
/TER	-	EX/RB	-	EX	PT01	EX	PT01	EX	PT01	DW	PT01	ACT	-	8'-0"	
/TER	-	EX/RB	_	EX	PT01	EX	PT01	DW	PT01	EX	PT01	ACT	-	8'-0"	
		FX		FX	PT01	FX	PT01	FX	PT01	FX	PT01	ACT	_	8'-0"	
					DT04	EX	DT04	EX	DT04		DT04	A01	_	0.0"	
	-	EX	-	EX	P101	EX	P101	EX	P101	EX	P101	ACT	-	8'-0"	
	-	EX	-	EX	PT02	EX	PT01	EX	PT01	EX	PT01	ACT	-	8'-0"	
	-	EX	-	EX	PT01	EX	PT01	EX	PT01	EX	PT01	ACT	-	8'-0"	
/TER	-	EX/RB	-	EX	PT03	EX	PT01	EX	PT01	EX	PT01	ACT	-	8'-0"	
	-	EX	-	EX	PT01	EX	PT01	EX	PT01	EX	PT01	ACT	-	8'-0"	
	-	EX	-	EX	PT01	EX	PT01	EX	PT01	EX	PT01	ACT	-	8'-0"	
R	-	POR	_	DWW	PT01	DWW	PT01	DWW	PT01	DWW	PT04	DWW	-	8'-0"	
		EY/PB		EY	PT01		PT01	FY	PT01	EY	PT01	АСТ		8'_0"	
					DT04	EV.	DT04		DT04		DT04		-	0-0	
	-	EA	-	DW	PIUI	EX	PIUI	EX	PIUI	EX	PIUI	ACT	-	8-0	
	-	EX	-	EX	PT02	EX	PT01	EX	PT01	EX	PT01	DWW	-	8'-0"	
	-	EX	-	EX											
/ TER	-	EX/RB	-	EX	PT01	EX	PT05	EX	PT01	EX	PT01	DWW	-	8'-0"	
	-	EX	-	EX	PT01	EX	PT01	EX	PT01	EX	PT01	ACT	-	8'-0"	
/ TER	-	EX/RB	-	EX	PT01	EX	PT01	EX	PT01	EX	PT01	ACT	-	8'-0"	
	-	EX/ RB	_	DW	PT04	EX	PT01	EX	PT01	EX	PT01	ACT	-	8'-0"	
		EY/ PB		EY	PT04		PT01	EY	PT01	EY	PT01	ACT		8'_0"	
	-		-		1104	EV.	1101		1101		1101		-	5-0	
	-	EX	-	EX											
	-	EX	-	EX											
	-	EX	-	ACT	-	8'-0"									
	-	EX	-	ACT	-	8'-0"									
T/EX	-	RB	-	EX	PT01	DW	PT01	DW	PT01	EX	PT01	ACT	-	8'-0"	
T/EX	-	RB	-	EX	PT01	EX	PT01	EX	PT01	DW	PT01	ACT	-	8'-0"	
	-	RB	_	DW	PT02	EX	PT01	EX	PT01	DW	PT01	ACT	-	8'-0"	
		RB		FX	PT01	FX	PT01	DW	PT01	FX	PT01	ACT	_	8'-0"	
					DT01		DT01	EV	DT01		DT01			8' 0"	
-1/EX	-	RB	-		P101		P101	EX	PIUI	EX/DW	P101	ACT	-	8-0	
I/EX	-	RB	-	EX	PI01	DW	P101	EX	P101	DW	P102	ACT	-	8'-0"	
	-	RB	-	EX	PT01	DW	PT02	DW	PT01	EX	PT01	ACT	-	8'-0"	
	-	RB	-	DW	PT02	EX	PT01	DW	PT01	EX	PT01	ACT	-	8'-0"	
	-	RB	-	DW	PT02	EX	PT01	EX	PT01	DW	PT01	ACT	-	8'-0"	
T/EX	-	RB	-	EX/DW	PT01	DW	PT03	EX	PT01	DW	PT01	ACT	-	8'-0"	
T/EX	-	RB	-	DW	PT01	EX	PT01	EX	PT03	EX	PT01	ACT	-	8'-0"	
T/EX	-	RB	_	EX	PT01	DW	PT01	DW	PT04	EX	PT01	ACT	-	8'-0"	
		DD		EV	PT01		DT04	EV	DT01		DT01	ACT		9' O"	
	-		-		DTO	EV.	DT04		DT04	DW	DT04		-	0-0	
	-	RB	-	Dvv	P104	EX	P101	EX	P101	Dvv	P101	ACT	-	8'-0"	
	-	RB	-	DW	PT04	EX	PT01	DW	PT01	EX	PT01	ACT	-	8'-0"	
T/EX	-	RB	-	DW	PT01	DW	PT01	EX	PT01	DW	PT05	ACT	-	8'-0"	
T/EX	-	RB	-	EX	PT01	DW	PT05	EX	PT01	DW	PT01	ACT	-	8'-0"	
	-	RB	-	EX	PT01	DW	PT05	DW	PT01	EX	PT01	ACT	-	8'-0"	
	-	RB	-	DW	PT05	EX	PT01	DW	PT01	EX	PT01	ACT	-	8'-0"	
	-	RB	-	DW	PT05	EX	PT01	EX	PT01	DW	PT01	ACT	-	8'-0"	
	_	RB	_	FX	PT01	WU	PT01	DW	PT02	FX	PT01	ACT	_	8'-0"	
					DT02		DT01	EV	DT01		DT01			8' 0"	
T (C) (-		-		F1U2		FIUI		FIUI		F101		-	0-0	
T/EX	-	RB	-	EX	PT01	DW	PT01	EX	PT01	DW	PT05	ACT	-	8'-0"	
	-	RB	-	EX	PT01	DW	PT05	DW	PT01	EX	PT01	ACT	-	8'-0"	
	-	RB	-	DW	PT01	DW	PT05	DW/EX	PT01	DW	PT01	ACT	-	8'-0"	
T/EX	-	RB	-	DWW	PT01	DWW	PT01	EX	PT03	EX	PT01	ACT	-	8'-0"	
T/EX	-	RB	-	DW	PT01	EX	PT01	EX/DW	PT01	EX/DW	PT01	ACT	-	8'-0"	
R	-	PORB	-	DW	PT06	DW	PT01	DW	PT01	DW	PT01	DWW	-	8'-0"	
R	-	PORB		DWW	PT01	DWW	PT01	DWW	PT01	DWW	PT06	DWW	_	8'-0"	
. .	-				DTO4		DT04		DT04		DTOC			0' 0"	
r t	-	PUKB	-		P101		P101		P101		P106		-	o -U	
ĸ	-	PORB	-	DWW	PT01	DWW	PT01	DWW	PT01	DWW	PT06	DWW	-	8'-0"	
R	-	PORB	-	DWW	PT01	DWW	PT01	DWW	PT01	DWW	PT06	DWW	-	8'-0"	
R	-	PORB	-	DWW	PT01	DWW	PT01	DWW	PT01	DWW	PT06	DWW	-	8'-0"	
T/EX	-	RB	-	DW	PT05	EX	PT01	DW	PT01	EX	PT01	ACT	-	8'-0"	
т	-	RB	-	DW	PT01	DW	PT01	DW	PT01	DW	PT02	ACT	-	14'-0"	
	_	RB	-	EX	PT01	DW	PT01	EX	PT01	DW	PT01	ACT	_	14'-0"	
т		RR	_	DW	PT02	FX	PT01	FX	PT01	DW	PT01	ACT	_	- 14'-0"	
	-		-		DTo 1								-	U	
I/EX	-	KR	-	EX	P101	EX	P101	אט	P101	⊨X	P101	ACI	-	8 [.] -0"	

1. NO.	ISSUED FOR TE DESCRIPTION	ENDER/ PERMIT	2024.03.0 DATE
Alex Alex (416 2118	EX WARV Warwick @WarwickDesigns 697-3008 Valley St. Moose	NICK ARCH Studio.com Creek, ON.	TECT
Ç	TOWN STORMON ⁻ RE	SHIP OF NOR T - NEW TOW ENOVATION	TH N HALL
THIS BY AN THE (FOR NOTIF INFOF ALEX ACCL REFE ELEC	DRAWING, AS AN IN ID IS THE PROPERT CONTRACTOR SHALL ALL DIMENSIONS A TY ARCHITECT OF / RMATION. WARWICK ARCHIT JRACY OF THE CONS R TO APPROPRIATE TRICAL, LANDSCA	NSTRUMENT OF SERVICE Y OF ALEX WARWICK ARC L VERIFY AND ACCEPT RE IND CONDITIONS ON SIT ANY VARIATIONS FROM ECT IS NOT RESPONSI SULTANT INFORMATION. E SURVEY, STRUCTURAL, PE, ETC. CONSULTAN	E IS PROVIDE HITECTS. ESPONSIBILIT E AND SHAI THE SUPPLIE BLE FOR TH MECHANICA T DRAWING
BEFO CONS AND I THE REPR THIS	RE PROCEEDING WI STRUCTION MUST OF REQUIREMENTS OF ARCHITECTURAL SESENTATION ONLY. DRAWING IS NOT TO	ITH THE WORK. CONFORM TO ALL APPLI AUTHORITIES HAVING JUI SYMBOLS ARE FC D BE SCALED.	CABLE CODE RISDICTION. DR GRAPH
		ASS OF ARCHITEC ALEXANDER W. W. LICENCE 8226 HILITHING	CTS Z
NOR	тн	The contractor shall check and verify all all errors and ommisions to the archi professional whose seal is affixed to this the drawings. This drawing shall not be used for cons issued for construction by the design pro affixed to this drawing and whose s	dimensions and repo tect and the design drawing. Do not scal truction purposes unt fessional whose seal ignature is below.
NOR		The contractor shall check and verify all all errors and ommisions to the archi professional whose seal is affixed to this the drawings. This drawing shall not be used for cons issued for construction by the design pro affixed to this drawing and whose s	dimensions and repo tect and the design a drawing. Do not scal truction purposes unt fessional whose seal ignature is below.
SHE V F	TH TITLE VINDOV INISH S	The contractor shall check and verify all all errors and ommisions to the archi professional whose sell is affixed to this the drawings. This drawing shall not be used for cons issued for construction by the design pro affixed to this drawing and whose s ISSUED FOR CONSTRUCTION	dimensions and repo tect and the design drawing. Do not sca truction purposes unt fessional whose seal ignature is below. DAT
SHEI V F SHEI	TH TH ET TITLE VINDOV INISH S ET NO. 701	The contractor shall check and verify all all errors and ommisions to the archi professional whose seal is affixed to this the drawings. This drawing shall not be used for cons issued for construction by the design pro affixed to this drawing and whose s ISSUED FOR CONSTRUCTION	dimensions and repc tect and the design drawing. Do not sca truction purposes unit fessional whose seal ignature is below. DAT

PAINT



BUILDING MATERIAL FINISHES

RUBBER WALL BASE - FLAGSTONE R41FS BY ARMSTRONG FLOORING



CARPET TILE - 106951 CHARCOAL, OPEN AIR 408 BY INTERFACE



PORCELAIN FLOOR TILE AND BASE JET BLACK, MATTE, 12" X 24", REGAL SERIES, BY OLYMPIA TILE



LUNCHROOM CABINET FINISH - BURNT STRAND 6307 MATT BY FORMICA

ALL COUNTER-TOP - WHITE COLORCORE 2 LAMINATE MATT 58 BY FORMICA



WHITE OAK RISER AND RAILINGS





-					
1. ISSUED FOR TE NO. DESCRIPTION	NDER/ PERMIT	2024.03.08 DATE			
REVISIONS					
ALEX WARV Alex Warwick Alex@WarwickDesignS (416) 697-3008 2118 Valley St. Moose	VICK ARCHI itudio.com Creek, ON.	TECT			
PROJECT					
TOWNSHIP OF NORTH STORMONT - NEW TOWN HALL RENOVATION					
THIS DRAWING, AS AN IN BY AND IS THE PROPERT THE CONTRACTOR SHALI FOR ALL DIMENSIONS A NOTIFY ARCHITECT OF A INFORMATION.	ISTRUMENT OF SERVICE Y OF ALEX WARWICK ARC L VERIFY AND ACCEPT RE ND CONDITIONS ON SIT ANY VARIATIONS FROM 1	IS PROVIDED HITECTS. SPONSIBILITY E AND SHALL THE SUPPLIED			
ALEX WARWICK ARCHIT ACCURACY OF THE CONS	ECT IS NOT RESPONSI SULTANT INFORMATION.	BLE FOR THE			
REFER TO APPROPRIATE ELECTRICAL, LANDSCAI BEFORE PROCEEDING WI	E SURVEY, STRUCTURAL, PE, ETC. CONSULTAN TH THE WORK.	MECHANICAL, T DRAWINGS			
CONSTRUCTION MUST C AND REQUIREMENTS OF THE ARCHITECTURAL REPRESENTATION ONLY.	ONFORM TO ALL APPLIC AUTHORITIES HAVING JUI SYMBOLS ARE FC	CABLE CODES RISDICTION. DR GRAPHIC			
THIS DRAWING IS NOT TO	BE SCALED.				
	OF OF ARCHITEC ARCHITEC ALEXANDER W.W. LICENCE 8226 8226	CTS Z			
NORTH	The contractor shall check and verify all all errors and ommisions to the archi professional whose seal is affixed to this the drawings.	dimensions and report tect and the design drawing. Do not scale			
	This drawing shall not be used for const issued for construction by the design pro affixed to this drawing and whose s	truction purposes until fessional whose seal is ignature is below.			
	ISSUED FOR CONSTRUCTION	DATE			
SHEET TITLE MATE	RIAL FIN 30ARD	ISH			
SHEET NO.	DRAWN BY C	HECKED Δ\Λ/			
∧7∩ Ω					
	SCALE N.T.	S.			





FINAL Hazardous Building Materials Assessment

North Stormont Public School 57 Cockburn Street, Berwick, Ontario

Prepared for:

Upper Canada District School Board

225 Central Avenue West Brockville, Ontario, K6V 5X1

March 9, 2023

Pinchin File: 302783.058



March 9, 2023 Pinchin File: 302783.058 FINAL

Issued to: Issued on: Pinchin File: Issuing Office: Upper Canada District School Board March 9, 2023 302783.058 Kingston, ON

Author:

Jeffrey Atrill, M.Eng. Project Technologist 613.541.1013 jatrill@pinchin.com

Reviewer:

Sarah Young, C. Tech. Operations Manager 613.541.1013 syoung@pinchin.com



EXECUTIVE SUMMARY

Upper Canada District School Board (Client) retained Pinchin Ltd. (Pinchin) to conduct a hazardous building materials assessment at North Stormont Public School located at 57 Cockburn Street, Berwick, Ontario. Pinchin performed the assessment on July 28, 2022.

The objective of the assessment was to document the locations of specified hazardous building materials, evaluate their condition and develop corrective action plans as required for the purposes of long-term management. The results of this assessment can be used for construction, renovation, demolition or project tendering purposes conditional that additional intrusive investigations are completed and excluded materials are sampled prior to disturbance, if required.

SUMMARY OF FINDINGS

Asbestos:

- Hard brown window caulking
- All asbestos-containing materials were observed to be in good condition

Lead:

- Low levels of lead in paints is present as follows:
 - Beige on concrete block walls (Phase A)
- Lead within batteries of emergency lights and fire alarm control panels

<u>Silica</u>: Crystalline silica is present in concrete, mortar, masonry, ceramics, grout, drywall, terrazzo and ceiling tiles.

Mercury: Mercury vapour is present in lamp tubes.

Polychlorinated Biphenyls (PCBs): PCBs are not present.

Mould and Water Damage: Visible mould growth and water damage was not observed.



SUMMARY OF RECOMMENDATIONS

The following is a summary of significant recommendations; refer to the body of the report for detailed recommendations.

- 1. Assess and/or sample materials listed as excluded or as presumed prior to disturbance.
- 2. Prepare an Asbestos Management Program (AMP).
- 3. Perform a re-assessment of ACM on an annual basis.
- Perform a pre-construction assessment and remove all ACM prior to alteration or maintenance work if ACM may be disturbed by the work.
- 5. Recycle mercury-containing lamp tubes.
- 6. Follow appropriate safe work procedures when handling or disturbing asbestos, lead and silica.

This Executive Summary is subject to the same standard limitations as contained in the report and must be read in conjunction with the entire report.



3.2 Existing Reports

Pinchin previously prepared the following reports, which have been reviewed as part of this assessment:

• *"Hazardous Building Materials Assessment, North Stormont Public School, 57 Cockburn Street, Berwick, Ontario",* prepared by Pinchin Ltd. Dated October 13, 2011, File No. 70594.005.

4.0 FINDINGS

The following section summarizes the findings of the assessment and provides a general description of the hazardous materials identified and their locations. For details on approximate quantities, condition, friability, accessibility and locations of hazardous materials; refer to the Hazardous Material Summary Report and All Data Report in Appendix V and VI.

Any quantities listed in this report or data tables are estimated based on visual approximations only and are subject to variation.

4.1 Asbestos

4.1.1 Pipe Insulation

Horsehair insulation present on rain water leaders in the Central Corridor (Loc.3) does not contain asbestos (previous Pinchin samples S0004A-C).

Remaining pipes are either uninsulated or insulated with non-asbestos fibreglass.





Non-asbestos horsehair insulation.

Pipes insulated with non-asbestos fibreglass.

4.1.2 Duct Insulation and Mastic

Ducts are either uninsulated or insulated with non-asbestos fibreglass (foil-faced or canvas).



March 9, 2023 Pinchin File: 302783.058 FINAL

4.1.3 Mechanical Equipment Insulation

Mechanical equipment (e.g. furnace, hot water tank, fan unit) is either uninsulated or insulated with nonasbestos fibreglass.





Furnace insulated with non-asbestos fibreglass.

Hot water tank insulated with non-asbestos fibreglass.

4.1.4 Vermiculite

Destructive testing of concrete block walls to investigate for loose fill vermiculite was not conducted due to the current building use.

Loose fill vermiculite debris was not observed in the spaces/areas inspected.

4.1.5 Acoustic Ceiling Tiles

Acoustic ceiling tiles are present in the assessed area, as follows:

Size, Type, Pattern	Sample Locations	Sample Number	Asbestos Type
2'x4' lay-in, small pinholes, small fissures	Boiler Room (Loc.1)	Previous Pinchin samples S0001A-C	None Detected
2'x4' lay-in, small and medium pinoles	Classroom (Loc.4)	Previous Pinchin samples S0005A-C	None Detected

Ceiling tiles present throughout Building Phase B are presumed to be non-asbestos based on the age of the materials determined from the age of the building phase construction (1989). The tiles were manufactured after asbestos stopped being used in acoustic ceiling tiles.



March 9, 2023 Pinchin File: 302783.058 FINAL



Non-asbestos lay-in ceiling tiles with small pinholes, small fissures.



Non-asbestos lay-in ceiling tiles with small and medium pinholes.

4.1.6 Drywall Joint Compound

Drywall joint compound present on wall and ceiling finishes throughout Building Phase A (previous Pinchin samples S0003A-G) and Building Phase B (previous Pinchin samples S0010A-G) does not contain asbestos.

4.1.7 Vinyl Sheet Flooring

Vinyl sheet flooring is present as follows:

Pattern, Colour	Sample Locations	Sample Number	Asbestos Type
Blue and white specks	Maintenance (Loc.10)	Previous Pinchin samples S0006A-C	None Detected
Grey squares	Maintenance (Loc.10)	Previous Pinchin samples S0007A-C	None Detected



Hazardous Building Materials Assessment North Stormont Public School, 57 Cockburn Street, Berwick, Ontario Upper Canada District School Board March 9, 2023 Pinchin File: 302783.058 FINAL







Non-asbestos vinyl sheet flooring with grey squares.

4.1.8 Vinyl Floor Tiles, Baseboard, and Stair Flooring

Vinyl floor products are present as follows:

Size, Pattern, Colour	Sample Locations	Sample Number	Asbestos Type (tile)	Asbestos Type (mastic)
12"x12" large white and beige streaks	Custodial Room (Loc.2)	Previous Pinchin samples S0002A-C	None Detected	None Detected
12"x12" large white and beige streaks (Abated Material)	Central Corridor (Loc.17)	Previous Pinchin samples S0008A-C	None Detected	None Detected
12"x12" large white and grey streaks	Storage Room (Loc.18) Gym (Loc.23)	Previous Pinchin samples S0009A-C and sample S0009D	None Detected	None Detected
12"x12" blue and light blue with fleck	Not sampled	N/A	None*	None*
12"x12" grey and beige with fleck	Not sampled	N/A	None*	None*

*Vinyl floor tiles were presumed to be non-asbestos based on historical knowledge of the date of installation (after 1992) based on information provided by the Client.

Mastic present under non-asbestos vinyl floor tiles installed after 1992 does not contain asbestos (samples S0016A-C).



Hazardous Building Materials Assessment

North Stormont Public School, 57 Cockburn Street, Berwick, Ontario Upper Canada District School Board March 9, 2023 Pinchin File: 302783.058 FINAL



Non-asbestos vinyl floor tiles with large white and beige streaks.



Non-asbestos vinyl floor tiles with large white and grey streaks.



Non-asbestos blue and light blue vinyl floor tiles with fleck.

4.1.9 Sealants, Caulking, and Putty



Non-asbestos grey and beige vinyl floor tiles with fleck.

The following table presents a summary of caulking, sealants and putties present:

Material and Colour	Application	Sample Locations	Sample Number	Asbestos Type
Caulking, light brown	Exterior window and door frames and expansion joints (Phase A)	Exterior – Phase A (Loc.100)	S0011A-C	None Detected
Caulking, brown	Exterior window frames and expansion joints (Phase B)	Exterior – Phase B (Loc.101)	S0012A-C	None Detected
Caulking, light grey	Exterior window frames (Phase B)	Exterior – Phase B (Loc.101)	S0013A-C	None Detected



North Stormont Public School, 57 Cockburn Street, Berwick, Ontario Upper Canada District School Board

Material and Colour	Application	Sample Locations	Sample Number	Asbestos Type
Caulking, hard brown	Interior window frames (Phase A)	Classroom (Loc.4) Classroom (Loc.7) Classroom (Loc.8)	S0015A-C	Chrysotile
Butyl sealant, black	Interior window liner (Phase A)	Vestibule (Loc.33)	S0017A-C	None Detected
Caulking, dark brown	Interior window frames (Phase B)	Classroom (Loc.21) Classroom (Loc.25) Classroom (Loc.26)	S0018A-C	None Detected
Caulking, silicone	Interior door frames	Not sampled	N/A	None*
Butyl sealant, rubber	Exterior window liners	Not sampled	N/A	None*

*Presumed to be non-asbestos based on the composition of the material (e.g. rubber, silicone).



Non-asbestos light brown caulking.



Non-asbestos brown caulking.



Non-asbestos light grey caulking.



Asbestos-containing hard brown caulking.



Hazardous Building Materials Assessment North Stormont Public School, 57 Cockburn Street, Berwick, Ontario Upper Canada District School Board March 9, 2023 Pinchin File: 302783.058 FINAL



Non-asbestos black butyl sealant.

Non-asbestos dark brown caulking.

4.1.10 Other Building Materials

Paint present on concrete block walls throughout Building Phase A does not contain asbestos (samples S0014A-G).

Paint present on concrete block walls throughout Building Phase B is presumed to be non-asbestos based on the age of the materials determined from the age of the building phase construction (1989).

4.1.11 Excluded Asbestos Materials

The following is a list of materials which may contain asbestos and was excluded from the assessment. These materials are presumed to contain asbestos until otherwise proven by sampling and analysis:

- Roofing felts and tar, mastics
- Ceramic tile setting compound
- Electrical components
- Vermiculite
- Baseboard adhesives
- Adhesives and duct mastics
- Fire resistant doors
- Terrazzo
- Sealants on pipe threads
- Firestopping sealants
- Materials concealed or outside the assessed area



4.2 Lead

4.2.1 Paints and Surface Coatings

The following table summarizes the analytical results of paints sampled:

Sample Number	Colour, Substrate Description	Sample Location	Lead (%)
L0001	Beige, concrete block walls (Phase A)	Classroom (Loc.4) Classroom (Loc.7) Kitchen (Loc.14)	0.0529
L0002	Beige, drywall (Phase A)	Classroom (Loc.4) Classroom (Loc.8) Staff Room (Loc.13)	0.0031
L0003	Pink, drywall (Phase A)	Administration (Loc.16)	0.0020
L0004	Beige, drywall (Phase B)	Gym Storage (Loc.22) Classroom (Loc.24) Classroom (Loc.26)	0.0015
L0005	Beige, concrete block walls (Phase B)	Storage Room (Loc.18) Gym (Loc. 23)	0.0059

Results less than or equal to 0.1% (1,000 mg/kg), but equal to or greater than 0.009% (90 mg/kg), are considered low-level lead paints or surface coatings in accordance with the EACC guideline.

Paints containing less than 0.009% (90 mg/kg) lead is assumed to be insignificant.

4.2.2 Lead Products and Applications

Lead-containing batteries are present in emergency lighting and fire control panels.



Lead-containing batteries in emergency lighting.



Lead-containing batteries in fire alarm control panel.



4.2.3 Excluded Lead Materials

Lead may be present in a number of materials which were not assessed and/or sampled. The following materials, where found, should be considered to contain lead:

- Electrical components, including wiring connectors, grounding conductors, and solder
- Solder on pipe connections
- Glazing on ceramic tiles

4.3 Silica

Crystalline silica is a presumed component of the following materials:

- Poured or pre-cast concrete
- Masonry and mortar
- Ceramic tiles and grout
- Drywall
- Terrazzo
- Ceiling tiles

4.4 Mercury

4.4.1 Lamps

Mercury vapour is present in fluorescent lamp tubes.

4.4.2 Mercury-Containing Devices

Thermostats inspected did not contain liquid mercury ampules.



Non-mercury digital thermostat.



4.5 Polychlorinated Biphenyls

4.5.1 Caulking and Sealants

The following table presents a summary of caulking sampled:

Material, Colour	Sample Location (Location #)	Sample Number	PCB concentration mg/kg
Various caulking and butyl sealants	Windows and door frames, window liners and expansion joints (Loc.4, Loc.33 and Loc.100)	P0001	<5
Caulking, silicone	Interior door frames	N/A	None*
Butyl sealant, rubber	Exterior window liners	N/A	None*

*Presumed to be a non-PCB solid based on the composition of the material (e.g. rubber, silicone).

Caulking in the table above is considered a non-PCB solid based on the threshold (50 mg/kg).

PCBs were banned in 1980; however, are found to be present in caulking and sealants until 1985. Caulking and sealants present in Building Phase B were installed after 1989 and is not suspected to contain PCBs.

4.5.2 Lighting Ballasts

Based on visual observations (evidence of T-8 fixtures) Building Phase A has been comprehensively relamped and will not contain PCB ballasts.

Based on date of construction (1989) and confirmed by visual observations (evidence of T-8 fixtures) Building Phase B will not contain PCB ballasts.

4.5.3 Transformers

All transformers in the building are dry type transformers and do not contain PCB-containing dielectric fluids; however, may contain capacitors, which could not be assessed for PCBs as the equipment was in service.